

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT				1. CONTRACT ID CODE	PAGE OF PAGES 1 218
2. AMENDMENT/MODIFICATION NO. 0004		3. EFFECTIVE DATE 02 NOV 2020	4. REQUISITION/PURCHASE REQ. NO.	5. PROJECT NO. (If applicable)	
6. ISSUED BY CODE W912PL		7. ADMINISTERED BY (If other than Item 6) SEE ITEM 6		CODE	
U.S Army Corps of Engineers, Los Angeles Dist CESPL-CT-E, East Region Branch 915 Wilshire Blvd. Los Angeles, CA 90017					
8. NAME AND ADDRESS OF CONTRACTOR (No., street, county, State and ZIP Code)				(X)	9A. AMENDMENT OF SOLICITATION NO. W912PL-21-B-0002
				<input type="checkbox"/>	9B. DATED (SEE ITEM 11) 18 September 2020
				<input type="checkbox"/>	10A. MODIFICATION OF CONTRACT/ORDER NO.
				<input type="checkbox"/>	10B. DATED (SEE ITEM 13)
CODE		FACILITY CODE			

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers is extended, is not extended.

Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods:
 (a) By completing items 8 and 15, and returning 1 copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted;
 or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment your desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA (If required)

**13. THIS ITEM ONLY APPLIES TO MODIFICATION OF CONTRACTS/ORDERS.
IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.**

CHECK ONE	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.
<input type="checkbox"/>	
<input type="checkbox"/>	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).
<input type="checkbox"/>	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
<input type="checkbox"/>	D. OTHER (Specify type of modification and authority)

E. IMPORTANT: Contractor is not, is required to sign this document and return 1 copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)

FY18 GROUND TRANSPORT EQUIPMENT FACILITY, FORT HUACHUCA, AZ

BID DUE DATE HAS BEEN EXTENDED FROM 6 NOV 2020 TO MONDAY 9 NOV 2020 12PM (PDT).

SEE CONTINUATION PAGE FOR AMENDMENT 0004 SUMMARY OF CHANGES.

PLEASE BE ADVISED THAT DOD SAFE DROP-OFF CODES EXPIRE IN 14 DAYS. ALL BIDDERS MUST REQUEST A NEW CODE IF THEIR EXISTING CODE WILL EXPIRE BEFORE BID SUBMITTAL.

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print)		16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)	
15B. CONTRACTOR/OFFEROR		16B. UNITED STATES OF AMERICA	16C. DATE SIGNED
(Signature of person authorized to sign)		(Signature of Contracting Officer)	

GROUND TRANSPORTATION EQUIPMENT BUILDING (GTEB)

FORT HUACHUCA

AMENDMENT 0004

SUMMARY OF CHANGES

SPECIFICATIONS:

- 1) SF-1442
- 2) Replaced Table of Contents
- 3) Replaced submittal register on Section 01 33 00-SUBMITTAL PROCEDURE
- 3) Replaced entire Section 05 50 13 - MISCELLANEOUS METAL FABRICATIONS
- 4) Replaced entire Section 08 33 23 - OVERHEAD COILING DOORS
- 5) Replaced entire Section 08 71 00 - DOOR HARDWARE
- 6) Added Section 32 01 19.61 - SEALING OF JOINTS IN RIGID PAVEMENT
- 7) Added Section 32 13 13.06 - PORTLAND CEMENT CONCRETE PAVEMENT FOR ROADS AND SITE FACILITIES

DRAWINGS:

- 1) Added PCC Option (contractor can use Resin Modified Pavement or PCC Pavement) and revised Drawing B101 PAVEMENT PLAN BASE BID OVERALL and Drawing B101.OP PAVEMENT PLANS OVERALL-OPTIONS.
- 2) Revised drawing sheet M-602 - HVAC SCHEDULES.

APPENDICES:

- 1) Added to APPENDIX 1, Hazardous Materials Test Results for Bldg 68048.
- 2) Added APPENDIX 3 PCASE DETAILS FOR PCC PAVEMENT OPTION.

SOLICITATION, OFFER, AND AWARD <i>(Construction, Alteration, or Repair)</i>	1. SOLICITATION NUMBER	2. TYPE OF SOLICITATION	3. DATE ISSUED	PAGE OF PAGES
	W912PL21B0002	<input checked="" type="checkbox"/> SEALED BID (IFB) <input type="checkbox"/> NEGOTIATED (RFP)	18 SEP 2020	1 OF

IMPORTANT - The "offer" section on the reverse must be fully completed by the offeror.

4. CONTRACT NUMBER	5. REQUISITION/PURCHASE REQUEST NUMBER	6. PROJECT NUMBER
--------------------	--	-------------------

7. ISSUED BY USACE, Los Angeles District Contracting Division, West Region Branch 915 Wilshire Blvd Los Angeles, CA 90017	CODE	8. ADDRESS OFFER TO DoD Secure Access File Exchange (DoD Safe) at https://safe.apps.mil/ See Section 00 22 13, Special Instructions Pertaining to Submission of Electronic Bids
---	------	---

9. FOR INFORMATION CALL	A. NAME JIMMY L. BARTON	B. TELEPHONE NUMBER (Include area code) (NO COLLECT CALLS) 213.452.3251
-------------------------	----------------------------	--

SOLICITATION

NOTE: In sealed bid solicitations "offer" and "offeror" mean "bid" and "bidder".

10. THE GOVERNMENT REQUIRES PERFORMANCE OF THE WORK DESCRIBED IN THESE DOCUMENTS (Title, identifying number, date):
FY18 GROUND TRANSPORT EQUIPMENT FACILITY, FORT HUACHUCA, AZ

This a fully designed project (Design Bid Build). Construct a Ground Transport Equipment Building Complex. Project includes a vehicle maintenance shop (ground transport equipment building), organizational storage building, organizational vehicle parking, vehicle wash platform, vehicle loading dock, petroleum, oils and lubricants (POL) storage, and other hazardous waste/material storage. The vehicle maintenance facility will include mechanical and electrical rooms, telecommunications, HVAC, fire detection and sprinkler suppression systems, building information systems, intrusion detection system (IDS) installation, integrated energy, monitoring and control system (EMCS) connected to the base monitoring systems, and the installation of fire alarm systems. Supporting facilities will include connection to all utilities, lighting, paving, parking areas, sidewalks, curbs and gutters, rainwater harvesting systems, and signage. Heating and air conditioning will be provided by self-contained systems.

The estimated magnitude of project is between \$25,000,000 and \$100,000,000. This solicitation is UNRESTRICTED and all responsive and responsible parties are invited to submit a bid. The North American Industry Classification System (NAICS) code is 236220 Commercial and Institutional Building

BIDDERS PLEASE NOTE: "This project may be delayed, canceled or revised at any time prior to award."

11. The Contractor shall begin performance within 10 calendar days and complete it within * 00 73 00 calendar days after receiving award, notice to proceed. This performance period is mandatory, negotiable. (See *Section 00 73 00 .)

12A. THE CONTRACTOR MUST FURNISH ANY REQUIRED PERFORMANCE PAYMENT BONDS? (If "YES," indicate within how many calendar days after award in Item 12B.) <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO	12B. CALENDAR DAYS 10
--	--------------------------

13. ADDITIONAL SOLICITATION REQUIREMENTS:
- A. Sealed offers in original and 0 copies to perform the work required are due at the place specified in Item 8 by 12PM (hour) local time 09 NOV 2020 (date). ~~If this is a sealed bid solicitation, offers will be publicly opened at that time. Sealed envelopes containing offers shall be marked to show the offeror's name and address, the solicitation number, and the date and time offers are due.~~
 - B. An offer guarantee is, is not required.
 - C. All offers are subject to the (1) work requirements, and (2) other provisions and clauses incorporated in the solicitation in full text or by reference.
 - D. Offers providing less than 120 calendar days for Government acceptance after the date offers are due will not be considered and will be rejected.

OFFER (Must be fully completed by offeror)

14. NAME AND ADDRESS OF OFFEROR (Include ZIP Code)		15. TELEPHONE NUMBER (Include area code) () - ; FAX () -	
DUNS NO. : TAX ID NO. : CAGE CODE NO. :		16. REMITTANCE ADDRESS (Include only if different than Item 14)	
CODE	FACILITY CODE		

17. The offeror agrees to perform the work required at the prices specified below in strict accordance with the terms of this solicitation, if this offer is accepted by the Government in writing within _____ calendar days after the date offers are due. (Insert any number equal or greater than the minimum requirement stated in 13D. Failure to insert any number means the offeror accepts the minimum in Item 13D.)

AMOUNTS 

18. The offeror agrees to furnish any required performance and payment bonds.

19. ACKNOWLEDGEMENT OF AMENDMENTS
(The offeror acknowledges receipt of amendments to the solicitation - give number and date of each)


AMENDMENT NO.										
DATE										

20A. NAME AND TITLE OF PERSON AUTHORIZED TO SIGN OFFER (Type or print)	20B. SIGNATURE	20C. OFFER DATE
--	----------------	-----------------

AWARD (To be completed by Government)

21. ITEMS ACCEPTED

22. AMOUNT	23. ACCOUNTING AND APPROPRIATION DATA
------------	---------------------------------------

24. SUBMIT INVOICES TO ADDRESS SHOWN IN  ITEM (4 copies unless otherwise specified)	25. OTHER THAN FULL AND OPEN COMPETITION PURSUANT TO <input type="checkbox"/> 10 U.S.C. 2304(c) () <input type="checkbox"/> 41 U.S.C. 253(c) ()
---	--

26. ADMINISTERED BY CODE	27. PAYMENT WILL BE MADE BY USACE, Finance Center ATTN: CEFCO-AO-D 5722 Integrity Drive Millington, TN 38054-5005
---	---

CONTRACTING OFFICER WILL COMPLETE ITEM 28 OR 29 AS APPLICABLE

<input type="checkbox"/> 28. NEGOTIATED AGREEMENT (Contractor is required to sign this document and return _____ copies to the issuing office.) Contractor agrees to furnish and deliver all items or perform all work requirements identified on this form and any continuation sheets for the consideration stated in this contract. The rights and obligations of the parties to this contract shall be governed by (a) this contract award, (b) the solicitation, and (c) the clauses, representations, certifications, and specifications incorporated by reference in or attached to this contract.	<input type="checkbox"/> 29. AWARD. (Contractor is not required to sign this document.) Your offer on this solicitation is hereby accepted as to the items listed. This award consummates the contract, which consists of (a) the Government solicitation and your offer, and (b) this contract award. No further contractual document is necessary.
---	--

30A. NAME AND TITLE OF CONTRACTOR OR PERSON AUTHORIZED TO SIGN (Type or print)	31A. NAME OF CONTRACTING OFFICER (Type or print)
30B. SIGNATURE	31B. UNITED STATES OF AMERICA BY
30C. DATE	31C. AWARD DATE

PROJECT TABLE OF CONTENTS**DIVISION 01 - GENERAL REQUIREMENTS**

01 00 00	GENERAL REQUIREMENTS
01 32 01	PROJECT SCHEDULE
01 33 00	SUBMITTAL PROCEDURES
01 33 29	SUSTAINABILITY REPORTING
01 35 26	GOVERNMENTAL SAFETY REQUIREMENTS
01 42 00	SOURCES FOR REFERENCE PUBLICATIONS
01 45 00	QUALITY CONTROL
01 45 00.15	RESIDENT MANAGEMENT SYSTEM CONTRACTOR MODE (RMS CM)
01 45 35	SPECIAL INSPECTIONS
01 50 00	TEMPORARY CONSTRUCTION FACILITIES AND CONTROLS
01 57 20	ENVIRONMENTAL PROTECTION
01 57 23	TEMPORARY STORMWATER POLLUTION CONTROL (ARIZONA)
01 74 19	CONSTRUCTION AND DEMOLITION WASTE MANAGEMENT
01 78 00	CLOSEOUT SUBMITTALS
01 78 23	OPERATION AND MAINTENANCE DATA
01 91 00.15	TOTAL BUILDING COMMISSIONING

DIVISION 02 - EXISTING CONDITIONS

02 41 00	DEMOLITION
02 82 13	ASBESTOS ABATEMENT
02 83 13	LEAD IN CONSTRUCTION
02 84 16	HANDLING OF LIGHTING BALLASTS AND LAMPS CONTAINING PCBs AND MERCURY

DIVISION 03 - CONCRETE

03 11 13	STRUCTURAL CAST-IN-PLACE CONCRETE FORMING
03 15 00	CONCRETE ACCESSORIES
03 20 00	CONCRETE REINFORCING
03 30 00	CAST-IN-PLACE CONCRETE
03 35 00	CONCRETE FINISHING
03 39 00	CONCRETE CURING
03 42 13	PLANT-PRECAST CONCRETE PRODUCTS FOR BELOW GRADE CONSTRUCTION

DIVISION 04 - MASONRY

04 20 00	UNIT MASONRY
----------	--------------

DIVISION 05 - METALS

05 05 23.16	STRUCTURAL WELDING
05 12 00	STRUCTURAL STEEL
05 21 00	STEEL JOIST FRAMING
05 30 00	STEEL DECKS
05 40 00	COLD-FORMED METAL FRAMING
05 50 13	MISCELLANEOUS METAL FABRICATIONS
05 51 00	METAL STAIRS
05 51 33	METAL LADDERS
05 52 00	METAL RAILINGS

DIVISION 06 - WOOD, PLASTICS, AND COMPOSITES

06 10 00	ROUGH CARPENTRY
----------	-----------------

06 20 00 FINISH CARPENTRY
 06 41 10 COUNTERS AND CASEWORK
 06 61 16 SOLID SURFACING FABRICATIONS

DIVISION 07 - THERMAL AND MOISTURE PROTECTION

07 05 23 PRESSURE TESTING AN AIR BARRIER SYSTEM FOR AIR TIGHTNESS
 07 13 53 ELASTOMERIC SHEET WATERPROOFING
 07 21 13 BOARD AND BLOCK INSULATION
 07 21 16 MINERAL FIBER BLANKET INSULATION
 07 22 00 ROOF AND DECK INSULATION
 07 27 10 BUILDING AIR BARRIER SYSTEM
 07 27 19.01 SELF-ADHERING AIR BARRIERS
 07 27 26 FLUID-APPLIED MEMBRANE AIR BARRIERS
 07 41 13 METAL ROOF PANELS
 07 41 16 METAL SOFFIT PANELS
 07 60 00 FLASHING AND SHEET METAL
 07 84 00 FIRESTOPPING
 07 92 00 JOINT SEALANTS

DIVISION 08 - OPENINGS

08 11 13 STEEL DOORS AND FRAMES
 08 33 23 OVERHEAD COILING DOORS
 08 34 59 VAULT DOORS
 08 51 13 ALUMINUM WINDOWS
 08 60 45 SKYLIGHTS AND TRANSLUCENT PANELS
 08 71 00 DOOR HARDWARE
 08 81 00 GLAZING
 08 91 00 METAL WALL AND DOOR LOUVERS

DIVISION 09 - FINISHES

09 22 00 SUPPORTS FOR GYPSUM BOARD
 09 29 00 GYPSUM BOARD
 09 30 10 CERAMIC, QUARRY, AND GLASS TILING
 09 51 00 ACOUSTICAL CEILINGS
 09 65 00 RESILIENT FLOORING
 09 67 23 RESINOUS FLOORING
 09 68 00 CARPETING
 09 84 20 ACOUSTICAL WALL PANELS
 09 90 00 PAINTS AND COATINGS

DIVISION 10 - SPECIALTIES

10 11 00 VISUAL DISPLAY UNITS
 10 21 13 TOILET COMPARTMENTS
 10 26 13 CORNER GUARDS
 10 28 13 TOILET ACCESSORIES
 10 51 13 METAL LOCKERS
 10 56 13 STEEL SHELVING

DIVISION 12 - FURNISHINGS

12 24 13 ROLLER WINDOW SHADES
 12 48 13 ENTRANCE FLOOR MATS AND FRAMES

DIVISION 13 - SPECIAL CONSTRUCTION

13 34 19 METAL BUILDING SYSTEMS
 13 48 00 SEISMIC PROTECTION FOR MISCELLANEOUS EQUIPMENT
 13 48 00.10 SEISMIC PROTECTION FOR MECHANICAL EQUIPMENT
 13 48 56 ALUMINUM PEDESTRIAN BRIDGE

DIVISION 21 - FIRE SUPPRESSION

21 13 13 WET PIPE SPRINKLER SYSTEM, FIRE PROTECTION

DIVISION 22 - PLUMBING

22 00 00 PLUMBING, GENERAL PURPOSE
 22 31 00 WATER SOFTENERS, CATION-EXCHANGE (SODIUM CYCLE)

DIVISION 23 - HEATING, VENTILATING, AND AIR CONDITIONING (HVAC)

23 00 00 AIR SUPPLY, DISTRIBUTION, VENTILATION, AND EXHAUST SYSTEMS
 23 05 15 COMMON PIPING FOR HVAC
 23 05 93 TESTING, ADJUSTING, AND BALANCING FOR HVAC
 23 07 00 THERMAL INSULATION FOR MECHANICAL SYSTEMS
 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC
 23 09 13 INSTRUMENTATION AND CONTROL DEVICES FOR HVAC
 23 09 23.01 LONWORKS DIRECT DIGITAL CONTROL FOR HVAC AND OTHER
 BUILDING CONTROL SYSTEMS
 23 11 25 FACILITY GAS PIPING
 23 21 23 HYDRONIC PUMPS
 23 23 00 REFRIGERANT PIPING
 23 25 00 CHEMICAL TREATMENT OF WATER FOR MECHANICAL SYSTEMS
 23 35 00 OVERHEAD VEHICLE TAILPIPE EXHAUST REMOVAL SYSTEM(S)
 23 52 00 HEATING BOILERS
 23 54 16 HEATING SYSTEM; GAS-FIRED HEATERS
 23 64 10 WATER CHILLERS, VAPOR COMPRESSION TYPE
 23 64 26 CHILLED WATER PIPING SYSTEMS
 23 82 02 UNITARY HEATING AND COOLING EQUIPMENT

DIVISION 25 - INTEGRATED AUTOMATION

25 05 11 CYBERSECURITY FOR FACILITY-RELATED CONTROL SYSTEMS
 25 08 10 BUILDING LEVEL DDC TESTING

DIVISION 26 - ELECTRICAL

26 00 00 BASIC ELECTRICAL MATERIALS AND METHODS
 26 05 48 SEISMIC PROTECTION FOR ELECTRICAL EQUIPMENT
 26 08 00 APPARATUS INSPECTION AND TESTING
 26 20 00 INTERIOR DISTRIBUTION SYSTEM
 26 27 13.10 ELECTRIC METERS
 26 28 01 COORDINATED POWER SYSTEM PROTECTION
 26 29 23 VARIABLE FREQUENCY DRIVE SYSTEMS UNDER 600 VOLTS
 26 31 00 SOLAR PHOTOVOLTAIC (PV) COMPONENTS
 26 41 00 LIGHTNING PROTECTION SYSTEM
 26 42 14 CATHODIC PROTECTION SYSTEM (SACRIFICIAL ANODE)
 26 51 00 INTERIOR LIGHTING
 26 56 00 EXTERIOR LIGHTING

DIVISION 27 - COMMUNICATIONS

27 05 14.00 10 CABLE TELEVISION PREMISES DISTRIBUTION SYSTEM
 27 05 28.36 CABLE TRAYS FOR COMMUNICATIONS SYSTEMS

27 10 00 BUILDING TELECOMMUNICATIONS CABLING SYSTEM
 27 13 23 COMMUNICATIONS OPTICAL BACKBONE CABLING
 27 51 16 RADIO AND PUBLIC ADDRESS SYSTEMS

DIVISION 28 - ELECTRONIC SAFETY AND SECURITY

28 08 10 ELECTRONIC SECURITY SYSTEM ACCEPTANCE TESTING
 28 10 05 ELECTRONIC SECURITY SYSTEMS (ESS)
 28 31 49 CARBON MONOXIDE DETECTORS
 28 31 76 INTERIOR FIRE ALARM AND MASS NOTIFICATION SYSTEM

DIVISION 31 - EARTHWORK

31 00 00 EARTHWORK
 31 11 00 CLEARING AND GRUBBING

DIVISION 32 - EXTERIOR IMPROVEMENTS

32 01 19.61 SEALING OF JOINTS IN RIGID PAVEMENT
 32 11 20 SUBBASES FOR FLEXIBLE PAVING
 32 11 23 AGGREGATE BASE COURSES
 32 12 10 BITUMINOUS TACK COAT
 32 12 17 HOT MIX BITUMINOUS PAVEMENT
 32 12 18 RESIN MODIFIED PAVEMENT SURFACING MATERIAL
32 13 13.06 PORTLAND CEMENT CONCRETE PAVEMENT FOR ROADS AND SITE FACILITIES
 32 16 13 CONCRETE SIDEWALKS AND CURBS AND GUTTERS
 32 17 23 PAVEMENT MARKINGS
 32 31 13.53 HIGH-SECURITY CHAIN LINK FENCES AND GATES

DIVISION 33 - UTILITIES

33 08 55 COMMISSIONING OF FUEL FACILITY SYSTEMS
 33 11 00 WATER UTILITY DISTRIBUTION PIPING
 33 30 00 SANITARY SEWERS
 33 40 00 STORM DRAINAGE UTILITIES
 33 51 13 NATURAL-GAS METERING
 33 51 15 NATURAL-GAS DISTRIBUTION
 33 56 10 FACTORY-FABRICATED FUEL STORAGE TANKS
 33 58 00 LEAK DETECTION FOR FUELING SYSTEMS
 33 71 02 UNDERGROUND ELECTRICAL DISTRIBUTION
 33 82 00 TELECOMMUNICATIONS OUTSIDE PLANT (OSP)

DIVISION 41 - MATERIAL PROCESSING AND HANDLING EQUIPMENT

41 22 13.13 BRIDGE CRANES

APPENDICES -

APPENDIX 1 HAZARDOUS MATERIAL REPORTS
 APPENDIX 2 FORT HUACHUCA FIRE DEPARTMENT REQUIREMENTS
 APPENDIX 3 PCASE DETAILS FOR PCC PAVEMENT OPTION

-- End of Project Table of Contents --

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		01 32 01	SD-01 Preconstruction Submittals															
			Project Scheduler Qualifications	1.3	G													
			Bar Chart Schedule	3.5														
			Project Schedule	3.1	G													
			Preliminary Project Schedule	3.5.1	G													
			Initial Project Schedule	3.5.2	G													
			Data Optical Discs	3.6.1														
			Periodic Schedule Update	3.5.3	G													
			Periodic Schedule Update	3.7.2	G													
			Justification of Delay	3.9.1	G													
			Time Impact Analysis	3.9.3	G													
			Forensic Schedule Analysis	3.9.4	G													
			Schedule Status Report	3.1.1	G													
		01 33 00	SD-01 Preconstruction Submittals															
			Submittal Register	1.9	G													
			SD-02 Shop Drawings															
			Mechanical Room Layout Drawings	1.13														
		01 33 29	SD-01 Preconstruction Submittals															
			Preliminary High Performance and Sustainable Building Checklist	1.5.3.1	G DO													
			Sustainability Action Plan	1.4.1	G DO													
			Preliminary Sustainability eNotebook	1.5.3.1	G DO													
			SD-11 Closeout Submittals															

SUBMITTAL REGISTER

CONTRACT NO. _____

TITLE AND LOCATION
Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR _____

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		01 33 29	Final High Performance and Sustainable Building Checklist	1.5.3.1	G DO													
			Final Sustainability eNotebook	1.5.3.1	G DO													
			Amended Final Sustainability eNotebook	1.5.3.1	G DO													
			Amended Final High Performance and Sustainable Building Checklist	1.5.3.1	G DO													
			Third Party Certification Certificates or Validation	3.2	G DO													
		01 35 26	SD-01 Preconstruction Submittals															
			Accident Prevention Plan (APP)	1.6	G DO													
			Health Hazard Control Plan	1.6.2.14	G													
			Emergency Action Plan	1.6.2.15	G													
			Standard Lift Plan	1.6.2.2	G													
			Critical Lift Plan	1.6.2.3	G DO													
			Activity Hazard Analysis (AHA)	1.7														
			SD-06 Test Reports															
			Monthly Exposure Reports	1.11.3														
			Notifications and Reports	1.11														
			Accident Investigation Reports	1.11.2	G DO													
			LHE Inspection Reports	1.11.4														
			Regulatory Citations and Violations	1.11.6														
			SD-07 Certificates															
			Crane Operators/Riggers	1.5.1.4														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		01 35 26	Confined Space Entry Permit	1.8.1														
			Hot Work Permit	1.8.1														
			Certificate of Compliance	1.11.5														
			Excavation Permit	3.7														
			Proof of Current Qualification	1.5.1.4														
		01 45 00	SD-01 Preconstruction Submittals															
			Contractor Quality Control Plan	3.2	G													
			MTC validation	3.7.2.1	G													
			SD-06 Test Reports															
			Verification Statement	3.9.2														
		01 45 35	SD-01 Preconstruction Submittals															
			Written Practices	3.1.2														
			NDT Procedures and Equipment Calibration Records	3.1.2														
			SD-06 Test Reports															
			Daily Reports	3.1.2														
			Biweekly Reports	3.1.1														
			SD-07 Certificates															
			Fabrication Plant	2.1														
			Steel Truss Plant	2.1														
			Wood Truss Plant	2.1														
			AC472 Accreditation	2.1														
			Steel Joist Institute Membership	2.1														
			Certified Plant	2.1														
			Certificate of Compliance	2.1														
			Special Inspector	1.5	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		01 45 35	Qualification Records	3.1.2														
			SD-11 Closeout Submittals															
			Comprehensive Final Report	3.1.2	G													
		01 50 00	SD-01 Preconstruction Submittals															
			Construction Site Plan	1.3	G													
			Traffic Control Plan	3.1.10.1	G													
			Temporary Earthwork Plan	1.4	G													
			Dust Control Methods And Procedures	3.1.10.3	G													
			SD-06 Test Reports															
			Backflow Preventer Tests	2.4														
			SD-07 Certificates															
			Backflow Tester	1.7.1														
			Backflow Preventers	1.7														
			Backflow Prevention Training Certificate	1.7.2														
		01 57 20	SD-01 Preconstruction Submittals															
			Environmental Protection Plan	1.7	G DO													
		01 57 23	SD-01 Preconstruction Submittals															
			SWPPP	1.5.1	G DO													
			SWPPP	1.5.1	G DO													
			PRRs	1.5.2	G DO													
			PRRs	1.5.2	G DO													
			PRRs	1.5.2	G DO													
			SD-03 Product Data															
			BMP Product Data	1.5.1.3														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		01 57 23	BMP Product Data	3.1.1													
			BMP Product Data	3.1.1													
			BMP Product Data	3.1.1													
			Geotextiles And Mats	2.1.1.4	G DO												
			SD-06 Test Reports														
			SWPPP Amendment	3.1.1													
			SWPPP Amendment	3.2.1													
			SWPPP Amendment	3.2.1													
			SWPPP Amendment	3.2.1													
			SWPPP Amendment	3.2.1													
			SWPPP Amendment	3.2.1													
			SWPPP Amendment	3.2.1													
			Sampling Results	1.5.2													
			Sampling Results	3.2.4													
			Inspection Reports	3.2.2													
			Annual Report	1.5.2													
			Annual Report	3.1.2													
			Annual Report	3.1.2													
			SD-10 Operation and Maintenance Data														
			Post-Construction Stormwater Management Plan	3.1.2	G DO												
			Post-Construction Stormwater Management Plan	3.1.2	G DO												
			SD-11 Closeout Submittals														
			Final SWPPP	3.1.2	G DO												
			Final SWPPP	3.2.1	G DO												

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY					REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		MAILED TO CONTR/ DATE RCD FRM APPR AUTH	
																		(g)
		01 57 23	NOT Application	3.1.2	G DO													
			NOT Application	3.1.2	G DO													
			NOT Application	3.1.2	G DO													
		01 74 19	SD-01 Preconstruction Submittals															
			Waste Management Plan	1.6	G													
			SD-11 Closeout Submittals															
			Records	1.7														
		01 78 00	SD-03 Product Data															
			Warranty Management Plan	1.7.1														
			Warranty Tags	1.7.5														
			Spare Parts Data	1.5														
			SD-06 Test Reports															
			working as-built drawings	3.1.4	G													
			final as-built record drawings	3.2	G DO													
			SD-08 Manufacturer's Instructions															
			Instructions	1.7.1														
			SD-10 Operation and Maintenance Data															
			Operation and Maintenance Manuals	3.9														
			SD-11 Closeout Submittals															
			Record Drawings	1.3.4	G DO													
			Certification of EPA Designated Items	2.3	G													
			Interim DD FORM 1354	3.11	G													
			Checklist for DD FORM 1354	3.11	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION						CONTRACTOR											
Ground Transportation Equipment Building (GTEB), Fort Huachuca																	
ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE		
(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		01 78 00	Final Approved Shop Drawings	3.6	G												
			Construction Contract	3.7	G												
			Specifications														
			As-Built Record Of Equipment	3.8													
			And Materials														
		01 78 23	SD-10 Operation and Maintenance														
			Data														
			O&M Database	1.3	G												
			Training Plan	3.1.1	G												
			Training Outline	3.1.3	G												
			Training Content	3.1.2	G												
			SD-11 Closeout Submittals														
			Training Video Recording	3.1.4	G												
			Validation of Training Completion	3.1.6	G												
		01 91 00.15	SD-06 Test Reports														
			Design Review Report	3.1.4	G DO												
			Interim Construction Phase	3.1.3.1	G DO												
			Commissioning Plan														
			Final Construction Phase	3.1.3.2	G DO												
			Commissioning Plan														
			Template Building Envelope	3.1.3.1.2	G DO												
			Inspection Checklists														
			Building Envelope Inspection	3.1.6.2	G DO												
			Checklists														
			Pre-Functional Checklists	3.1.6.3	G DO												
			Issues Log	1.9													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		01 91 00.15	Commissioning Report	3.2	G DO												
			Post-Construction Trend Log Report	3.3.1	G DO												
			SD-07 Certificates														
			Certificate of Readiness	1.10	G DO												
			SD-10 Operation and Maintenance Data														
			Training Plan	3.1.7	G RO												
			Training Attendance Rosters	3.1.7	G RO												
			Systems Manual and Computerized Maintenance Management System Manual	3.1.8	G DO												
			Maintenance and Service Life Plans	3.1.9	G DO												
			SD-11 Closeout Submittals														
			Construction Phase Commissioning Plan	3.1.3.1	S DO												
			Final Commissioning Report	3.2	S DO												
		02 41 00	SD-01 Preconstruction Submittals														
			Demolition Plan	1.2.1	G												
			Existing Conditions	1.9													
			SD-07 Certificates														
			Notification	1.6	G												
			SD-11 Closeout Submittals														
			Receipts	3.3.4													
		02 82 13	SD-02 Shop Drawings														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		02 82 13	Detailed Drawings	1.3	G												
			SD-03 Product Data														
			Asbestos Waste Shipment Records	3.10.3.1	G												
			Encapsulants	2.1	G												
			Respiratory Protection Program	1.8.1	G DO												
			Cleanup and Disposal	3.10	G												
			Qualifications	1.5.1	G												
			Training Program	1.10													
			Licenses, Permits and Notifications	1.7.1													
			Asbestos Management Plan	3.10.3.2	G DO												
			SD-06 Test Reports														
			Exposure Assessment and Air Monitoring	3.8													
			Local Exhaust System	1.6.3													
			SD-07 Certificates														
			Local Exhaust System	1.6.3													
			Encapsulants	2.1	G												
			Medical Surveillance	1.8													
			Requirements														
		02 83 13	SD-01 Preconstruction Submittals														
			Lead Compliance Plan	1.5.2.2	G												
			Competent Person	1.5.1.1	G												
			Training Certification	1.5.1.2	G												
			Lead waste management plan	1.5.2.8	G												

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		02 83 13	Written evidence	3.5.2.1	G												
			Medical Examinations	1.5.2.4	G												
			SD-06 Test Reports														
			Sampling results	1.5.2.3	G												
			Occupational and Environmental Assessment Data Report	1.5.2.3	G												
			SD-07 Certificates														
			Testing laboratory	1.5.1.3													
			Clearance Certification	3.5.1.1													
			SD-11 Closeout Submittals														
			hazardous waste manifest	3.5.2.1													
			turn-in documents or weight tickets	3.5.2.1													
		02 84 16	SD-06 Test Reports														
			Testing Results	3.3.1	G												
			SD-07 Certificates														
			Qualifications of CIH	1.8.1													
			Training Certification	1.8.1													
			PCB and Lamp Removal Work Plan	1.8.2	G												
			PCB and Lamp Disposal Plan	1.8.3	G												
			Certification of Decontamination	3.2.4	G												
			SD-11 Closeout Submittals														
			Transporter certification	3.5.2	G												
			Certificate of Disposal and/or recycling	3.5.2.1													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION	
																		(g)
		02 84 16	DD Form 1348-1	3.5.3														
		03 11 13	SD-02 Shop Drawings															
			Formwork	2.2.1	G													
			Formwork	3.1.1	G													
			Form Removal Schedule	2.2.1	G													
			SD-03 Product Data															
			Form Materials	2.2														
			SD-04 Samples															
			Sample Panels	1.3	G													
			SD-05 Design Data															
			Calculations	2.1														
			SD-06 Test Reports															
			Inspection	3.2														
		03 15 00	SD-03 Product Data															
			Preformed Expansion Joint Filler	2.2														
			Sealant	2.3														
			SD-04 Samples															
			Lubricant for Preformed	2.3.2														
			Compression Seals															
			Field-Molded Type	2.3.3														
			SD-07 Certificates															
			Preformed Expansion Joint Filler	2.2														
			Sealant	2.3														
		03 20 00	SD-02 Shop Drawings															
			Reinforcement	3.1	G													
			SD-03 Product Data															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		03 20 00	Mechanical Butt-Splices	2.3.1													
			SD-07 Certificates														
			Reinforcing Steel	2.3													
			Qualified Welders	1.3.1													
			Qualification of Steel Bar	1.3.2													
			Butt-Splicers														
		03 30 00	SD-01 Preconstruction Submittals														
			Quality Control Plan	1.4.2	G												
			Laboratory Accreditation	1.4.1													
			Sampling Plan	3.9.5.4	G												
			SD-03 Product Data														
			Recycled Content Products	Part 2													
			Cementitious Materials	2.2													
			Vapor Barrier	2.11													
			Floor Finish	2.1.5													
			Floor Hardener	2.9													
			Chemical Admixtures	2.4													
			SD-04 Samples														
			Surface Retarder	2.4.5													
			SD-05 Design Data														
			Mixture Proportions	2.1.1	G												
			SD-06 Test Reports														
			Mixture Proportions	2.1.1	G												
			Testing and Inspection for CQC	3.9	G												
			Fly Ash	2.2.2													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		03 30 00	Ground Granulated Blast-Furnace (GGBF) Slag	2.2.3													
			Aggregates	2.3													
			Air Content	3.9.5.1													
			Slump	3.9.5.2													
			Compressive Strength	3.9.5.4													
			Water	2.5													
			SD-07 Certificates														
			Contractor Quality Control personnel	1.4													
			Ready-Mix Plant	3.2.1													
		03 35 00	SD-03 Product Data														
			Recycled Content Products	Part 2													
			SD-04 Samples														
			Field Test Panels	1.3.1													
			Sample Wall Panels	1.3.1.1													
			Slab Panels	1.3.1.2													
		03 39 00	SD-03 Product Data														
			Curing Materials	2.1													
			SD-06 Test Reports														
			Testing and Inspection for CQC	3.2													
			SD-08 Manufacturer's Instructions														
			Curing Compound	2.1													
		03 42 13	SD-01 Preconstruction Submittals														
			Quality Control Procedures	1.3.2.2													
			SD-02 Shop Drawings														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		03 42 13	Standard Precast Units	2.1.1	G													
			Custom-Made Precast Units	2.1.2	G													
			Special Finishes	3.2.4.3														
			SD-03 Product Data															
			Standard Precast Units	2.1.1														
			Proprietary Precast Units	2.1.3														
			Embedded Items	3.1.3														
			Accessories	2.2.4														
			SD-05 Design Data															
			Design Calculations	2.1.2	G													
			Concrete Mix Proportions	2.1.5.1														
			SD-06 Test Reports															
			Test Reports	1.3.2.4														
			SD-07 Certificates															
			Quality Control Procedures	1.3.2.2														
		04 20 00	SD-02 Shop Drawings															
			Cut CMU	3.3.2.1	G													
			Detail Drawings	3.4.1.1	G													
			SD-03 Product Data															
			Hot Weather Procedures	1.5.1	G													
			Cold Weather Procedures	1.5.2	G													
			Cement	2.2.2.2.1	G													
			Cementitious Materials	2.4.1.1	G													
			SD-04 Samples															
			Mock-Up Panel	1.3.1.1	G													
			Admixtures for Masonry Mortar	2.4.1.4	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		04 20 00	Anchors, Ties, and Bar Positioners	2.6.2	G													
			Joint Reinforcement	1.3.1.3	G													
			SD-05 Design Data															
			Masonry Compressive Strength	2.1.2	G													
			Fire-Rated Concrete Masonry Units	2.2.2.5														
			Bracing Calculations	3.2.5	G													
			SD-06 Test Reports															
			Field Testing of Mortar	3.6.1.1														
			Field Testing of Grout	3.6.1.2														
			Prism Tests	3.6.1.3														
			SD-07 Certificates															
			Special Masonry Inspector Qualifications	1.3.2														
			Cementitious Materials	2.4.1.1														
			Admixtures for Masonry Mortar	2.4.1.4														
			Admixtures for Grout	2.4.2.2														
			Anchors, Ties, and Bar Positioners	2.6.2														
			Joint Reinforcement	1.3.1.3														
			SD-08 Manufacturer's Instructions															
			Admixtures for Masonry Mortar	2.4.1.4														
			Admixtures for Grout	2.4.2.2														
			SD-10 Operation and Maintenance Data															

SUBMITTAL REGISTER

CONTRACT NO. _____

TITLE AND LOCATION
Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR _____

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		04 20 00	Take-Back Program	3.8														
		05 05 23.16	SD-01 Preconstruction Submittals															
			Welding Quality Assurance Plan	3.2	G													
			SD-03 Product Data															
			Welding Procedure Qualifications	1.3	G													
			Welder, Welding Operator, and Tacker Qualification	1.3.5														
			Inspector Qualification	1.3.6														
			Previous Qualifications	1.3.2														
			Pre-Qualified Procedures	1.3.3														
			Welding Electrodes and Rods	2.2														
			SD-06 Test Reports															
			Nondestructive Testing	3.3														
			SD-07 Certificates															
			Certified Welding Procedure Specifications (WPS)	1.3.1														
			Certified Brazing Procedure Specifications (BPS)	1.3.1														
			Certified Procedure Qualification Records (PQR)	1.3.1														
			Certified Welder Performance Qualifications (WPQ)	1.3.1														
			Certified Brazer Performance Qualifications (BPQ)	1.3.1														
		05 12 00	SD-01 Preconstruction Submittals															
			Erection Drawings	1.5.1.1	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		05 12 00	SD-02 Shop Drawings														
			Fabrication drawings	1.5.2	G												
			SD-03 Product Data														
			Shop primer	2.6.2													
			Welding electrodes and rods	2.4.1													
			Direct Tension Indicator Washers	2.3.2.3													
			Non-Shrink Grout	2.4.2													
			Tension control bolts	2.3.3													
			SD-06 Test Reports														
			Class B coating	2.6.2													
			Bolts	2.3.1.1													
			Bolts	2.3.2.1													
			Nuts	2.3.1.2													
			Nuts	2.3.2.2													
			Washers	2.3.1.3													
			Washers	2.3.2.4													
			Weld Inspection Reports	3.8.1.2													
			Direct Tension Indicator Washer	3.8.2.1													
			Inspection Reports														
			Bolt Testing Reports	3.8.3.1													
			Embrittlement Test Reports	3.8.4													
			SD-07 Certificates														
			Steel	2.2													
			Bolts	2.3.1.1													
			Bolts	2.3.2.1													
			Nuts	2.3.1.2													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		05 12 00	Nuts	2.3.2.2														
			Washers	2.3.1.3														
			Washers	2.3.2.4														
			Galvanizing	2.5														
			AISC Fabrication Plant Quality Certification	1.3														
			AISC Erector Quality Certification	1.3														
			Welding procedures and qualifications	1.5.3.1														
			Welding electrodes and rods	2.4.1														
		05 21 00	SD-01 Preconstruction Submittals															
			Welder Qualification	1.3.2														
			SD-02 Shop Drawings															
			Steel Joist Framing	1.3.1	G													
			SD-05 Design Data															
			Design Calculations	2.2	G													
			SD-06 Test Reports															
			Erection Inspection	3.4														
			Welding Inspections	3.4														
			SD-07 Certificates															
			Certification of Compliance	1.3.2														
			SD-11 Closeout Submittals															
			Recycled Content of Steel Products	2.3	S													
		05 30 00	SD-02 Shop Drawings															
			Fabrication Drawings	1.3.4	G RO													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		05 30 00	Roof Deck Units	2.3	G RO													
			Cant Strips	2.3.2.1	G RO													
			Ridge and Valley Plates	2.3.2.2	G RO													
			Metal Closure Strips	2.3.2.3	G RO													
			SD-03 Product Data															
			Accessories	2.2														
			Deck Units	2.3.1	G RO													
			Galvanizing Repair Paint	2.1.5														
			Joint Sealant Material	2.1.4														
			Roof Deck Units	2.3														
			Repair Paint	2.3.4														
			Welder Qualifications	1.3.2														
			Welding Equipment	1.3.2														
			Welding Rods and Accessories	1.3.2														
			SD-04 Samples															
			Roof Deck Units	2.3														
			Flexible Closure Strips	2.1.6														
			Flexible Closure Strips	2.3														
			Accessories	2.2														
			SD-05 Design Data															
			Deck Units	2.3.1	G RO													
			SD-07 Certificates															
			Welding Procedures	1.3.2														
			Fire Safety	1.3.3.1														
			Wind Storm Resistance	1.3.3.2														
		05 40 00	SD-02 Shop Drawings															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		05 40 00	Framing Components	1.6.1	G												
			SD-03 Product Data														
			Studs, Joists	2.1													
			SD-05 Design Data														
			Metal Framing Calculations	1.6.2	G												
			SD-07 Certificates														
			Load-Bearing Cold-Formed Metal Framing	1.4													
			Welds	3.2.1													
			SD-11 Closeout Submittals														
			Recycled Content of Steel Products	2.1	S												
		05 50 13	SD-02 Shop Drawings														
			Floor Gratings	2.4	G												
			Roof Walkways	2.4	G												
			Bollards/Pipe Guards	2.5	G												
			SD-03 Product Data														
			Floor Gratings	2.4	G												
			Roof Walkways	2.4	G												
			SD-07 Certificates														
			Certificates of Compliance	2.1	G												
			Certified Mill	2.2	G												
			SD-11 Closeout Submittals														
			Recycled Content	2.1	S												
		05 51 00	SD-02 Shop Drawings														
			Iron and Steel Hardware	2.1	G												

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		05 51 00	Steel Shapes, Plates, Bars, and Strips	2.1	G												
			Metal Stair System	2.2.1	G												
			SD-03 Product Data														
			Structural-Steel Plates, Shapes, and Bars	2.4.1	G												
			Structural-Steel Tubing	2.4.2	G												
			Hot-Rolled Carbon Steel Sheets and Strips	2.4.5	G												
			Cold-Finished Steel Bars	2.4.4	G												
			Hot-Rolled Carbon Steel Bars	2.4.3	G												
			Cold-Rolled Carbon Steel Sheets	2.4.6	G												
			Galvanized Carbon Steel Sheets	2.4.7	G												
			Cold-Drawn Steel Tubing	2.4.8	G												
			Gray Iron Castings	2.4.9	G												
			Malleable Iron Castings	2.4.10	G												
			Concrete Inserts	2.3.4	G												
			Masonry Anchorage Devices	2.3.5	G												
			Protective Coating	2.2.4	G												
			Steel Pan Stairs	2.2.2	G												
			Steel Stairs	2.3.1	G												
			Steel Stairs, Circular	2.3.2	G												
			SD-07 Certificates														
			Welding Procedures	1.3.1	G												
			Welder Qualification	1.3.1	G												
			SD-08 Manufacturer's Instructions														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		05 51 00	Structural-Steel Plates, Shapes, and Bars	2.4.1	G													
			Structural-Steel Tubing	2.4.2	G													
			Hot-Rolled Carbon Steel Sheets and Strips	2.4.5	G													
			Cold-Finished Steel Bars	2.4.4	G													
			Hot-Rolled Carbon Steel Bars	2.4.3	G													
			Cold-Rolled Carbon Steel Sheets	2.4.6	G													
			Galvanized Carbon Steel Sheets	2.4.7	G													
			Cold-Drawn Steel Tubing	2.4.8	G													
			Gray Iron Castings	2.4.9	G													
			Malleable Iron Castings	2.4.10	G													
			Protective Coating	2.2.4	G													
			Masonry Anchorage Devices	2.3.5	G													
		05 51 33	SD-02 Shop Drawings															
			Ladders	2.3														
			Ship's Ladder	2.3.3														
			SD-03 Product Data															
			Ladders	2.3														
			Ship's Ladder	2.3.3														
			Ladder Safety Devices	2.3.2														
			SD-07 Certificates															
			Fabricator Certification for Ladder Assembly	1.3														
			Fabricator Certification for Ships Ladder Assembly	1.3														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		05 52 00	SD-02 Shop Drawings														
			Fabrication Drawings	1.2.1	G												
			Iron and Steel Hardware	3.2	G												
			Steel Shapes, Plates, Bars and Strips	3.2	G												
			SD-03 Product Data														
			Structural Steel Plates, Shapes, and Bars	2.2.1	G												
			Structural Steel Tubing	2.2.2	G												
			Cold-Finished Steel Bars	2.2.4	G												
			Hot-Rolled Carbon Steel Bars	2.2.3	G												
			Cold-Drawn Steel Tubing	2.2.5	G												
			Concrete Inserts	2.2.7	G												
			Masonry Anchorage Devices	2.2.8	G												
			Protective Coating	2.1.3	G												
			Steel Railings and Handrails	2.2.10	G												
			Aluminum Railings and Handrails	2.2.11	G												
			Anchorage and Fastening Systems	1.2.1	G												
			SD-07 Certificates														
			Welding Procedures	1.4.1	G												
			Welder Qualification	1.4.2	G												
			SD-08 Manufacturer's Instructions														
			Installation Instructions	3.2	G												
		06 10 00	SD-03 Product Data														
			Fire-retardant Treatment	1.8													

SUBMITTAL REGISTER

CONTRACT NO. _____

TITLE AND LOCATION
Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR _____

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION	
																		(g)
		06 10 00	Adhesives	2.2.2														
			SD-06 Test Reports															
			Preservative-treated	1.4.3														
			SD-07 Certificates															
			Certificates of Grade	1.9.1														
			Preservative Treatment	1.7														
		06 20 00	SD-02 Shop Drawings															
			Detail Drawings Indicating All	1.3	G													
			Wood Assemblies															
			SD-03 Product Data															
			Wood Products	2.2	G													
			Countertops	2.3	G													
			Treated Wood Products	1.4	G													
			Soffits	3.4	G													
			Hardware and Accessories	2.7	G													
			SD-04 Samples															
			Samples	1.5	G													
			SD-07 Certificates															
			Certificates of Grade	1.7.1.1	G													
			Certified Sustainably Harvested	1.7.1.2	G													
			Wood															
			Indoor Air Quality	1.7.1.3	G													
			SD-11 Closeout Submittals															
			Certified Sustainably Harvested	2.2.5	S													
			Softwood Plywood															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION	
																		(g)
		06 20 00	Certified Sustainably Harvested Hardboard	2.2.7	S													
			VOC Content for Softwood Plywood	2.2.5	S													
			VOC Content for Hardwood Plywood	2.2.6	S													
			Indoor Air Quality for Non-aerosol Adhesives	2.8.1.2	S													
			Indoor Air Quality for Aerosol Adhesives	2.8.1.2	S													
		06 41 10	SD-02 Shop Drawings															
			Shop Drawings Installation	3.1.2 3.1	G													
			SD-03 Product Data															
			Laminated Plastic Covered	2.1.1														
			Hardware Finish	2.2.1														
			Certification	1.4														
			SD-04 Samples															
			Cabinet Hardware	2.2														
			Casework Hardware	2.2.2														
		06 61 16	SD-02 Shop Drawings															
			Solid Polymer Material	2.1.3	G													
			Solid Polymer Material	2.3	G													
			Solid Polymer Material	2.3.2	G													
			SD-03 Product Data															
			Solid Polymer Material	2.1.3														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY					REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		MAILED TO CONTR/ DATE RCD FRM APPR AUTH	
																		(g)
		06 61 16	Solid Polymer Material	2.3														
			Solid Polymer Material	2.3.2														
			SD-04 Samples															
			Solid Polymer Material	2.1.3	G													
			Solid Polymer Material	2.3	G													
			Solid Polymer Material	2.3.2	G													
			SD-06 Test Reports															
			Solid Polymer Material	2.1.3														
			Solid Polymer Material	2.3														
			Solid Polymer Material	2.3.2														
			SD-08 Manufacturer's Instructions															
			Solid Polymer Material	2.1.3														
			Solid Polymer Material	2.3														
			Solid Polymer Material	2.3.2														
		07 05 23	SD-01 Preconstruction Submittals															
			Work Plan	1.4	G													
			SD-03 Product Data															
			Thermal Imaging Camera	2.2	G													
			SD-05 Design Data															
			Envelope Surface Area Calculations	3.2	G													
			SD-07 Certificates															
			Pressure Test Agency	1.6.2.1														
			Thermographer Qualifications	1.6.2.2														
			Test Instruments	1.6.3														
			Date Of Last Calibration	1.6.3														

SUBMITTAL REGISTER

CONTRACT NO. _____

TITLE AND LOCATION
Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR _____

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		07 05 23	SD-06 Test Reports															
			Pressure Test Procedures	3.5	G													
			Air Leakage Test Report	3.5.8	G													
			Diagnostic Test Report	3.6.5	G													
		07 13 53	SD-03 Product Data															
			Manufacturer's Standard Details	1.3	G													
			Elastomeric Waterproofing Sheet Material	2.2	G													
			Primers, Adhesives, and Mastics	1.4	G													
			Primers, Adhesives, and Mastics	2.2	G													
			SD-06 Test Reports															
			Elastomeric Waterproofing Sheet Material	2.2	G													
			Field Quality Control	3.6	G													
			Protective Covering	3.7	G													
			SD-07 Certificates															
			Elastomeric Waterproofing Sheet Material	2.2														
			Primers, Adhesives, and Mastics	1.4	G													
			Primers, Adhesives, and Mastics	2.2	G													
			Protective Coverings	1.4	G													
			Special Warranties	1.8	G													
			Special Warranties	1.8	G													
			Certificates Of Compliance	2.1.1	G													
			Certificates Of Compliance	2.1.2	G													
			SD-08 Manufacturer's Instructions															

SUBMITTAL REGISTER

CONTRACT NO. _____

TITLE AND LOCATION
Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR _____

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		07 13 53	Primers, Adhesives, and Mastics	1.4	G												
			Primers, Adhesives, and Mastics	2.2	G												
			SD-11 Closeout Submittals														
			Certificates Of Compliance	2.1.1	G												
			Certificates Of Compliance	2.1.2	G												
		07 21 13	SD-03 Product Data														
			Manufacturer's Standard Details	1.3	G												
			Block or Board Insulation	2.2	G												
			Vapor Retarder	2.3	G												
			Pressure Sensitive Tape	2.4	G												
			Protection Board or Coatings	1.4	G												
			Accessories	2.6	G												
			SD-07 Certificates														
			Block or Board Insulation	2.2	G												
			Vapor Retarder	2.3	G												
			Protection Board or Coating	2.5	G												
			Protection Board or Coating	3.4.5	G												
			Special Warranties	1.8	G												
			Special Warranties	1.8	G												
			ULE Greenguard	1.5	G S												
			SD-08 Manufacturer's Instructions														
			Block or Board Insulation	2.2													
			Adhesive	2.6.1													
			SD-11 Closeout Submittals														
			ULE Greenguard	1.5	S												

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY					REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		MAILED TO CONTR/ DATE RCD FRM APPR AUTH	
																		(g)
		07 21 13	Volatile Organic Compound (VOC) Content	2.1.1	S													
			Recycled Content	2.1.2	S													
		07 21 16	SD-03 Product Data															
			Blanket Insulation	2.2														
			Sill Sealer Insulation	2.3														
			Vapor Retarder	2.5														
			Pressure Sensitive Tape	2.6														
			Accessories	2.7														
			SD-08 Manufacturer's Instructions															
			Insulation	3.3.1														
			SD-11 Closeout Submittals															
			Recycled Content for Insulation Materials	2.1.1	S													
			Reduce Volatile Organic Compounds (VOC)	2.1.2	S													
		07 22 00	SD-02 Shop Drawings															
			Insulation Board Layout	1.3	G													
			Verification of Existing Conditions	1.3	G													
			SD-03 Product Data															
			Insulation	2.2	G													
			Cover Board	1.4	G													
			Fasteners	2.5	G													
			Moisture Control	2.4	G													
			SD-06 Test Reports															
			Flame Spread Rating	1.8.1	G													

SUBMITTAL REGISTER

CONTRACT NO. _____

TITLE AND LOCATION
Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR _____

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION	
																		(g)
		07 22 00	SD-07 Certificates															
			Volatile Organic Compounds (VOC) Content	1.9	G													
			Installer Qualifications	1.6	G													
			Certificates Of Compliance For Felt Materials	1.6	G													
			SD-08 Manufacturer's Instructions															
			Fasteners	2.5	G													
			Insulation	2.2	G													
			SD-11 Closeout Submittals															
			Volatile Organic Compounds (VOC) Content	1.9	S													
		07 27 10	SD-04 Samples															
			Mock-Up	3.1.2	G													
			SD-06 Test Reports															
			Design Review Report	1.8	G DO													
			Testing and Inspection	3.1.3	G RO													
			SD-07 Certificates															
			Air Barrier Inspector	1.7	G RO													
		07 27 19.01	SD-01 Preconstruction Submittals															
			Qualifications of Manufacturer	1.8.1	G													
			Qualifications of Installer	1.8.2	G													
			SD-02 Shop Drawings															
			Self-adhering Air Barrier	1.4	G													
			SD-03 Product Data															
			Self-adhering Air Barrier	1.4	G													

SUBMITTAL REGISTER

CONTRACT NO. _____

TITLE AND LOCATION
Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR _____

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY					REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		MAILED TO CONTR/ DATE RCD FRM APPR AUTH	
																		(g)
		07 27 19.01	Primers, Adhesives, and Mastics	2.2	G													
			Safety Data Sheets	1.4.2	G													
			SD-04 Samples															
			Self-adhering Air Barrier	1.4	G													
			SD-06 Test Reports															
			Field Peel Adhesion Test	1.6	G													
			Flame Propagation of Wall Assemblies	1.4.4	G													
			Flame Spread and Smoke Developed Index Ratings	1.4.4	G													
			Site Inspections and Testing	3.4.1	G													
			SD-07 Certificates															
			Self-adhering Air Barrier	1.4	G													
			Qualifications of Manufacturer	1.8.1	G													
			Qualifications of Installer	1.8.2	G													
			SD-08 Manufacturer's Instructions															
			Self-adhering Air Barrier	1.4	G													
			Primers, Adhesives, and Mastics	2.2	G													
		07 27 26	SD-01 Preconstruction Submittals															
			Qualifications of Manufacturer	1.9.1	G													
			Qualifications of Installer	1.9.2	G													
			SD-02 Shop Drawings															
			Fluid-Applied Membrane Air Barrier	1.4	G													
			SD-03 Product Data															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		07 27 26	Fluid-Applied Membrane Air Barrier	1.4	G													
			Transition Membrane	2.4	G													
			Primers, Adhesives, and Mastics	2.3	G													
			Reinforcement	2.7	G													
			Safety Data Sheets	1.4.2	G													
			SD-04 Samples															
			Mockup	1.4.3	G													
			SD-06 Test Reports															
			Capillary Moisture Test	1.6	G													
			Field Peel Adhesion Test	1.4.4	G													
			Flame Propagation of Wall Assemblies	1.4.4	G													
			Flame Spread and Smoke Developed Index Ratings	1.4.4	G													
			Site Inspections	3.4.1	G													
			SD-07 Certificates															
			Fluid-Applied Membrane Air Barrier	1.4	G													
			Transition Membrane	2.4	G													
			Qualifications of Manufacturer	1.9.1	G													
			Qualifications of Installer	1.9.2	G													
			SD-08 Manufacturer's Instructions															
			Fluid-Applied Membrane Air Barrier	1.4	G													
			Transition Membrane	2.4	G													

SUBMITTAL REGISTER

CONTRACT NO. _____

TITLE AND LOCATION
Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR _____

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY					REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		MAILED TO CONTR/ DATE RCD FRM APPR AUTH	
																		(g)
		07 27 26	Primers, Adhesives, and Mastics	2.3	G													
			SD-11 Closeout Submittals															
			Volatile Organic Compound (VOC) Content	2.1	S													
		07 41 13	SD-02 Shop Drawings															
			Roofing Panels	1.4.5	G													
			Flashing and Accessories	1.4.5	G													
			Gutter/Downspout Assembly	1.4.5	G													
			SD-03 Product Data															
			Roof Panels	2.1	G													
			Factory-Applied Color Finish	1.4.5	G													
			Accessories	2.4	G													
			Fasteners	1.4.5	G													
			Pressure Sensitive Tape	1.4.5	G													
			Underlayments	2.7	G													
			Gaskets and Sealing/Insulating Compounds	2.8	G													
			Coil Stock	1.4.5	G													
			Galvanizing Repair Paint	1.4.5	G													
			SD-04 Samples															
			Roof Panels	2.1	G													
			Factory-applied Color Finish	1.4.5	G													
			Accessories	2.4	G													
			Fasteners	1.4.5	G													
			Gaskets and Sealant/Insulating Compounds	1.4.5	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		07 41 13	SD-05 Design Data															
			Wind Uplift Resistance	1.2.1.2	G													
			SD-06 Test Reports															
			Leakage Test Report	1.2.1.1	G													
			Wind Uplift Test Report	1.2.1.2	G													
			Fire Rating Test Report	2.6.2	G													
			Factory Finish and Color	2.2	G													
			Performance Requirements															
			SD-07 Certificates															
			Roof Panels	2.1	G													
			Coil Stock Compatibility	1.4.5	G													
			Self-Adhering Modified Bitumen	2.7.1	G													
			Underlayment															
			Qualification of Manufacturer	1.4.1	G													
			Qualification of Applicator	1.4.2	G													
			SD-08 Manufacturer's Instructions															
			Insulation	2.6	G													
			Installation Manual	1.4.5	G													
			SD-11 Closeout Submittals															
			Warranties	1.8	G													
			Information Card	3.11	G													
		07 41 16	SD-03 Product Data															
			Soffit panels	2.1	G													
			Closures	3.1.1														
			flashing	3.1.1														
			Accessories	2.3														

SUBMITTAL REGISTER

CONTRACT NO. _____

TITLE AND LOCATION
Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR _____

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		07 41 16	Fasteners	2.4														
			Gaskets and Insulating Compounds	2.6														
			SD-04 Samples															
			SOFFIT PANEL	2.1														
			Accessories	2.3														
			Fasteners	2.4														
			Gaskets and Insulating Compounds	2.6														
			Sealant	2.5	G													
			SD-06 Test Reports															
			Salt Spray Test	2.2.1														
			SD-07 Certificates															
			Accessories	2.3														
			SD-08 Manufacturer's Instructions															
			INSTALLATION	3.1	G													
		07 60 00	SD-02 Shop Drawings															
			Exposed Sheet Metal	2.2.1	G													
			Gutters	3.1.17	G													
			Downspouts	3.1.18	G													
			Expansion Joints	3.1.26	G													
			Gravel Stops and Fasciae	2.2.1	G													
			Splash Pans	3.1.22	G													
			Flashing for Roof Drains	3.1.19	G													
			Base Flashing	3.1.11	G													
			Counterflashing	3.1.12	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		07 60 00	Flashing at Roof Penetrations and Equipment Supports	3.1.27	G												
			Reglets	2.2.15	G												
			Scuppers	3.1.20	G												
			Copings	3.1.30	G												
			Drip Edges	3.1.16	G												
			Conductor Heads	3.1.21	G												
			Open Valley Flashing	3.1.23	G												
			Eave Flashing	3.1.24	G												
			SD-03 Product Data														
			Cool Roof	2.2.12	G S												
			SD-04 Samples														
			Finish Samples	1.4.2	G												
			SD-07 Certificates														
			Certificates of Compliance	2.1	G												
			SD-08 Manufacturer's Instructions														
			Instructions for Installation	1.4.3	G												
			Quality Control Plan	3.5	G												
			SD-10 Operation and Maintenance Data														
			Cleaning and Maintenance	1.4.3	G												
			SD-11 Closeout Submittals														
			Recycled Content	2.1	S												
		07 84 00	SD-02 Shop Drawings														
			Firestopping System	2.1	G												
			SD-03 Product Data														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		07 84 00	Firestopping Materials	2.2	G													
			SD-06 Test Reports															
			Inspection	3.3	G													
			SD-07 Certificates															
			Inspector Qualifications	1.5.2														
			Firestopping Materials	2.2														
			Installer Qualifications	1.5.1	G													
		07 92 00	SD-03 Product Data															
			Sealants	2.2	G													
			Primers	2.3	G													
			Bond Breakers	2.4	G													
			Backstops	2.5	G													
			SD-06 Test Reports															
			Field Adhesion	3.1	G													
			SD-07 Certificates															
			Indoor Air Quality	1.4.1	G													
			SD-11 Closeout Submittals															
			Indoor Air Quality For Interior	2.2.1	S													
			Sealants															
			Indoor Air Quality For Interior	2.2.3	S													
			Floor Joint Sealants															
			Indoor Air Quality For Interior	2.2.4	S													
			Acoustical Sealants															
			Indoor Air Quality For Interior	2.6	S													
			Caulking															
		08 11 13	SD-02 Shop Drawings															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY					REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		MAILED TO CONTR/ DATE RCD FRM APPR AUTH	
																		(g)
		08 11 13	Doors	2.1	G													
			Doors	2.1	G													
			Frames	2.7	G													
			Frames	2.7	G													
			Accessories	2.5														
			Weatherstripping	2.9														
			SD-03 Product Data															
			Doors	2.1	G													
			Frames	2.7	G													
			Accessories	2.5														
			Weatherstripping	2.9														
		08 33 23	SD-02 Shop Drawings															
			Overhead Coiling Doors	2.2.1														
			Counterbalancing Mechanism	2.2.3														
			Manual Door Operators	2.2.4														
			Electric Door Operators	2.2.5														
			Bottom Bars	2.2.1.2														
			Guides	2.1.1.1														
			Mounting Brackets	2.2.3.1														
			Overhead Drum	2.2.1.9														
			Hood	3.3.2														
			Installation Drawings	2.1.1.1														
			SD-03 Product Data															
			Overhead Coiling Doors	2.2.1														
			Hardware	2.2.2														
			Counterbalancing Mechanism	2.2.3														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION			
																		(g)
		08 33 23	Manual Door Operators	2.2.4														
			Electric Door Operators	2.2.5														
			Recycled Content For Steel	2.2.1.1														
			Curtain Slats															
			SD-05 Design Data															
			Overhead Coiling Doors	2.2.1														
			Hardware	2.2.2														
			Counterbalancing Mechanism	2.2.3														
			Manual Door Operators	2.2.4														
			Electric Door Operators	2.2.5														
			SD-10 Operation and Maintenance															
			Data															
			Operation and Maintenance	3.3.2	G													
			Manuals															
			Materials	3.3.2														
			Devices	3.3.2														
			Procedures	3.3.2														
			Manufacture's Brochures	3.3.2														
			Parts Lists	3.3.2	G													
			SD-11 Closeout Submittals															
			Warranty	3.3.1	G													
		08 34 59	SD-02 Shop Drawings															
			Vault Door Unit	2.1	G													
			SD-03 Product Data															
			Vault Door and Frame	2.2														
			SD-07 Certificates															

SUBMITTAL REGISTER

CONTRACT NO. _____

TITLE AND LOCATION
Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR _____

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		08 34 59	Vault Door and Frame	2.2													
			SD-08 Manufacturer's Instructions														
			Installation	3.1													
			SD-11 Closeout Submittals														
			LEED Documentation	1.2													
		08 51 13	SD-02 Shop Drawings														
			Windows	2.2	G												
			Fabrication Drawings	1.10													
			SD-03 Product Data														
			Windows	2.2	G												
			Hardware	2.3.8.1	G												
			Fasteners	2.3.3	G												
			Window Performance	1.11	G												
			Thermal-Barrier Windows	2.5	G												
			Mullions	2.6	G												
			Window Cleaners' Bolts	2.7	G												
			Screens	2.3.10	G												
			Weatherstripping	2.3.2	G												
			Accessories	2.3.8	G												
			Adhesives	2.3.4													
			Thermal Performance	1.11.5	G												
			SD-04 Samples														
			Finish Sample	1.4.2.1													
			Window Sample	1.4.2.2													
			SD-05 Design Data														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		08 51 13	Structural Calculations for Deflection	2.2	G												
			Design Analysis	1.4.3	G												
			SD-06 Test Reports														
			Minimum Condensation Resistance Factor	1.4.4													
			Resistance to Forced Entry Standard Airblast Test	1.4.4 1.11.2.3													
			SD-10 Operation and Maintenance Data														
			Windows	2.2	G												
			Plastic Identification	1.7													
			SD-11 Closeout Submittals														
			Recycled Content of Aluminum Windows	2.1.1	S												
		08 60 45	SD-02 Shop Drawings														
			Shop Drawings	3.2	G												
			SD-03 Product Data														
			Skylights and Translucent Panels Warranty	2.2 1.6	G												
			SD-06 Test Reports														
			Test Reports	2.2													
			SD-07 Certificates														
			Systems	2.6													
			Qualifications	1.4													
			SD-11 Closeout Submittals														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		08 60 45	Recycled Content for Aluminum Framing	2.1.1	S													
		08 71 00	SD-02 Shop Drawings															
			Hardware Schedule	1.4	G													
			Keying System	2.3.6	G													
			SD-03 Product Data															
			Hardware Items	2.3	G													
			SD-08 Manufacturer's Instructions															
			Installation	3.1														
			SD-10 Operation and Maintenance Data															
			Hardware Schedule	1.4	G													
			SD-11 Closeout Submittals															
			Key Bitting	1.5.1														
		08 81 00	SD-02 Shop Drawings															
			Installation	3.3.1	G													
			SD-03 Product Data															
			Insulating Glass	1.6.1														
			Glazing Accessories	1.3														
			SD-04 Samples															
			Insulating Glass	1.6.1														
			Plastic Sheet	3.2.7														
			Glazing Compound	2.4.2														
			Tape	2.4.5														
			Sealant	2.4.3.1														
			SD-07 Certificates															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		08 81 00	Insulating Glass	1.6.1													
			SD-08 Manufacturer's Instructions														
			Setting and Sealing Materials	2.4													
			Glass Setting	3.2													
		08 91 00	SD-02 Shop Drawings														
			Wall louvers	1.4													
			Wall louvers	1.5													
			SD-03 Product Data														
			Metal Wall Louvers	2.2													
			SD-04 Samples														
			Wall louvers	1.4	G												
			Wall louvers	1.5	G												
			Door louvers	1.5	G												
			Door louvers	2.3	G												
		09 22 00	SD-02 Shop Drawings														
			Metal support systems	2.1	G												
		09 29 00	SD-03 Product Data														
			Cementitious Backer Units	2.2.7													
			Glass Mat Water-Resistant	2.2.4													
			Gypsum Tile Backing Board														
			Water-Resistant Gypsum Backing Board	2.2.3													
			Glass Mat Covered or Reinforced Gypsum Sheathing	2.2.5													
			Glass Mat Covered or Reinforced Gypsum Sheathing Sealant	2.2.5.1													

SUBMITTAL REGISTER

CONTRACT NO. _____

TITLE AND LOCATION
Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR _____

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		09 29 00	Abuse Resistant Gypsum Board	2.2.6														
			Accessories	2.2.13														
			Certifications	1.3														
			Gypsum Board	2.2.1														
			SD-07 Certificates															
			Asbestos Free Materials	2.2	G													
			Indoor Air Quality	1.3.1	G													
			SD-11 Closeout Submittals															
			Recycled Content for Gypsum Board	2.2.1	S													
			Recycled Content for Paper Facing and Gypsum Cores	2.2.1	S													
			Indoor Air Quality for Gypsum Board	2.2.1	S													
			VOC Content of Joint Compound	2.2.8	S													
			Indoor Air Quality for Non-aerosol Adhesives	2.2.10	S													
			Indoor Air Quality for Aerosol Adhesives	2.2.10	S													
		09 30 10	SD-02 Shop Drawings															
			Detail Drawings	3.2	G													
			SD-03 Product Data															
			Porcelain Tile	2.1.1	G													
			Glazed Wall Tile	2.1.2	G													
			Setting-Bed	2.2	G													
			Mortar, Grout, and Adhesive	2.4	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION	
																		(g)
		09 30 10	Reinforcing Wire Fabric	2.2.6	G													
			SD-04 Samples															
			Tile	2.1	G													
			Accessories	2.1	G													
			Accessories	2.1.3	G													
			Transition Strips	2.1	G													
			Transition Strips	2.6	G													
			Grout	2.4.3	G													
			SD-07 Certificates															
			Indoor Air Quality	1.3.1														
			SD-08 Manufacturer's Instructions															
			Maintenance Instructions	3.7														
			SD-10 Operation and Maintenance Data															
			Installation	3.2	G													
			SD-11 Closeout Submittals															
			Recycled Content for Porcelain Tile	2.1.1	S													
			Recycled Content For Glazed Wall Tile	2.1.2														
			Indoor Air Quality For Adhesives	2.4														
			Indoor Air Quality For Sealants	2.4.7														
		09 51 00	SD-02 Shop Drawings															
			Approved Detail Drawings	1.2	G RO													
			SD-03 Product Data															
			Acoustical Ceiling Systems	1.2.4	G RO													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		09 51 00	SD-04 Samples															
			Acoustical Units	2.1	G RO													
			Acoustic Ceiling Tiles	2.1.1	G RO													
			SD-06 Test Reports															
			Ceiling Attenuation Class and Test	1.2.1	G RO													
			SD-07 Certificates															
			Acoustical Units	2.1	G RO													
			Acoustic Ceiling Tiles	2.1.1	G RO													
		09 65 00	SD-02 Shop Drawings															
			Resilient Flooring and Accessories	2.8	G													
			SD-03 Product Data															
			Resilient Flooring and Accessories	2.8	G													
			Adhesives	2.4														
			Wall Base	2.2														
			SD-04 Samples															
			Resilient Flooring and Accessories	2.8	G G													
			SD-06 Test Reports															
			Moisture, Alkalinity and Bond Tests	3.3	G													
			SD-08 Manufacturer's Instructions															
			Surface Preparation	3.2	G													
			Installation	3.1	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		09 65 00	Luxury Vinyl Tile	2.1													
			SD-10 Operation and Maintenance Data														
			Resilient Flooring and Accessories	2.8	G G												
			SD-11 Closeout Submittals														
			LEED Documentation	1.3													
		09 67 23	SD-02 Shop Drawings														
			Installation Drawings	2.1	G												
			SD-03 Product Data														
			Manufacturer's Catalog Data	1.2.1	G												
			SD-04 Samples														
			Hardboard Mounted Epoxy Flooring	1.5.2	G												
			Floor Topping	3.1.4	G												
			SD-05 Design Data														
			Design Mix Data	1.2.2	G												
			SD-07 Certificates														
			Listing of Product Installations	1.5.1	G												
			Referenced Standards	1.5	G												
			Certificates														
			SD-11 Closeout Submittals														
			Warranty	1.6	G												
		09 68 00	SD-02 Shop Drawings														
			Installation Drawings	3.4	G												
			SD-03 Product Data														

SUBMITTAL REGISTER

CONTRACT NO. _____

TITLE AND LOCATION
Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR _____

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		09 68 00	Carpet	2.1	G													
			Moldings	2.4	G													
			SD-04 Samples															
			Carpet	2.1	G													
			Moldings	2.4	G													
			SD-06 Test Reports															
			Moisture and Alkalinity Tests	3.2	G													
			SD-07 Certificates															
			Carpet	2.1														
			Regulatory Requirements	1.4														
			SD-08 Manufacturer's Instructions															
			Surface Preparation	3.1														
			Installation	3.4														
			SD-10 Operation and Maintenance Data															
			Carpet	2.1	G													
			Cleaning and Protection	3.5	G													
			SD-11 Closeout Submittals															
			LEED Documentation	1.2														
		09 84 20	SD-02 Shop Drawings															
			Approved Detail Drawings	2.2	G													
			SD-03 Product Data															
			Installation	3.2														
			Acoustical Wall Panels	2.2	G													
			SD-04 Samples															
			Acoustical Wall Panels	2.2	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		09 84 20	SD-07 Certificates															
			Acoustical Wall Panels	2.2														
			Certified Sustainably Harvested Wood	1.3.1	S													
			SD-11 Closeout Submittals															
			Warranty	1.5														
		09 90 00	SD-02 Shop Drawings															
			Piping identification stencil	3.10	G													
			SD-03 Product Data															
			Coating	2.1	G													
			Manufacturer's Technical Data Sheets	2.1														
			SD-04 Samples															
			Color	1.10	G													
			SD-07 Certificates															
			Applicator's qualifications	1.3														
			Qualification Testing	1.4.1.2	G													
			SD-08 Manufacturer's Instructions															
			Application instructions	3.2.1														
			Mixing	3.6.2														
			Manufacturer's Material Safety Data Sheets	1.7.2														
			SD-10 Operation and Maintenance Data															
			Coatings:	2.1	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		10 11 00	SD-03 Product Data															
			Visual Display Board	1.2	G													
			SD-04 Samples															
			Aluminum	2.1.4	G													
			Porcelain Enamel	2.1.1	G													
			Materials	2.1	G													
			SD-07 Certificates															
			Visual Display Board	1.2														
		10 21 13	SD-02 Shop Drawings															
			Fabrication Drawings	2.1														
			Installation Drawings	3.3	G													
			SD-03 Product Data															
			Cleaning and Maintenance Instructions	2.1														
			Colors And Finishes	2.7														
			Galvanized Steel Sheet	2.2.1														
			Sound-Deadening Cores	2.2.2														
			Anchoring Devices and Fasteners	2.2.3														
			Hardware and Fittings	2.2.5														
			Brackets	2.2.4														
			Door Hardware	2.2.6														
			Pilaster Shoes	2.5														
			Finishes	2.2.5.2	G													
			Toilet Enclosures	2.3.1														
			Urinal Screens	2.3.2														
			SD-04 Samples															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		10 21 13	Colors and Finishes	2.7	G													
			Hardware and Fittings	2.2.5														
			Anchoring Devices and Fasteners	2.2.3														
			SD-07 Certificates															
			Warranty	1.6														
			Indoor Air Quality	1.3.1	G													
			SD-11 Closeout Submittals															
			Recycled content for stainless steel partitions and screens	2.3	S													
		10 26 13	SD-02 Shop Drawings															
			Corner Guards	2.2	G RO													
			SD-03 Product Data															
			Corner Guards	2.2	G RO													
			SD-04 Samples															
			Finish	2.4	G RO													
			SD-06 Test Reports															
			Corner Guards	2.2														
			SD-07 Certificates															
			Corner Guards	2.2														
		10 28 13	SD-03 Product Data															
			Finishes	2.1.2	G													
			Accessory Items	2.2	G													
			SD-04 Samples															
			Finishes	2.1.2														
			Accessory Items	2.2														
			SD-07 Certificates															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		10 28 13	Accessory Items	2.2													
		10 51 13	SD-02 Shop Drawings														
			Types	2.1	G												
			Location	1.4	G												
			Installation	3.1													
			SD-03 Product Data														
			Material	2.2													
			Locking Devices	2.3.1													
			Handles	2.3.4													
			Finish	2.2.3													
			components	2.3													
			Assembly	3.1													
			SD-04 Samples														
			Color chips	1.5.1	G												
		10 56 13	SD-01 Preconstruction Submittals														
			Shelving Units	2.1													
			SD-03 Product Data														
			Shelving Units	2.1													
			Accessories	2.2													
			Installation instructions	3.2													
			SD-04 Samples														
			Finish	2.3													
			SD-06 Test Reports														
			Shelving Units	2.1													
			Finish	2.3													
		12 24 13	SD-02 Shop Drawings														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY					REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		MAILED TO CONTR/ DATE RCD FRM APPR AUTH	
																		(g)
		12 24 13	Installation	3.3	G DO													
			SD-03 Product Data															
			Window Shades	2.1	G DO													
			Certification	1.4.6														
			SD-04 Samples															
			Window Shades	2.1	G DO													
			SD-06 Test Reports															
			Window Shades	2.1														
			SD-08 Manufacturer's Instructions															
			Window Shades	2.1														
			SD-10 Operation and Maintenance Data															
			Window Shades	2.1														
			SD-11 Closeout Submittals															
			Local/Regional Materials (LEED)	1.1														
			Shade Cloth (LEED)	1.4.5														
		12 48 13	SD-02 Shop Drawings															
			Installation Drawings	3.2	G													
			Detail Drawings	3.2	G													
			Custom Graphics Drawings	3.2	G													
			SD-03 Product Data															
			Entrance Floor Mats and Frames	2.1.1	G													
			Adhesives and Concrete Primers	2.1.2	G													
			SD-04 Samples															
			Entrance Floor Mats and Frames	2.1.1	G													
			Custom Graphics	2.1.1	G													

SUBMITTAL REGISTER

CONTRACT NO. _____

TITLE AND LOCATION
Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR _____

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		12 48 13	SD-08 Manufacturer's Instructions															
			Manufacturer's Instructions	3.2														
			SD-10 Operation and Maintenance Data															
			Protection, Maintenance, and Repair Information	3.2														
		13 34 19	SD-01 Preconstruction Submittals															
			Manufacturer's Qualifications	1.6.3	G													
			SD-02 Shop Drawings															
			Detail Drawings	1.2.1.8	G													
			Detail Drawings	1.6.1	G													
			SD-03 Product Data															
			sustainable acquisition compliance	2.4.4	G													
			Manufacturer's catalog data	1.6.1	G													
			SD-04 Samples															
			Coil Stock	1.6.1	G													
			Coil Stock	2.1.8	G													
			Roof Panels	1.2.1.10	G													
			Wall Panels	1.2.1.10	G													
			Fasteners	2.5.2	G													
			Metal Closure Strips	2.8.1	G													
			Insulation	1.4.7	G													
			Insulation	2.4.3	G													
			Vapor Barrier	1.6.10	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		13 34 19	Manufacturer's color charts and chips	2.4.5	G												
			SD-05 Design Data descriptive and technical literature	1.6.1	G												
			building design analysis	1.6.1	G												
			SD-06 Test Reports test reports	1.6.1	G												
			Coatings and base metals	1.6.1	G												
			Factory Color Finish Performance Requirements	1.6.1	G												
			SD-07 Certificates system components	1.6.1	G												
			Coil Stock	1.6.1	G												
			Coil Stock	2.1.8	G												
			Aluminized Steel Repair Paint	1.6.1	G												
			Galvanizing Repair Paint	1.6.1	G												
			Enamel Repair Paint	1.6.1	G												
			Qualification of Manufacturer	1.6.1	G												
			Qualification of Erector	1.6.1	G												
			SD-08 Manufacturer's Instructions Installation of Roof and Wall panels	1.6.2	G												
			shipping, handling, and storage	1.7	G												
			SD-11 Closeout Submittals Manufacturer's Warranty	3.14.1	G												

SUBMITTAL REGISTER

CONTRACT NO. _____

TITLE AND LOCATION
Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR _____

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		13 34 19	Contractor's Warranty for Installation	3.14.2	G													
		13 48 00	SD-02 Shop Drawings															
			Bracing	3.1	G PO													
			Resilient Vibration Isolation Devices	3.4	G PO													
			Equipment Requirements	2.1	G PO													
			SD-03 Product Data															
			Bracing	3.1	G PO													
			Equipment Requirements	2.1	G PO													
			SD-06 Test Reports															
			Anchor Bolts	3.3	G PO													
		13 48 00.10	SD-02 Shop Drawings															
			Coupling and Bracing	3.1	G													
			Flexible Couplings or Joints	3.3	G													
			Equipment Requirements	2.1	G													
			Contractor Designed Bracing	1.2.4	G													
			SD-03 Product Data															
			Coupling and Bracing	3.1	G													
			Equipment Requirements	2.1	G													
			Contractor Designed Bracing	1.2.4	G													
			SD-07 Certificates															
			Flexible Ball Joints	2.3														
		13 48 56	SD-01 Preconstruction Submittals															
			Bridge Manufacturer's Qualifications	1.4.1.1	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		13 48 56	Manufacture's Descriptive and Technical Literature	1.4.1.2	G												
			Detailed Design Drawings	1.4.1.3	G												
			Manufacture's design analysis	1.4.1.4	G												
			Representative Design Calculations	1.4.1.5	G												
			Splicing and Erection Procedures	1.4.1.6	G												
			Warranty Information	1.4.1.7	G												
			Inspection and Maintenance Procedures	1.4.1.8	G												
			Welder Qualifications	1.4.1.9	G												
		21 13 13	SD-02 Shop Drawings														
			Shop Drawings	1.4.3	G												
			As-Built Drawings	3.9													
			SD-03 Product Data														
			Fire Protection Related Submittals	1.4.1													
			Materials and Equipment	2.3	G												
			Spare Parts	1.6													
			Preliminary Tests	3.8	G												
			Final Acceptance Test	3.9	G												
			Onsite Training	3.10	G												
			Fire Protection Specialist	1.4.1	G												
			Sprinkler System Installer	1.4.2	G												
			SD-05 Design Data														
			Sway Bracing	1.4.3	G												

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		21 13 13	Hydraulic Calculations	1.2.1.3	G												
			SD-06 Test Reports														
			Preliminary Test Report	3.8													
			Final Acceptance Test Report	3.9													
			SD-07 Certificates														
			Inspection by Fire Protection Specialist	3.3													
			SD-10 Operation and Maintenance Data														
			Operating and Maintenance Manuals	3.10	G												
		22 00 00	SD-02 Shop Drawings														
			Plumbing System	3.9.1	G												
			SD-03 Product Data														
			Fixtures	2.5													
			Flush Valve Water Closets	2.5.2													
			Countertop Lavatories	2.5.4													
			Kitchen Sinks	2.5.5													
			Service Sinks	2.5.6													
			Water Heaters	2.10	G												
			Pumps	2.12	G												
			Backflow Prevention Assemblies	3.9.1.1	G												
			Welding	1.5.1													
			Vibration-Absorbing Features	3.4	G												
			Plumbing System	3.9.1													
			SD-06 Test Reports														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY					REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		MAILED TO CONTR/ DATE RCD FRM APPR AUTH
(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		22 00 00	Tests, Flushing and Disinfection	3.9													
			Test of Backflow Prevention Assemblies	3.9.1.1	G												
			SD-07 Certificates														
			Materials and Equipment	1.3													
			Bolts	2.2.1													
			SD-10 Operation and Maintenance Data														
			Plumbing System	3.9.1	G												
			SD-11 Closeout Submittals														
			Water-Efficient Products	2.1.1	S												
			Energy-Efficient Water Heaters	2.1.2	S												
		22 31 00	SD-02 Shop Drawings														
			Installation	3.2													
			SD-03 Product Data														
			Softening Equipment	2.2													
			Spare Parts	1.4													
			Field Instructions	3.3.2													
			SD-06 Test Reports														
			Softening Equipment	2.2													
			Piping	3.4.2													
			SD-10 Operation and Maintenance Data														
			Operating and Maintenance Instructions	3.3.2	G												
		23 00 00	SD-02 Shop Drawings														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		23 00 00	Detail Drawings	1.4.5	G													
			SD-03 Product Data															
			Metallic Flexible Duct	2.10.1.1														
			Insulated Nonmetallic Flexible Duct Runouts	2.10.1.2														
			Duct Connectors	2.10.1.2														
			Duct Access Doors	2.10.2	G													
			Manual Balancing Dampers	2.10.3	G													
			Diffusers	2.10.6.1														
			Registers and Grilles	2.10.6.2														
			Louvers	2.10.7														
			Air Vents, Penthouses, and Goosenecks	2.10.8														
			Centrifugal Fans	2.11.1.1														
			In-Line Centrifugal Fans	2.11.1.2														
			Panel Type Power Wall Ventilators	2.11.1.3														
			Air Handling Units	2.12	G													
			Variable Volume, Single Duct Terminal Units	2.15.1.1	G													
			Reheat Units	2.15.1.2	G													
			Radiant Heaters	2.13	G													
			Unit Heaters	2.14														
			Unit Heaters	3.3.2														
			Diagrams	1.2.1.2	G													
			SD-06 Test Reports															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		23 00 00	Performance Tests	3.13	G													
			Damper Acceptance Test	3.11	G													
			SD-07 Certificates															
			Bolts	1.4.1														
			Certification	1.4.6														
			Ozone Depleting Substances	1.4.3														
			SD-08 Manufacturer's Instructions															
			Manufacturer's Installation	3.3														
			Instructions															
			Operation and Maintenance	3.15.2														
			Training															
			SD-10 Operation and Maintenance															
			Data															
			Operation and Maintenance	3.15.1	G													
			Manuals															
			Manual Balancing Dampers	2.10.3	G													
			Centrifugal Fans	2.11.1.1	G													
			In-Line Centrifugal Fans	2.11.1.2	G													
			Panel Type Power Wall	2.11.1.3	G													
			Ventilators															
			Air Handling Units	2.12	G													
			Reheat Units	2.15.1.2	G													
			Radiant Heaters	2.13	G													
			Unit Heaters	2.14														
			Unit Heaters	3.3.2														
			SD-11 Closeout Submittals															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		23 00 00	Energy Efficient Equipment	2.1.1	S													
			Reduce Volatile Organic Compounds (VOC)	2.1.2	S													
			Indoor Air Quality During Construction	3.1	S													
			Ozone Depleting Substances for Refrigerants	2.1.3	S													
		23 05 15	SD-01 Preconstruction Submittals															
			Material, Equipment, and Fixture Lists	1.2	G													
			SD-02 Shop Drawings															
			Record Drawings	1.2	G													
			Connection Diagrams	1.2	G													
			Coordination Drawings	1.2	G													
			Fabrication Drawings	1.2	G													
			Installation Drawings	3.1	G													
			SD-03 Product Data															
			Pipe and Fittings	2.1	G													
			Piping Specialties	2.2	G													
			Valves	2.3	G													
			Miscellaneous Materials	2.4	G													
			Supporting Elements	2.5	G													
			Equipment Foundation Data	1.2	G													
			SD-04 Samples															
			Manufacturer's Standard Color Charts	1.2	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		23 05 15	SD-05 Design Data														
			Pipe and Fittings	2.1	G												
			Piping Specialties	2.2	G												
			Valves	2.3	G												
			SD-06 Test Reports														
			Hydrostatic Tests	3.1	G												
			Air Tests	3.1	G												
			Valve-Operating Tests	3.1	G												
			Drainage Tests	3.1	G												
			Pneumatic Tests	3.1	G												
			Non-Destructive Electric Tests	3.1	G												
			System Operation Tests	3.1	G												
			SD-07 Certificates														
			Record of Satisfactory Field Operation	1.4.2	G												
			List of Qualified Permanent Service Organizations	1.4.3	G												
			Listing of Product Installations	1.2	G												
			Records of Existing Conditions	1.2	G												
			Surface Resistance	3.1	G												
			Shear and Tensile Strengths	3.1	G												
			Temperature Ratings	3.1	G												
			Bending Tests	3.1	G												
			Flattening Tests	3.1	G												
			Transverse Guided Weld Bend Tests	3.1	G												

SUBMITTAL REGISTER

CONTRACT NO. _____

TITLE AND LOCATION
Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR _____

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		23 05 15	SD-10 Operation and Maintenance Data														
			Operation and Maintenance Manuals	3.10	G												
		23 05 93	SD-01 Preconstruction Submittals														
			Records of Existing Conditions	1.3.3	G RO												
			TAB Firm	1.5.3.1	G RO												
			TAB Team Assistants	1.2	G RO												
			TAB Team Engineer	1.2	G RO												
			TAB Specialist	1.5.3.2	G RO												
			TAB Team Field Leader	1.2	G RO												
			SD-02 Shop Drawings														
			TAB Schematic Drawings and Report Forms	1.3.3	G RO												
			SD-03 Product Data														
			Equipment and Performance Data	1.3	G RO												
			TAB Related HVAC Submittals	1.5.3.4	G RO												
			TAB Procedures	1.5.2	G RO												
			Calibration	1.5.2	G RO												
			Systems Readiness Check	1.3.3	G RO												
			TAB Execution	1.5.4	G RO												
			TAB Verification	1.5.4.3	G RO												
			SD-06 Test Reports														
			Completed Pre-Final DALT Report	3.3.5	G												

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		23 05 93	Certified Final DAL T Report	3.3.8	G													
			TAB Design Review Report	1.6.2.1	G													
			TAB Report for Season 1	1.5.5.2	G													
			TAB Report for Season 2	1.5.5.2	G													
			SD-07 Certificates															
			Independent TAB Agency and Personnel Qualifications	1.5.1	G PO													
			DAL T and TAB Submittal and Work Schedule	1.6.2	G PO													
			TAB Pre-Field Engineering Report	1.6.2.3	G PO													
			TAB Firm	1.5.3.1	G PO													
			Design Review Report	1.3.3	G PO													
			Pre-field DAL T Preliminary Notification	1.6.2.2	G													
			Advanced Notice for Season 1 TAB Field Work	1.6.2	G PO													
			Prerequisite HVAC Work Check Out List For Season 1	1.6.2	G PO													
			Advanced Notice for Season 2 TAB Field Work	1.6.2	G PO													
			Prerequisite HVAC Work Check Out List For Season 2	1.6.2	G PO													
		23 07 00	SD-02 Shop Drawings															
			MICA Plates	3.2.2.4	G PO													
			Pipe Insulation Systems	2.4														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		23 07 00	Pipe Insulation Systems	3.2													
			Duct Insulation Systems	3.3													
			Equipment Insulation Systems	3.4													
			SD-03 Product Data														
			Pipe Insulation Systems	2.4	G PO												
			Pipe Insulation Systems	3.2	G PO												
			Duct Insulation Systems	3.3	G PO												
			Equipment Insulation Systems	3.4	G PO												
			SD-04 Samples														
			Thermal Insulation	2.3.1.3	G PO												
			Display Samples	3.1.1	G PO												
			SD-08 Manufacturer's Instructions														
			Pipe Insulation Systems	2.4	G PO												
			Pipe Insulation Systems	3.2	G PO												
			Duct Insulation Systems	3.3	G PO												
			Equipment Insulation Systems	3.4	G PO												
			SD-11 Closeout Submittals														
			Reduce Volatile Organic Compounds (VOC)	2.1.1	S												
			Recycled Content	2.1.2	S												
		23 09 00	SD-02 Shop Drawings														
			DDC Contractor Design Drawings	3.2	G												
			Draft As-Built Drawings	3.2	G												
			Final As-Built Drawings	3.2	G												
			SD-03 Product Data														

SUBMITTAL REGISTER

CONTRACT NO. _____

TITLE AND LOCATION
Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR _____

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		23 09 00	Certificate of Networkiness Documentation	1.8.7	G													
			Programming Software	1.8.1	G													
			Controller Application Programs	1.8.2	G													
			Configuration Software	1.8.1	G													
			Manufacturer's Product Data	2.2	G													
			XIF files	2.2.1	G													
			Draft LNS Database	3.4.3	G													
			Final LNS Database	3.5.4	G													
			LNS Plug-ins	1.8.3	G													
			Niagara Framework Supervisory Gateway Backups	1.8.5	G													
			Niagara Framework Engineering Tool	1.8.6	G													
			Niagara Framework Wizards	1.8.4	G													
			SD-06 Test Reports															
			Start-Up Testing Report	3.4.2	G													
			PVT Procedures	3.5.1	G													
			PVT Report	3.5.3	G													
			Pre-Construction Quality Control (QC) Checklist	1.9.1	G													
			Post-Construction Quality Control (QC) Checklist	1.9.2	G													
			SD-10 Operation and Maintenance Data															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		23 09 00	Operation and Maintenance (O&M) Instructions	3.6	G												
			Training Documentation	3.7.1	G												
			SD-11 Closeout Submittals														
			Enclosure Keys	2.5	G												
			Password Summary Report	3.1.6.1	G												
			Closeout Quality Control (QC) Checklist	1.9.3	G												
		23 11 25	SD-02 Shop Drawings														
			Gas Piping System	1.5.3	G												
			Gas Piping System	2.2	G												
			Gas Piping System	3.3	G												
			SD-03 Product Data														
			Pipe and Fittings	1.6.1	G												
			Gas Equipment Connectors	1.5.3	G												
			Gas Piping System	1.5.3	G												
			Gas Piping System	2.2	G												
			Gas Piping System	3.3	G												
			Pipe Coating Materials	2.1	G												
			Pressure Regulators	2.6	G												
			Risers	2.4	G												
			Transition Fittings	2.2.12	G												
			Valves	2.3	G												
			Warning and Identification Tape	2.2.8	G												
			SD-06 Test Reports														
			Testing	3.19	G												

SUBMITTAL REGISTER

CONTRACT NO. _____

TITLE AND LOCATION
Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR _____

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		23 11 25	Pressure Tests	3.19.1	G													
			Pressure Tests for Liquefied Petroleum Gas	3.19.2	G													
			Test with Gas	3.19.3	G													
			SD-07 Certificates															
			Welders Procedures and Qualifications	1.5.1	G													
			Assigned Number, Letter, or Symbol	1.5.1	G													
			SD-08 Manufacturer's Instructions															
			PE Pipe and Fittings	1.5.2	G													
			Pipe Coating Materials	2.1	G													
			SD-10 Operation and Maintenance Data															
			Gas Facility System and Equipment Operation	1.3.1	G													
			Gas Facility System Maintenance	1.3.2	G													
			Gas Facility Equipment Maintenance	1.3.3	G													
		23 21 23	SD-02 Shop Drawings															
			System Coordination	2.1.2	G													
			SD-03 Product Data															
			Instructions	2.2.2	G													
			Equipment Data	2.2.5	G													
			Training Period	3.5.2	G													
			SD-06 Test Reports															

SUBMITTAL REGISTER

CONTRACT NO. _____

TITLE AND LOCATION
Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR _____

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION	
																		(g)
		23 21 23	Factory Tests	2.1.1														
			Field Quality Control	3.3														
			SD-07 Certificates															
			Manufacturer's Representative	1.3.1														
			SD-10 Operation and Maintenance Data															
			Operation and Maintenance Manuals	3.5.1	G													
			Training	3.5.2	G													
		23 23 00	SD-02 Shop Drawings															
			Refrigerant Piping System	2.3	G													
			SD-03 Product Data															
			Refrigerant Piping System	2.3														
			Spare Parts	1.5.2														
			Qualifications	1.3.1														
			Refrigerant Piping Tests	3.5														
			Verification of Dimensions	3.1														
			SD-06 Test Reports															
			Refrigerant Piping Tests	3.5														
			SD-07 Certificates															
			Service Organization	2.1														
			SD-10 Operation and Maintenance Data															
			Maintenance	1.5	G													
			Operation and Maintenance Manuals	3.4	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY					REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		MAILED TO CONTR/ DATE RCD FRM APPR AUTH
(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		23 23 00	Demonstrations	3.4	G												
		23 25 00	SD-03 Product Data														
			Water Analysis	2.5	G												
			Spare Parts	1.6													
			Field Instructions	3.4													
			Tests	3.5	G												
			Training Course	3.4	G												
		23 35 00	SD-02 Shop Drawings														
			Detail Drawings	1.4.1	G												
			Exhaust System Installation	3.4	G												
			SD-03 Product Data														
			Related Submittals	1.4.2													
			Ductwork Components	2.4	G												
			Materials and Equipment	2.1													
			Spare Parts	1.6													
			Field Instructions	3.6													
			Final Acceptance Tests	3.7													
			Onsite Training	3.6	G												
			Exhaust System Specialist	1.4.2	G												
			SD-06 Test Reports														
			Final Acceptance Tests	3.7													
			SD-07 Certificates														
			Inspection	3.3	G												
			SD-10 Operation and Maintenance Data														
			Exhaust System	1.2													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION	
																		(g)
		23 35 00	Operation and Maintenance Manuals	3.6														
		23 52 00	SD-02 Shop Drawings															
			Detail Drawings	1.5	G													
			SD-03 Product Data															
			Materials and Equipment	2.2.1														
			Spare Parts	1.5														
			Heating System Tests	3.9														
			Fuel System Tests	3.12														
			Welding	1.3														
			Qualifications	3.9														
			Field Instructions	3.11														
			Tests	3.5														
			SD-06 Test Reports															
			Heating System Tests	3.9														
			Fuel System Tests	3.12														
			SD-07 Certificates															
			Bolts	2.9.9.3														
			Energy Star	2.2.3														
			SD-10 Operation and Maintenance Data															
			Operation and Maintenance Instructions	3.11	G													
			SD-11 Closeout Submittals															
			Energy Efficient Equipment for Boilers	2.1	S													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		23 52 00	Indoor Air Quality During Construction	3.1	S													
		23 54 16	SD-02 Shop Drawings															
			Detail Drawings	1.3	G													
			Installation	3.2	G													
			SD-03 Product Data															
			Spare Parts	1.5														
			SD-06 Test Reports															
			Testing, Adjusting, and Balancing	3.4														
			SD-10 Operation and Maintenance Data															
			Operation and Maintenance Instructions	3.3														
		23 64 10	SD-03 Product Data															
			Water Chiller	2.10.2	G													
			Posted Instructions	3.2.3														
			Verification of Dimensions	1.5.1														
			Factory Tests	2.9														
			System Performance Tests	3.7														
			Demonstrations	3.8														
			Water Chiller - Field Acceptance Test Plan	3.6.1														
			SD-06 Test Reports															
			Field Acceptance Testing	3.6														
			Water Chiller - Field Acceptance Test Report	3.6.2														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		23 64 10	Factory Tests	2.9													
			System Performance Tests	3.7													
			SD-07 Certificates														
			Refrigeration System	3.2.9	G												
			SD-08 Manufacturer's Instructions														
			Water Chiller - Installation	3.2	G												
			Instructions														
			SD-10 Operation and Maintenance														
			Data														
			Operation and Maintenance	3.8	G												
			Manuals														
			SD-11 Closeout Submittals														
			Energy Efficient Equipment for	2.1.1	S												
			Chillers														
			Indoor Air Quality During	3.1.1	S												
			Construction														
			Ozone Depleting Substances	2.1.2	S												
		23 64 26	SD-03 Product Data														
			Grooved Mechanical Connections	2.2.2.4	G PO												
			For Steel														
			Grooved Mechanical Connections	2.4.3	G PO												
			For Copper														
			Calibrated Balancing Valves	2.5.8	G PO												
			Automatic Flow Control Valves	2.5.9	G PO												
			Pump Discharge Valve	2.5.10													
			Water Temperature Mixing Valve	2.5.11	G												

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY					REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		MAILED TO CONTR/ DATE RCD FRM APPR AUTH	
																		(g)
		23 64 26	Water Temperature Regulating Valves	2.5.12	G													
			Water Pressure Reducing Valve	2.5.13														
			Pressure Relief Valve	2.5.14														
			Combination Pressure and Temperature Relief Valves	2.5.15														
			Expansion Joints	2.6.9	G PO													
			Combination Strainer and Pump Suction Diffuser	2.6.3														
			Expansion Tanks	2.7														
			Air Separator Tanks	2.8														
			SD-06 Test Reports															
			Piping Welds NDE Report	3.1.1.3														
			Pressure Tests Reports	3.5.2	G PO													
			SD-07 Certificates															
			Employer's Record Documents (For Welding)	3.1.1.1														
			Welding Procedures and Qualifications	3.1.1.2														
			SD-08 Manufacturer's Instructions															
			Lesson plan for the Instruction Course	3.6	G PO													
			SD-10 Operation and Maintenance Data															
			Calibrated Balancing Valves	2.5.8	G PO													
			Automatic Flow Control Valves	2.5.9	G PO													

SUBMITTAL REGISTER

CONTRACT NO. _____

TITLE AND LOCATION
Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR _____

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		23 64 26	Pump Discharge Valve	2.5.10	G PO													
			Water Temperature Mixing Valve	2.5.11	G PO													
			Water Temperature Regulating Valves	2.5.12	G PO													
			Water Pressure Reducing Valve	2.5.13	G PO													
			Pressure Relief Valve	2.5.14	G PO													
			Combination Pressure and Temperature Relief Valves	2.5.15	G PO													
			Expansion Joints	2.6.9	G PO													
			Combination Strainer and Pump Suction Diffuser	2.6.3	G PO													
			Expansion Tanks	2.7	G PO													
			Air Separator Tanks	2.8	G PO													
		23 82 02	SD-02 Shop Drawings															
			Drawings	1.4														
			SD-03 Product Data															
			Materials and Equipment	2.1														
			Spare Parts	1.6														
			Posted Instructions	3.4														
			Verification of Dimensions	3.1														
			Coil Corrosion Protection	2.8.1.1														
			System Performance Tests	3.6														
			Demonstrations	3.4	G													
			SD-06 Test Reports															
			Refrigerant Tests, Charging, and Start-Up	3.5	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		23 82 02	System Performance Tests	3.6	G												
			SD-07 Certificates														
			Materials and Equipment	2.1													
			Service Organization	2.1.1													
			SD-10 Operation and Maintenance Data														
			Operation and Maintenance Manuals	3.4	G												
		25 05 11	SD-01 Preconstruction Submittals														
			Wireless Communication Request	3.1.5.3	G												
			Device Account Lock Exception Request	3.1.2.2	G												
			Multiple IP Connection Device Request	3.9	G												
			Contractor Computer Cybersecurity Compliance Statements	1.10.1.4	G												
			Contractor Temporary Network Cybersecurity Compliance Statements	1.10.6	G												
			Control System Cybersecurity Subject Matter Expert	1.7.1	G												
			SD-02 Shop Drawings														
			User Interface Banner Schedule	3.1.3.1													
			Network Communication Report	1.8.2	G												

SUBMITTAL REGISTER

CONTRACT NO. _____

TITLE AND LOCATION
Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR _____

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		25 05 11	Cybersecurity Riser Diagram	1.8.5	G													
			Control System Inventory Report	1.8.3	G													
			Cybersecurity Interconnection Schedule	1.8.1	G													
			SD-03 Product Data															
			Control System Cybersecurity Documentation	1.8.6	G													
			SD-06 Test Reports															
			Wireless Communication Test Report	3.1.5.4	G													
			SD-07 Certificates															
			Software Licenses	1.9	G													
			SD-11 Closeout Submittals															
			Password Summary Report	3.5.2.2.5														
			Software Recovery And Reconstitution Images	1.8.4														
			Device Audit Record Upload Software	3.2.2.1														
		25 08 10	SD-06 Test Reports															
			Building Level DDC Testing Sequence	3.1														
			Performance Verification Test	3.5	G													
		26 05 48	SD-02 Shop Drawings															
			Lighting Fixtures in Buildings	3.1														
			Equipment Requirements	1.3														
			SD-03 Product Data															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		26 05 48	Lighting Fixtures in Buildings	3.1														
			Equipment Requirements	1.3														
			Contractor Designed Bracing	1.2.4														
		26 08 00	SD-06 Test Reports															
			Acceptance tests and inspections	3.1	G													
			SD-07 Certificates															
			Qualifications	1.4.1	G													
			Acceptance test and inspections procedure	1.4.3	G													
		26 20 00	SD-02 Shop Drawings															
			Panelboards	2.15	G													
			Transformers	2.19	G													
			Busway	2.4	G													
			Cable trays	2.5	G													
			Wireways	2.31														
			Marking strips	3.1.12.1														
			SD-03 Product Data															
			Receptacles	2.14														
			Circuit breakers	2.15.3														
			Switches	2.12														
			Transformers	2.19	G													
			Enclosed circuit breakers	2.17														
			Motor controllers	2.21														
			Manual motor starters	2.22														
			Metering	2.32														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		26 20 00	Electric Vehicle Supply Equipment	2.16														
			Electric Vehicle Supply Equipment	3.1.19														
			Grounding Busbar	2.25.3														
			Surge protective devices	2.33														
			SD-06 Test Reports															
			600-volt wiring test	3.5.2														
			Grounding system test	3.5.5														
			Transformer tests	3.5.3														
			Ground-fault receptacle test	3.5.4														
			SD-07 Certificates															
			Fuses	2.13														
			SD-09 Manufacturer's Field Reports															
			Transformer factory tests	2.35.1														
			SD-10 Operation and Maintenance Data															
			Electrical Systems	1.5.1														
			Metering	2.32														
			Electric Vehicle Supply Equipment	2.16														
			Electric Vehicle Supply Equipment	3.1.19														
		26 27 13.10	SD-03 Product Data															
			Power Meters	2.1	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		26 27 13.10	Current Transformers	3.3.1.2														
			Potential Transformer	2.1.2														
			Communications Module	2.2.2														
			Protocol Modules	1.6.1														
			Data Recorder	1.6.2														
			Modem	1.6.2														
			SD-06 Test Reports															
			Acceptance Checks and Tests	3.3.1														
			SD-10 Operation and Maintenance Data															
			Power Meters	2.1														
			Communications Module	2.2.2														
			Protocol Modules	1.6.1														
			Data Recorder	1.6.2														
			Modem	1.6.2														
			SD-11 Closeout Submittals															
			System Function Verification	3.3.2														
		26 28 01	SD-03 Product Data															
			Fault Current Analysis	2.9														
			Protective Device Coordination Study	2.9														
			Equipment	2.1														
			System Coordinator	1.4.1														
			Protective Relays	3.3.4														
			Installation	3.2														
			SD-06 Test Reports															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY					REMARKS			
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE		DATE OF ACTION	MAILED TO CONTR/	DATE RCD FRM APPR AUTH
		26 28 01	Field Testing	3.3															
			SD-07 Certificates																
			Devices and Equipment	1.6															
		26 29 23	SD-02 Shop Drawings																
			Schematic diagrams	1.5.1															
			Interconnecting diagrams	1.5.2															
			Installation drawings	1.5.3															
			SD-03 Product Data																
			Variable frequency drives	2.1	G														
			Wires and cables	2.3															
			Equipment schedule	1.5.4															
			SD-06 Test Reports																
			VFD Test	3.2.1															
			Performance Verification Tests	3.2.2															
			Endurance Test	3.2.3															
			SD-08 Manufacturer's Instructions																
			Installation instructions	1.5.5															
			SD-09 Manufacturer's Field Reports																
			VFD Factory Test Plan	2.5.1															
			Factory test results	1.5.6															
			SD-10 Operation and Maintenance Data																
			Variable frequency drives	2.1															
		26 31 00	SD-02 Shop Drawings																
			Schematic Diagrams	2.9	G														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		26 31 00	Interconnection Diagrams	2.9	G													
			Installation Drawings	3.1	G													
			SD-03 Product Data															
			Combiner Boxes	2.4														
			Disconnects	3.1.3	G													
			Inverters	2.3	G													
			String Inverter CEC Efficiency	2.3.1	G													
			Ground Mounting Structure for Modules	2.5	G													
			Photovoltaic Module Backsheet	2.2.1														
			Photovoltaic Module Encapsulent	2.2.2														
			Photovoltaic Modules	2.2	G													
			Photovoltaic Wire	2.2	G													
			System Monitoring	2.7	G													
			SD-05 Design Data															
			System Operation	1.6.3	G													
			Calculations	1.9	G													
			System Performance	1.6.10	G													
			Calculations															
			SD-06 Test Reports															
			NABCEP Acceptance Checks and Tests	3.9.1	G													
			NETA Acceptance Checks and Tests	3.9.2	G													
			SD-07 Certificates															
			Installer	1.6.4	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		26 31 00	Materials	1.6.5	G													
			Warranty	1.8	G													
			Cybersecurity Equipment	1.6.6	G													
			Certification															
			Cybersecurity Installation	3.9.4	G													
			Certification															
			SD-08 Manufacturer's Instructions															
			Installation Instructions	3.1	G													
			SD-10 Operation and Maintenance															
			Data															
			Electrical Systems	1.6.7.1	G													
			Training Course	1.6.7.2	G													
		26 41 00	SD-02 Shop Drawings															
			Overall lightning protection	1.4.1.1	G													
			system															
			Each major component	1.4.1.2	G													
			SD-06 Test Reports															
			Lightning Protection and	1.4.3														
			Grounding System Test Plan															
			Lightning Protection and	3.5.1	G													
			Grounding System Test															
			SD-07 Certificates															
			Lightning Protection System	1.2.3	G													
			Installers Documentation															
			Component UL Listed and	1.4.2														
			Labeled															

SUBMITTAL REGISTER

CONTRACT NO. _____

TITLE AND LOCATION
Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR _____

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		26 41 00	Lightning protection system inspection certificate	1.4.4	G													
			Roof manufacturer's warranty	3.1.1														
		26 42 14	SD-02 Shop Drawings															
			Drawings	1.3.6														
			Contractor's Modifications	2.1.1	G													
			SD-03 Product Data															
			Equipment	2.1														
			Spare Parts	1.5														
			SD-06 Test Reports															
			Tests and Measurements	3.5														
			Contractor's Modifications	2.1.1														
			SD-07 Certificates															
			Cathodic Protection System	2.1														
			Services of 'Corrosion Expert'	1.3.1														
			SD-10 Operation and Maintenance Data															
			Cathodic Protection System	2.1														
			Training Course	3.6														
		26 51 00	SD-02 Shop Drawings															
			Luminaire Drawings	1.5.1	G													
			Occupancy/Vacancy Sensor Coverage Layout	1.5.2	G													
			SD-03 Product Data															
			Luminaires	2.2	G													
			Light Sources	2.4	G													

SUBMITTAL REGISTER

CONTRACT NO. _____

TITLE AND LOCATION
Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR _____

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		26 51 00	Drivers, Ballasts and Generators	2.3													
			LED Luminaire Warranty	1.6.1													
			Luminaire Design Data	1.5.4													
			Vacancy Sensors	2.5.3.2													
			Dimming Controllers (Dimmers)	2.5.2													
			Lighting Contactor	2.5.4													
			Timeswitch	2.5.5													
			Power Hook Luminaire Hangers	2.8													
			Exit Signs	2.6.1													
			LED Emergency Drivers	2.6.2													
			Occupancy Sensors	2.5.3.1													
			Ambient Light Level Sensor	3.1.8													
			Lighting Control Panel	2.5.6	G												
			SD-06 Test Reports														
			LED Luminaire - IES LM-79 Test Report	1.5.5													
			LED Light Source - IES LM-80 Test Report	1.5.6													
			LED Light Source - IES TM-21 Test Report	1.5.7													
			Occupancy/Vacancy Sensor Verification Tests	1.5.8	G												
			Energy Efficiency	1.5.11.3													
			SD-07 Certificates														
			Luminaire Useful Life Certificate	1.6.1.1	G												

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		26 51 00	LED Driver and Dimming Switch Compatibility Certificate	1.5.3	G													
		26 56 00	SD-01 Preconstruction Submittals															
			Photometric Plan	1.5.3	G													
			LED Luminaire Warranty	1.7.1	G													
			SD-02 Shop Drawings															
			Luminaire drawings	1.5.2.1	G													
			Poles	1.5.2.2	G													
			SD-03 Product Data															
			LED Luminaires	2.2	G													
			Luminaire Light Sources	2.2.2	G													
			Luminaire Power Supply Units (Drivers)	2.2.3	G													
			Lighting contactor	2.3.3														
			Time switch	2.3.2														
			Lighting Control Relay Panel	2.3.4	G													
			Motion Sensor	2.3.5														
			Photocell	2.3.1														
			Aluminum poles	2.4.1	G													
			SD-05 Design Data															
			Design Data for luminaires	1.5.4	G													
			SD-06 Test Reports															
			LED Luminaire - IES LM-79 Test Report	1.5.5														
			LED Light Source - IES LM-80 Test Report	1.5.6														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION	
																		(g)
		26 56 00	Operating test	3.2														
			SD-07 Certificates															
			Luminaire Useful Life Certificate	1.7.1														
			SD-10 Operation and Maintenance Data															
			Operational Service	1.8														
		27 05 14.00 10	SD-02 Shop Drawings															
			Cable TV Premises Distribution System	1.2														
			Installation	3.1														
			SD-03 Product Data															
			Spare Parts	1.7														
			Test Plan	3.4														
			Qualifications	1.4														
			SD-06 Test Reports															
			Testing	3.4														
			SD-07 Certificates															
			Materials and Equipment	2.1														
			SD-08 Manufacturer's Instructions															
			Manufacturer's Recommendations	3.1.1														
			SD-10 Operation and Maintenance Data															
			Operation and Maintenance Manuals	3.5														
		27 05 28.36	SD-02 Shop Drawings															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		27 05 28.36	Fabrication Drawings	2.2	G												
			Installation Drawings	3.1.2	G												
			SD-03 Product Data														
			Cable Trays	2.1	G												
			Supports	2.3.1													
			SD-08 Manufacturer's Instructions														
			Manufacturer's Instructions	3.1.1													
		27 10 00	SD-02 Shop Drawings														
			Telecommunications drawings	1.5.1.1	G												
			Telecommunications Space Drawings	1.5.1.2	G												
			SD-03 Product Data														
			Telecommunications cabling	2.3													
			Patch panels	2.4.3	G												
			Telecommunications outlet/connector assemblies	2.5													
			Equipment support frame	2.4.2													
			Connector blocks	3.1.6.1													
			Spare Parts	1.9.3	G												
			SD-06 Test Reports														
			Telecommunications cabling testing	3.5.1													
			SD-07 Certificates														
			Telecommunications Contractor	1.5.2.1													
			Key Personnel	1.5.2.2	G												
			Manufacturer Qualifications	1.5.2.3													

SUBMITTAL REGISTER

CONTRACT NO. _____

TITLE AND LOCATION
Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR _____

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY					REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		MAILED TO CONTR/ DATE RCD FRM APPR AUTH	
																		(g)
		27 10 00	Test plan	1.5.3														
			SD-09 Manufacturer's Field Reports															
			Factory reel tests	2.11.1	G													
			SD-10 Operation and Maintenance Data															
			Telecommunications cabling and pathway system	1.9.1														
			SD-11 Closeout Submittals															
			Record Documentation	1.9.2														
		27 13 23	SD-01 Preconstruction Submittals															
			Qualifications	1.3.1	G													
			Quality Assurance Plan	1.3.1	G													
			SD-02 Shop Drawings															
			Fiber Optic System Contract Drawings	1.3.1														
			Detailed Shop Drawings	1.3.1														
			Record (As-Built) Drawings	3.3														
			SD-03 Product Data															
			Optical Fibers	1.3.1														
			Fiber Optic Cable Design	1.3.1														
			Splice Organizers	1.3.1														
			Pre-Connected Cable Assembly	1.3.1														
			Fiber Optic Terminal Cabinets	1.3.1														
			Fiber Optic Terminal Cabinets	2.2.5														
			Optical Patch Panel Assemblies	1.3.1														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		27 13 23	Fiber Optic Media Types	1.3.1													
			Fiber Optic Terminations and Connectors	1.3.1													
			Fiber Optic Enclosures	1.3.1													
			SD-06 Test Reports														
			Factory Test Certificates	2.4.2													
			Single and Multi-Mode OTDR Test	3.2.1.1													
			End-to-End Attenuation Tests	3.2.1.2													
			End-to-End Bandwidth Tests	3.2.1.3													
			Fiber Optic Factory Test Plan	1.5.4													
			Fiber Optic Field Tests Plan	1.5.5													
			SD-07 Certificates														
			Fiber Optic Cable Installer and Splicer Qualifications	1.3.1													
			Manufacturer's Qualifications	1.3.1													
			SD-08 Manufacturer's Instructions														
			Fiber Optic System Instructions	1.3.1													
		27 51 16	SD-02 Shop Drawings														
			Detail Drawings	2.1.4	G												
			SD-03 Product Data														
			Spare Parts	1.4													
			SD-06 Test Reports														
			Approved Test Procedures	3.5													
			Acceptance Tests	3.5													
			SD-07 Certificates														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		27 51 16	Components	2.2													
			SD-10 Operation and Maintenance Data														
			Radio and Public Address System	2.1	G												
		28 08 10	SD-05 Design Data														
			Test Plan	3.1	G												
			SD-06 Test Reports														
			Draft Test Report	3.2.2													
			Final Test Report	3.4	G												
			SD-07 Certificates														
			Qualifications	1.4.1													
		28 10 05	SD-02 Shop Drawings														
			ESS Components	1.3.3.1	G												
			Overall System Schematic	1.3.3.2	G												
			SD-03 Product Data														
			Access Control Unit	2.4.4	G												
			Access Control Devices	2.4.5	G												
			Cameras	2.5.1	G												
			Camera Lenses	2.5.1.2													
			Camera Housing and Mounts	2.5.1.4													
			Video Recording	2.5.4.3													
			Communications Interface	2.7													
			Devices														
			Network Switch	2.7.3													
			Video and ESS Transmission	2.7.4													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		28 10 05	Uninterruptible Power Supply (UPS)	2.9.1	G													
			Component Enclosure	2.11														
			Equipment Rack	2.12														
			SD-05 Design Data															
			Backup Battery Capacity Calculations	1.5.1	G													
			Throughput Rates	2.4.2														
			CCTV Storage Calculations	1.5.2														
			SD-07 Certificates															
			Contractor Qualifications	1.3.4.1														
			Instructor Qualifications	1.3.4.2														
			SD-10 Operation and Maintenance Data															
			Training Plan	3.6.1														
			Training Content	3.6														
			ESS Components	1.3.3.1														
			ESS Software	1.6														
			SD-11 Closeout Submittals															
			As-Built Drawings	1.7	G													
		28 31 49	SD-03 Product Data															
			Carbon monoxide detector	2.1														
			SD-06 Test Reports															
			Carbon monoxide detector test	3.2.1														
			SD-10 Operation and Maintenance Data															

SUBMITTAL REGISTER

CONTRACT NO. _____

TITLE AND LOCATION
Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR _____

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		28 31 49	Carbon monoxide detector	2.1														
		28 31 76	SD-02 Shop Drawings															
			Nameplates	2.1.2														
			Instructions	2.14.9														
			Wiring Diagrams	3.3.1	G													
			System Layout	1.2.1	G													
			System Operation	2.3	G													
			Notification Appliances	2.18	G													
			Amplifiers	2.15														
			SD-03 Product Data															
			Technical Data And Computer Software	1.6														
			Fire Alarm Control Unit and Mass Notification Control Unit (FMCP)	2.13														
			Terminal Cabinets	3.3.2														
			Manual Stations	2.17														
			Transmitters	2.20														
			Batteries	2.12.1														
			Battery Chargers	2.12.2														
			Smoke Sensors	2.10														
			Notification Appliances	2.18	G													
			Addressable Interface Devices	2.7	G													
			Amplifiers	2.15														
			Tone Generators	2.15														
			Digitalized Voice Generators	2.15														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION			
																		(g)
		28 31 76	Remote Fire Alarm/Mass Notification Control Units	2.14	G													
			Radio Transmitter and Interface Panels	2.20.1	G													
			Digital Alarm Communicator Transmitter (DACT)	2.20.2	G													
			Local Operating Console (LOC)	1.4.4	G													
			SD-05 Design Data															
			Battery Power	2.12.1.2	G													
			Battery Chargers	2.12.2	G													
			Voltage Drop Calculations	2.3.1														
			SD-06 Test Reports															
			Field Quality Control	3.6														
			Testing Procedures	3.6.1	G													
			Smoke Sensor Testing	2.10.3	G													
			SD-07 Certificates															
			Installer	1.7.1.4														
			Formal Inspection and Tests	3.6.2.2														
			Final Testing	3.6.2.3														
			Designer Qualifications	1.7.1.1	G													
			SD-09 Manufacturer's Field Reports															
			System Operation	2.3														
			Fire Alarm/Mass Notification System	1.7.2.2														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		28 31 76	SD-10 Operation and Maintenance Data														
			Operation and Maintenance (O&M) Instructions	3.9													
			Instruction of Government Employees	3.7													
			SD-11 Closeout Submittals														
			As-Built Drawings	3.6.2.4													
		31 00 00	SD-01 Preconstruction Submittals														
			Shoring	3.2	G												
			Dewatering Work Plan	1.3.3	G												
			SD-03 Product Data														
			Utilization of Excavated Materials	3.6	G												
			Shoulder Construction	3.12													
			SD-06 Test Reports														
			Testing	3.14													
			Borrow Site Testing	2.1													
			SD-07 Certificates														
			Testing	3.14													
		31 11 00	SD-03 Product Data														
			Tree Wound Paint	2.1.1													
		32 01 19.61	SD-03 Product Data														
			Sealants	2.1	G												
			Manufacturer's Recommendations	Part 3	G												

SUBMITTAL REGISTER

CONTRACT NO. _____

TITLE AND LOCATION
Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR _____

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION	
																		(g)
		32 01 19.61	Manufacturer's Recommendations	3.5.2	G													
			SD-04 Samples															
			Sealants	2.1														
			Blocking Media/Backup Materials	2.3.1														
			Backer Rod	3.3.3.1														
			Bond Breaking Tapes	2.3.2														
			SD-06 Test Reports															
			Sealant	1.3.1														
			SD-07 Certificates															
			Equipment List	3.1														
			SD-08 Manufacturer's Instructions															
			Sealants	2.1														
		32 11 20	SD-03 Product Data															
			Plant, Equipment, and Tools	1.4	G													
			SD-06 Test Reports															
			Initial Tests	2.2.1	G													
			In-Place Tests	3.12.1	G													
		32 11 23	SD-03 Product Data															
			Plant, Equipment, and Tools	1.4	G													
			SD-06 Test Reports															
			Initial Tests	2.3.1	G													
			In-Place Tests	3.12.1	G													
		32 12 10	SD-06 Test Reports															
			Sampling and Testing	3.7														
		32 12 17	SD-04 Samples															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY					REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		MAILED TO CONTR/ DATE RCD FRM APPR AUTH	
																		(g)
		32 12 17	Bituminous pavement	1.6.1.6														
			SD-05 Design Data															
			Job-mix formula	1.3.2														
			Asphalt Cement Binder	2.2														
			Mix Design	2.3														
			SD-06 Test Reports															
			Specific gravity test of asphalt	2.4.1														
			Coarse aggregate tests	2.4.1														
			Percent of crushed pieces in gravel	2.4.1														
			Fine aggregate tests	2.4.1														
			Specific gravity of mineral filler	2.4.1														
			Bituminous mixture tests	2.4.1														
			Aggregates tests	3.5.2.1														
			Bituminous mix tests	3.5.2.2														
			Pavement courses	3.5.2.3														
		32 12 18	SD-04 Samples															
			Open Graded Asphalt Job Mix Formula	2.7.1														
			Job Mix Formula for Slurry Grout	2.7.2														
			SD-06 Test Reports															
			Coarse Aggregate	2.2.1	G													
			Coarse and Fine Aggregates	2.2	G													
			Open-Graded Mix Aggregate	2.2.3	G ERDC													
			Bituminous Material	2.3	G													
			Slurry Grout Sand	2.2.4	G ERDC													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		32 12 18	Filler (Fly Ash)	2.2.5	G ERDC													
			Job Mix Formula for Slurry Grout	2.7.2	G ERDC													
			Contractor Quality Control	3.13	G													
			SD-07 Certificates															
			Cement	2.4	G													
			Cross Polymer Resin	2.5	G													
			Curing Compound	2.6	G													
		32 13 13.06	SD-01 Preconstruction Submittals															
			Joint, Dowel and Reinforcement	2.2.1	G													
			Layout Drawings															
			SD-03 Product Data															
			Curing Materials	2.1.6														
			Reinforcement	2.1.5.3														
			Epoxy Resin	2.1.8														
			Epoxy Resin	2.1.8														
			Dowel Bars	2.1.5.1														
			Expansion Joint Filler	2.1.9.1														
			Cementitious Materials	2.1.1														
			SD-04 Samples															
			Test Section	1.7.2	G													
			SD-05 Design Data															
			Mix Design Report	2.3.2	G													
			SD-06 Test Reports															
			Concrete Slump Tests	3.8.2	G													
			Concrete Uniformity	2.4.1	G													
			Flexural Strength	3.8.3	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		32 13 13.06	Air Content	3.8.4	G												
			Surface Smoothness Report	3.8.5	G												
			Repair Recommendations Plan	3.7.1	G												
			SD-07 Certificates														
			Batch Tickets	1.5.3													
			NRMCA Certificate Of Conformance	1.5.1													
			SD-08 Manufacturer's Instructions														
			Diamond Grinding Plan	3.8.5.4													
		32 16 13	SD-03 Product Data														
			Concrete	2.1													
			Biodegradable Form Release Agent	2.6.3													
			Biodegradable Form Release Agent	3.2													
			SD-06 Test Reports														
			Field Quality Control	3.8													
		32 17 23	SD-03 Product Data														
			Surface Preparation Equipment List	2.1.1	G												
			Application Equipment List	2.1.2	G												
			Exterior Surface Preparation	3.2													
			Safety Data Sheets	1.3.1	G												
			Reflective media for roads	2.2.7.1	G												
			Waterborne Paint	2.2.1	G												
			Solventborne Paint	2.2.2	G												

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		32 17 23	SD-06 Test Reports														
			Reflective Media for Roads	2.2.7.1	G												
			Waterborne Paint	2.2.1	G												
			Solventborne Paint	2.2.2	G												
			High Build Acrylic Coating (HBAC)	2.2.6	G												
			Thermoplastic Compound	2.2.5	G												
			Test Reports	3.4.1													
			SD-07 Certificates														
			Qualifications	1.3.2	G												
			Reflective Media for Roads	2.2.7.1													
			Waterborne Paint	2.2.1													
			Solventborne Paint	2.2.2													
			Volatile Organic Compound	1.3.1	G												
			Volatile Organic Compound	2.2.6	G												
			SD-08 Manufacturer's Instructions														
			Waterborne Paint	2.2.1	G												
			Solventborne Paint	2.2.2	G												
		32 31 13.53	SD-02 Shop Drawings														
			Fence Installation	1.3.2													
			Fence Installation	3.1													
			Installation Drawings	1.3.2													
			Location of gate, corner, end, and pull posts	1.3.2													
			Gate Assembly	1.3.2													
			Gate Assembly	2.6.1													

SUBMITTAL REGISTER

CONTRACT NO. _____

TITLE AND LOCATION
Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR _____

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		32 31 13.53	Gate Assembly	2.6.1														
			Turnstiles	1.3.2														
			Gate Hardware and Accessories	1.3.2														
			Gate Hardware and Accessories	2.6.3														
			SD-03 Product Data															
			Fence Installation	1.3.2														
			Fence Installation	3.1														
			Gate Assembly	1.3.2														
			Gate Assembly	2.6.1														
			Gate Assembly	2.6.1														
			Gate Hardware and Accessories	1.3.2														
			Gate Hardware and Accessories	2.6.3														
			SD-04 Samples															
			Fabric	2.1.1														
			Posts	2.2														
			Post Caps	2.2.2														
			Braces	2.3														
			Line Posts	2.3														
			Bottom Rail	3.3														
			Tension Wire	2.4.3														
			Barbed Wire	2.4.2														
			Barbed Wire Supporting Arms	2.2.2														
			Stretcher Bars	2.1.1														
			Gate Posts	2.1.1														
			Gate Hardware and Accessories	1.3.2														
			Gate Hardware and Accessories	2.6.3														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		32 31 13.53	Turnstiles	1.3.2														
			Padlocks	2.7														
			Wire Ties	2.4.1														
			SD-06 Test Reports															
			zinc coating	1.3.1														
			PVC coating	1.3.1														
			Aluminum Alloy Coating	1.3.1														
			SD-07 Certificates															
			Chain Link Fence	2.2.1														
			Reports	1.3.1														
			Zinc Coating	1.3.1														
			PVC coating	1.3.1														
			aluminum alloy coating	1.3.1														
			Fabric	2.1.1														
			Barbed Wire	2.4.2														
			Stretcher Bars	2.1.1														
			Gate Hardware and Accessories	1.3.2														
			Gate Hardware and Accessories	2.6.3														
			Concrete	2.5														
			Gate Operator	2.8														
			SD-08 Manufacturer's Instructions															
			Fence Installation	1.3.2														
			Fence Installation	3.1														
			Gate Assembly	1.3.2														
			Gate Assembly	2.6.1														
			Gate Assembly	2.6.1														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		32 31 13.53	Hardware Assembly	3.6														
			Accessories	1.3.1														
			SD-10 Operation and Maintenance Data															
			Electro-Mechanical Locks	2.9														
			Gate Operator	2.8														
			operating and maintenance instructions	3.6														
		33 08 55	SD-01 Preconstruction Submittals															
			Commissioning Plan	1.4	G													
			SD-06 Test Reports															
			Piping Flushing Checklist	3.4.3	G													
			Control Valve Checklist	3.5.1	G													
			Commissioning Report	1.6	G													
			SD-07 Certificates															
			Certification of Completion	1.5														
			Disposal of Waste Materials	1.7														
		33 11 00	SD-03 Product Data															
			Pipe, Fittings, Joints and Couplings	2.2	G													
			Valves	2.3	G													
			Indicator Posts	2.3.3	G													
			Valve Boxes	2.3.4	G													
			Hydrants	2.4.1	G													
			Pipe Anchorage	2.2.4	G													
			Tapping Sleeves	2.5.1	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		33 11 00	Fire Department Connections	2.5.7	G												
			SD-06 Test Reports														
			Bacteriological Samples	3.2.6	G												
			SD-07 Certificates														
			Pipe, Fittings, Joints and Couplings	2.2													
			Lining	2.2.1.1													
			Lining for Fittings	2.2.2.1.1													
			Valves	2.3													
			Hydrants	2.4.1													
			Disinfection Procedures	3.2.6													
			SD-08 Manufacturer's Instructions														
			Manufacturer's Instructions	3.2.1													
		33 30 00	SD-01 Preconstruction Submittals														
			Existing Conditions	1.6													
			Request For Field Support	3.1.1													
			Request For Pre-Connection Inspection	3.1.1													
			SD-02 Shop Drawings														
			Drawings	1.4.2													
			Precast Concrete Manhole	2.3.1													
			Metal Items	2.3.4													
			Frames, Covers, and Gratings	2.3.4.1													
			SD-03 Product Data														
			Pipeline Materials	2.1													
			SD-06 Test Reports														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		33 30 00	Reports	2.4														
			SD-07 Certificates															
			Portland Cement	2.2.2														
			Gaskets	2.1.3.2														
		33 40 00	SD-04 Samples															
			Pipe for Culverts and Storm Drains	2.1														
			SD-07 Certificates															
			Oil Resistant Gasket	2.3.7.1														
			Leakage Test	3.9.3.1														
			Hydrostatic Test on Watertight Joints	3.9.1.1														
			Determination of Density	3.9.1.2														
			Frame and Cover for Gratings	2.3.6														
			Post-Installation Inspection Report	3.9.2.1.2														
			SD-08 Manufacturer's Instructions															
			Placing Pipe	3.3														
		33 51 13	SD-03 Product Data															
			Pressure Regulator	2.3.3	G													
			Valves	2.3														
			Risers	2.2.2														
			Transition Fittings	2.2.3														
			Gas Meter	2.4	G													
			SD-07 Certificates															
			Welder's Qualifications	1.3.1														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY					REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		MAILED TO CONTR/ DATE RCD FRM APPR AUTH	
																		(g)
		33 51 13	Welder's Identification Symbols	1.3.1														
		33 51 15	SD-02 Shop Drawings															
			Pipe, Fittings, and Associated Materials	2.1														
			SD-03 Product Data															
			Materials and Equipment	2.1	G													
			Spare Parts	1.6	G													
			Pipe and Accessory Coatings	2.1	G													
			SD-05 Design Data															
			Connections to Existing Lines	3.12	G													
			Connection and Abandonment Plan	1.4.2.2	G													
			SD-06 Test Reports															
			Pressure and Leak Tests	3.13.2														
			SD-07 Certificates															
			Welder's training, qualifications and procedures	1.4.1.1														
			Jointing of Polyethylene Piping	1.4.1.2														
			Utility Work	3.12.1														
			SD-10 Operation and Maintenance Data															
			Gas Distribution System and Equipment Operation	3.14.1	G													
			Gas Distribution System Maintenance	3.14.2	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY					REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		MAILED TO CONTR/ DATE RCD FRM APPR AUTH
(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		33 51 15	Gas Distribution Equipment Maintenance	3.14.3	G												
		33 56 10	SD-02 Shop Drawings														
			Grounding and Bonding	2.3.2													
			SD-03 Product Data														
			Aboveground Storage Tank	2.4	G												
			Tank Protective Coatings	2.5													
			Automatic Level Alarm System	2.7													
			Tank Gauges	2.8													
			Tank Mounted Fuel Dispensing Unit	2.9													
			SD-06 Test Reports														
			Aboveground Storage Tank Tightness Tests	3.2.1	G												
			Tank Manufacturer's Tests	3.2.2													
			Tank Fill Tests	3.4													
			SD-07 Certificates														
			Contractor Qualifications	1.4.1	G												
			Permitting	1.4.2.1													
			Registration	1.4.2.2													
			Licensed Personnel	1.4.2.3													
			Demonstrations	3.3													
			SD-08 Manufacturer's Instructions														
			Aboveground Storage Tank	2.4													
			Automatic Level Alarm System	2.7													
			Tank Gauges	2.8													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		33 56 10	SD-10 Operation and Maintenance Data															
			Aboveground Storage Tank	2.4	G													
			Automatic Level Alarm System	2.7	G													
			Tank Gauges	2.8	G													
		33 58 00	SD-02 Shop Drawings															
			Leak Detection System	2.3	G													
			Electronic Monitoring/Alarm Panel	2.4														
			SD-03 Product Data															
			Leak Detection System	2.3	G													
			Electronic Monitoring/Alarm Panel	2.4														
			SD-06 Test Reports															
			Leak Detection System Test	3.2.1														
			SD-07 Certificates															
			Demonstrations	3.3														
			SD-08 Manufacturer's Instructions															
			Leak Detection System	2.3														
			SD-10 Operation and Maintenance Data															
			Leak Detection System	2.3	G													
			Electronic Monitoring/Alarm Panel	2.4	G													
		33 71 02	SD-02 Shop Drawings															
			Aluminum conductors	2.2.1	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS		
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/	DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER			ACTION CODE	DATE OF ACTION
		33 71 02	Precast underground structures	1.5.1	G													
			SD-03 Product Data															
			Medium voltage cable	2.5	G													
			Precast concrete structures	2.11.2.1	G													
			Sealing Material	2.11.2.4														
			Pulling-In Irons	3.5.3														
			Manhole frames and covers	2.11.3														
			Handhole frames and covers	2.11.4														
			Composite/fiberglass handholes	2.11.6	G													
			Cable supports	2.12														
			SD-06 Test Reports															
			Field Acceptance Checks and Tests	3.18.1	G													
			Arc-proofing test	2.17.1														
			Cable Installation Plan and Procedure	3.3														
			SD-07 Certificates															
			Cable Installer Qualifications	1.5.2														
		33 82 00	SD-02 Shop Drawings															
			Telecommunications Outside Plant	1.6.1.1	G													
			Telecommunications Entrance Facility Drawings	1.6.1.2	G													
			SD-03 Product Data															
			Wire and cable	2.8														
			Cable splices, and connectors	2.5														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		33 82 00	Closures	2.3													
			Building protector assemblies	2.2.1	G												
			Protector modules	2.2.2	G												
			Cross-connect terminal cabinets	2.4													
			Spare Parts	1.8.2													
			SD-06 Test Reports														
			Pre-installation tests	3.5.1													
			Acceptance tests	3.5.2													
			Outside Plant Test Plan	1.6.3													
			SD-07 Certificates														
			Telecommunications Contractor	1.6.2.1	G												
			Key Personnel	1.6.2.2	G												
			Manufacturer's Qualifications	1.6.2.3													
			SD-08 Manufacturer's Instructions														
			Building protector assembly installation	2.2.1	G												
			Cable tensions	3.1.7.1													
			Fiber Optic Splices	3.1.8.2													
			SD-09 Manufacturer's Field Reports														
			Factory Reel Test Data	2.15.1													
			SD-10 Operation and Maintenance Data														
			Telecommunications outside plant (OSP)	1.6.1.1													
			SD-11 Closeout Submittals														

SUBMITTAL REGISTER

CONTRACT NO. _____

TITLE AND LOCATION
Ground Transportation Equipment Building (GTEB), Fort Huachuca

CONTRACTOR _____

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS	
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE			DATE OF ACTION
		33 82 00	Record Documentation	1.8.1													
		41 22 13.13	SD-02 Shop Drawings														
			Overhead Electric Traveling (OET) Crane(s)	1.5.1	G												
			Crane runway system	1.5.3	G												
			Complete schematic wiring diagram	1.5.4	G												
			SD-03 Product Data														
			OET Design Criteria	1.3.2	G												
			Overhead Electric Traveling (OET) Crane(s)	1.5.1	G												
			Load and Sizing Calculations	1.3.1	G												
			Festoon System	2.4.11.4	G												
			Runway Electrification System	1.5.4	G												
			Variable Frequency Drives	2.3.1	G												
			Bumpers	2.2.7	G												
			End Stops	2.2.7	G												
			Spare Parts	1.7	G												
			Framed Instructions	2.1.5	G												
			Nameplates	2.1.2	G												
			Pendant Control Station	2.4.6	G												
			Overloads	2.4.8.5	G												
			Limit Switches	2.4.9	G												
			SD-06 Test Reports														
			Acceptance Testing	3.3	G												
			Hook Assembly	1.5.2	G												

SECTION TABLE OF CONTENTS

DIVISION 05 - METALS

SECTION 05 50 13

MISCELLANEOUS METAL FABRICATIONS

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 QUALIFICATION OF WELDERS
- 1.4 DELIVERY, STORAGE, AND PROTECTION
- 1.5 MISCELLANEOUS REQUIREMENTS
 - 1.5.1 Fabrication Drawings
 - 1.5.2 Installation Drawings

PART 2 PRODUCTS

- 2.1 RECYCLED CONTENT
- 2.2 MATERIALS
 - 2.2.1 Structural Carbon Steel
 - 2.2.2 Structural Tubing
 - 2.2.3 Steel Pipe
 - 2.2.4 Fittings for Steel Pipe
 - 2.2.5 Gratings
 - 2.2.6 Floor Plates, Patterned
 - 2.2.7 Anchor Bolts
 - 2.2.7.1 Expansion Anchors
 - 2.2.7.2 Lag Screws and Bolts
 - 2.2.7.3 Toggle Bolts
 - 2.2.7.4 Bolts, Nuts, Studs and Rivets
 - 2.2.7.5 Powder Actuated Fasteners
 - 2.2.7.6 Screws
 - 2.2.7.7 Washers
 - 2.2.7.8 Welded Headed Shear Studs
 - 2.2.8 Aluminum Alloy Products
- 2.3 FABRICATION FINISHES
 - 2.3.1 Galvanizing
 - 2.3.2 Galvanize
 - 2.3.3 Shop Cleaning and Painting
 - 2.3.3.1 Surface Preparation
 - 2.3.3.2 Pretreatment, Priming and Painting
 - 2.3.4 Nonferrous Metal Surfaces
 - 2.3.5 Aluminum Surfaces
 - 2.3.5.1 Surface Condition
 - 2.3.5.2 Aluminum Finishes
- 2.4 FLOOR GRATINGS AND ROOF WALKWAYS
- 2.5 BOLLARDS/PIPE GUARDS
- 2.6 SECURITY GRILLES
- 2.7 GUY CABLES
- 2.8 ROOF HATCHES (SCUTTLES)

PART 3 EXECUTION

- 3.1 GENERAL INSTALLATION REQUIREMENTS
- 3.2 WORKMANSHIP
- 3.3 ANCHORAGE, FASTENINGS, AND CONNECTIONS
- 3.4 BUILT-IN WORK
- 3.5 WELDING
- 3.6 DISSIMILAR METALS
- 3.7 PREPARATION
 - 3.7.1 Material Coatings and Surfaces
 - 3.7.2 Environmental Conditions
- 3.8 INSTALLATION OF BOLLARDS/PIPE GUARDS

-- End of Section Table of Contents --

SECTION 05 50 13

MISCELLANEOUS METAL FABRICATIONS

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ALUMINUM ASSOCIATION (AA)

AA DAF45 (2003; Reaffirmed 2009) Designation System for Aluminum Finishes

AMERICAN CONCRETE INSTITUTE (ACI)

ACI 318 (2014; Errata 1-2 2014; Errata 3-5 2015; Errata 6 2016; Errata 7-9 2017) Building Code Requirements for Structural Concrete (ACI 318-14) and Commentary (ACI 318R-14)

AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC)

AISC 303 (2016) Code of Standard Practice for Steel Buildings and Bridges

AMERICAN SOCIETY OF CIVIL ENGINEERS (ASCE)

ASCE 7 (2017) Minimum Design Loads for Buildings and Other Structures

AMERICAN SOCIETY OF SAFETY PROFESSIONALS (ASSP)

ASSP A10.3 (2013) Safety Requirements for Powder-Actuated Fastening Systems American National Standard for Construction and Demolition Operations

AMERICAN WELDING SOCIETY (AWS)

AWS D1.1/D1.1M (2015; Errata 1 2015; Errata 2 2016) Structural Welding Code - Steel

ASME INTERNATIONAL (ASME)

ASME B18.2.1 (2012; Errata 2013) Square and Hex Bolts and Screws (Inch Series)

ASME B18.2.2 (2015) Nuts for General Applications: Machine Screw Nuts, Hex, Square, Hex Flange, and Coupling Nuts (Inch Series)

ASME B18.6.2 (1998; R 2010) Slotted Head Cap Screws,

	Square Head Set Screws, and Slotted Headless Set Screws: Inch Series
ASME B18.6.3	(2013; R 2017) Machine Screws, Tapping Screws, and Machine Drive Screws (Inch Series)
ASME B18.21.1	(2009; R 2016) Washers: Helical Spring-Lock, Tooth Lock, and Plain Washers (Inch Series)
ASME B18.21.2M	(1999; R 2014) Lock Washers (Metric Series)
ASME B18.22M	(1981; R 2017) Metric Plain Washers

ASTM INTERNATIONAL (ASTM)

ASTM A29/A29M	(2016) Standard Specification for General Requirements for Steel Bars, Carbon and Alloy, Hot-Wrought
ASTM A36/A36M	(2014) Standard Specification for Carbon Structural Steel
ASTM A47/A47M	(1999; R 2018; E 2018) Standard Specification for Ferritic Malleable Iron Castings
ASTM A48/A48M	(2003; R 2012) Standard Specification for Gray Iron Castings
ASTM A53/A53M	(2018) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless
ASTM A108	(2013) Standard Specification for Steel Bar, Carbon and Alloy, Cold-Finished
ASTM A123/A123M	(2017) Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products
ASTM A153/A153M	(2016) Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware
ASTM A307	(2014; E 2017) Standard Specification for Carbon Steel Bolts, Studs, and Threaded Rod 60 000 PSI Tensile Strength
ASTM A475	(2003; R 2014) Standard Specification for Zinc-Coated Steel Wire Strand
ASTM A500/A500M	(2018) Standard Specification for Cold-Formed Welded and Seamless Carbon Steel Structural Tubing in Rounds and Shapes
ASTM A653/A653M	(2018) Standard Specification for Steel

	Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM A786/A786M	(2015a) Standard Specification for Hot-Rolled Carbon, Low-Alloy, High-Strength Low-Alloy, and Alloy Steel Floor Plates
ASTM A924/A924M	(2018) Standard Specification for General Requirements for Steel Sheet, Metallic-Coated by the Hot-Dip Process
ASTM B26/B26M	(2014; E 2015) Standard Specification for Aluminum-Alloy Sand Castings
ASTM B108/B108M	(2015) Standard Specification for Aluminum-Alloy Permanent Mold Castings
ASTM B209	(2014) Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate
ASTM B209M	(2014) Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate (Metric)
ASTM B221	(2014) Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes
ASTM B221M	(2013) Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes (Metric)
ASTM C1513	(2018) Standard Specification for Steel Tapping Screws for Cold-Formed Steel Framing Connections
ASTM D1187/D1187M	(1997; E 2011; R 2011) Asphalt-Base Emulsions for Use as Protective Coatings for Metal
ASTM E488/E488M	(2015) Standard Test Methods for Strength of Anchors in Concrete and Masonry Elements
ASTM F1554	(2018) Standard Specification for Anchor Bolts, Steel, 36, 55, and 105-ksi Yield Strength
MASTER PAINTERS INSTITUTE (MPI)	
MPI 79	(2012) Primer, Alkyd, Anti-Corrosive for Metal
NATIONAL ASSOCIATION OF ARCHITECTURAL METAL MANUFACTURERS (NAAMM)	
NAAMM MBG 531	(2017) Metal Bar Grating Manual
NAAMM MBG 532	(2009) Heavy Duty Metal Bar Grating Manual

SOCIETY FOR PROTECTIVE COATINGS (SSPC)

SSPC SP 3 (1982; E 2004) Power Tool Cleaning

SSPC SP 6/NACE No.3 (2007) Commercial Blast Cleaning

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1 (2014) Safety and Health Requirements Manual

THE MASONRY SOCIETY (TMS)

TMS 402/602 (2016) Building Code Requirements and Specification for Masonry Structures

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance with Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Floor Gratings, Installation Drawings; G

Roof Walkways, Installation Drawings; G

Bollards/Pipe Guards; G

SD-03 Product Data

Floor Gratings; G

Roof Walkways; G

SD-07 Certificates

Certificates of Compliance; G

Certified Mill Test Reports for Chemistry and Mechanical Properties; G

SD-11 Closeout Submittals

Recycled Content; S

1.3 QUALIFICATION OF WELDERS

Qualify welders in accordance with AWS D1.1/D1.1M. Use procedures, materials, and equipment of the type required for the work.

1.4 DELIVERY, STORAGE, AND PROTECTION

Protect from corrosion, deformation, and other types of damage. Store items in an enclosed area free from contact with soil and weather. Remove

and replace damaged items with new items.

1.5 MISCELLANEOUS REQUIREMENTS

1.5.1 Fabrication Drawings

Submit fabrication drawings showing layout(s), connections to structural system, and anchoring details as specified in AISC 303.

1.5.2 Installation Drawings

Submit templates, erection, and installation drawings indicating thickness, type, grade, class of metal, and dimensions. Show construction details, reinforcement, anchorage, and installation in relation to the building construction.

PART 2 PRODUCTS

2.1 RECYCLED CONTENT

Provide products with recycled content and provide certificates of compliance in accordance with Section 01 33 29 SUSTAINABILITY REPORTING.

2.2 MATERIALS

Provide exposed fastenings of compatible materials (avoid contact of dissimilar metals). Coordinate color and finish with the material to which fastenings are applied. Submit the manufacturer's certified mill reports which clearly show the applicable ASTM mechanical and chemical requirements together with the actual test results for the supplied materials.

2.2.1 Structural Carbon Steel

Provide in accordance with ASTM A36/A36M.

2.2.2 Structural Tubing

Provide in accordance with ASTM A500/A500M.

2.2.3 Steel Pipe

Provide in accordance with ASTM A53/A53M, Type E or S, Grade B.

2.2.4 Fittings for Steel Pipe

Provide standard malleable iron fittings in accordance with ASTM A47/A47M.

2.2.5 Gratings

- a. Provide gray cast iron in accordance with ASTM A48/A48M, Class 40.
- b. Provide metal plank grating, non-slip requirement, aluminum in accordance with ASTM B209M ASTM B209, 6061-T6.
- c. Provide metal bar type grating in accordance with NAAMM MBG 531.

2.2.6 Floor Plates, Patterned

Provide floor plate in accordance with ASTM A786/A786M. Provide steel plate not less than 14 gage.

2.2.7 Anchor Bolts

Provide in accordance with ASTM F1554. Where exposed, provide anchor bolts of the same material, color, and finish as the metal to which they are applied.

2.2.7.1 Expansion Anchors

Provide 3/8 in. min diameter expansion anchors. Minimum concrete and masonry embedment of 3" in. Design values listed are as tested in accordance with ASTM E488/E488M.

- a. Provide minimum allowable pullout capacity capable of resisting loads applied on anchor per ASCE 7. Calculate pullout capacity according to ACI 318, or TMS 402/602 as applicable.
- b. Provide minimum allowable shear capacity capable of resisting loads applied on anchor per ASCE 7. Calculate shear capacity according to ACI 318, or TMS 402/602 as applicable.

2.2.7.2 Lag Screws and Bolts

Provide in accordance with ASME B18.2.1, type and grade best suited for the purpose.

2.2.7.3 Toggle Bolts

Provide in accordance with ASME B18.2.1.

2.2.7.4 Bolts, Nuts, Studs and Rivets

Provide in accordance with ASME B18.2.2 or ASTM A307.

2.2.7.5 Powder Actuated Fasteners

Follow safety provisions in accordance with ASSP A10.3.

2.2.7.6 Screws

Provide in accordance with ASME B18.2.1, ASME B18.6.2, ASME B18.6.3 and ASTM C1513.

2.2.7.7 Washers

Provide plain washers in accordance with ASME B18.22M, ASME B18.21.1. Provide beveled washers for American Standard beams and channels, square or rectangular, tapered in thickness, and smooth. Provide lock washers in accordance with ASME B18.21.2M, ASME B18.21.1.

2.2.7.8 Welded Headed Shear Studs

Provide in accordance with ASTM A108 or ASTM A29/A29M-12.

2.2.8 Aluminum Alloy Products

Provide in accordance with ASTM B209M, ASTM B209 for sheet plate, ASTM B221M, ASTM B221M, ASTM B221 for extrusions and ASTM B26/B26M or ASTM B108/B108M for castings. Provide aluminum extrusions at least 1/8 inch thick and aluminum plate or sheet at least 0.050 inch thick.

2.3 FABRICATION FINISHES

2.3.1 Galvanizing

Hot-dip galvanize items specified to be zinc-coated, after fabrication where practicable. Provide galvanizing in accordance with ASTM A123/A123M, ASTM A153/A153M, ASTM A653/A653M or ASTM A924/A924M, Z275 G90.

2.3.2 Galvanize

Anchor bolts, grating fasteners, washers, and parts or devices necessary for proper installation, unless indicated otherwise.

2.3.3 Shop Cleaning and Painting

2.3.3.1 Surface Preparation

Blast clean surfaces in accordance with SSPC SP 6/NACE No.3. Surfaces that will be exposed in spaces above ceiling or in attic spaces, crawl spaces, furred spaces, and chases may be cleaned in accordance with SSPC SP 3 in lieu of being blast cleaned. Wash cleaned surfaces which become contaminated with rust, dirt, oil, grease, or other contaminants with solvents until thoroughly clean. Steel to be embedded in concrete must be free of dirt and grease prior to embed. Do not paint or galvanize bearing surfaces, including contact surfaces within slip critical joints. Shop coat these surfaces with rust prevention.

2.3.3.2 Pretreatment, Priming and Painting

Apply pre-treatment, primer, and paint in accordance with manufacturer's printed instructions. On surfaces concealed in the finished construction or not accessible for finish painting, apply an additional prime coat to a minimum dry film thickness of 1.0 mil. Tint additional prime coat with a small amount of tinting pigment.

2.3.4 Nonferrous Metal Surfaces

Protect by plating, anodic, or organic coatings.

2.3.5 Aluminum Surfaces

2.3.5.1 Surface Condition

Before finishes are applied, remove roll marks, scratches, rolled-in scratches, kinks, stains, pits, orange peel, die marks, structural streaks, and other defects which will affect uniform appearance of finished surfaces.

2.3.5.2 Aluminum Finishes

Unexposed sheet, plate and extrusions may have mill finish as fabricated. Sandblast castings' finish, medium, AA DAF45. Unless otherwise specified,

provide all other aluminum items with a standard mill finish. Provide a coating thickness not less than that specified for protective and decorative type finishes for items used in interior locations or architectural Class I type finish for items used in exterior locations. Provide in accordance with AA DAF45. Provide a polished satin finish on items to be anodized.

2.4 FLOOR GRATINGS AND ROOF WALKWAYS

Design steel grating in accordance with NAAMM MBG 531 and NAAMM MBG 532 for bar type gratings, or in accordance with manufacturer's charts for plank grating. Galvanize steel floor gratings.

- a. Design floor gratings to support a stress live load of 300 pounds per square foot for the spans indicated, with maximum deflection of $L/240$.
- b. In accordance with NAAMM MBG 531, band edges of grating with bars of the same size as the bearing bars. Weld banding in accordance with the manufacturer's standard for trim. Design tops of bearing bars, cross or intermediate bars to be in the same plane and to match grating finish.
- d. Provide slip resistant surface finishes.
- e. Rooftop walkway: Minimum 2 feet wide, 14 gage, ASTM A653/A653M, G-90, steel with slip resistant surface. Furnish all brackets, connectors and other accessories. Support at minimum 5 foot intervals on hard rubber pads in accordance with manufacturer's instructions.

2.5 BOLLARDS/PIPE GUARDS

Provide 8 and 12 inch prime coated extra strong weight steel pipe in accordance with ASTM A53/A53M. Anchor posts in concrete as indicated and fill solidly with concrete with minimum compressive strength of 2500 psi.

2.6 SECURITY GRILLES

Fabricate of channel frames with not less than two masonry anchors at each jamb and 1/2 inch hardened steel bars spaced not over 4 inches both ways and welded to frame. Provide 18 by 16 mesh screen and two layers of 1/4 inch hardware cloth clamped to frame.

2.7 GUY CABLES

Provide guy cables as pre-stretched, galvanized wire rope of sizes indicated. Provide wire rope in accordance with ASTM A475, high strength grade with Class A coating. Guys must have a factory attached clevis top-end fitting, a factory attached open-bridge strand socket bottom-end fitting, and must be complete with oval eye, threaded anchor rods. Provide hot-dip galvanized fittings and accessories.

2.8 ROOF HATCHES (SCUTTLES)

Provide aluminim or zinc-coated steel, per adjacent roof panel material, sheets not less than 14 gauge with 3 inch beaded flange, welded and ground at corners. Provide a minimum clear opening of 30 by 36 inches. Insulate

cover and curb with one inch thick rigid fiberboard insulation, covered and protected by aluminim or zinc-coated steel, per adjacent roof panel material, of not less than 26 gage. Provide with 12 inches high curb, formed with 3 inch mounting flanges with holes for securing to the roof deck.

PART 3 EXECUTION

3.1 GENERAL INSTALLATION REQUIREMENTS

Install items at locations indicated in accordance with manufacturer's instructions. Verify all field dimensions prior to fabrication. Include materials and parts necessary to complete each assembly, whether indicated or not. Miss-alignment and miss-sizing of holes for fasteners is cause for rejection. Conceal fastenings where practicable. Joints exposed to weather must be watertight.

3.2 WORKMANSHIP

Provide miscellaneous metalwork that is true and accurate in shape, size, and profile. Make angles and lines continuous and straight. Make curves consistent, smooth and unafaceted. Provide continuous welding along the entire area of contact except where tack welding is permitted. Do not tack weld exposed connections. Unless otherwise indicated and approved, provide a smooth finish on exposed surfaces. Provide countersuck rivets where exposed. Provide coped and mitered corner joints aligned flush and without gaps.

3.3 ANCHORAGE, FASTENINGS, AND CONNECTIONS

Provide anchorage as necessary, whether indicated or not, for fastening miscellaneous metal items securely in place. Include slotted inserts, expansion shields, powder-driven fasteners, toggle bolts (when approved for concrete), through bolts for masonry, headed shear studs, machine and carriage bolts for steel, through bolts, lag bolts, and screws for wood. Do not use wood plugs. Provide non-ferrous attachments for non-ferrous metal. Provide exposed fastenings of compatible materials (avoid contact of dissimilar metals), that generally match in color and finish the surfaces to which they are applied. Conceal fastenings where practicable. Provide all fasteners flush with the surfaces they fasten, unless indicated otherwise.

3.4 BUILT-IN WORK

Where necessary and not otherwise indicated, form built-in metal work for anchorage with concrete or masonry. Provide built-in metal work in ample time for securing in place as the work progresses.

3.5 WELDING

Perform welding, welding inspection, and corrective welding in accordance with AWS D1.1/D1.1M. Use continuous welds on all exposed connections. Grind visible welds smooth in the finished installation. Provide welded headed shear studs in accordance with AWS D1.1/D1.1M, Clause 7, except as otherwise specified. Provide in accordance with the safety requirements of EM 385-1-1.

3.6 DISSIMILAR METALS

Where dissimilar metals are in contact, protect surfaces with a coating in accordance with MPI 79 to prevent galvanic or corrosive action. Where aluminum is in contact with concrete, plaster, mortar, masonry, wood, or absorptive materials subject to wetting, protect in accordance with ASTM D1187/D1187M, asphalt-base emulsion. Clean surfaces with metal shavings from installation at the end of each work day.

3.7 PREPARATION

3.7.1 Material Coatings and Surfaces

Remove rust preventive coating just prior to field erection, using a remover approved by the metal manufacturer. Surfaces, when assembled, must be free of rust, grease, dirt and other foreign matter.

3.7.2 Environmental Conditions

Do not clean or paint surfaces when damp or exposed to foggy or rainy weather, when metallic surface temperature is less than minus 5 degrees F above the dew point of the surrounding air, or when surface temperature is below 45 degrees F or over 95 degrees F, unless approved by the Contracting Officer. Metal surfaces to be painted must be dry for a minimum of 48 hours prior to the application of primer or paint.

3.8 INSTALLATION OF BOLLARDS/PIPE GUARDS

Set bollards/pipe guards vertically in concrete piers. Fill hollow cores with concrete having a compressive strength of 3000 psi.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 08 - OPENINGS

SECTION 08 33 23

OVERHEAD COILING DOORS

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 QUALITY CONTROL
- 1.4 DELIVERY, STORAGE, AND HANDLING

PART 2 PRODUCTS

- 2.1 SYSTEM DESCRIPTION
 - 2.1.1 Design Requirements
 - 2.1.1.1 Overhead Coiling Door Detail Shop Drawings
 - 2.1.2 Performance Requirements
 - 2.1.2.1 Wind Loading
 - 2.1.2.2 Operational Cycle Life
- 2.2 COMPONENTS
 - 2.2.1 Overhead Coiling Doors
 - 2.2.1.1 Curtain Materials and Construction
 - 2.2.1.2 Curtain Bottom Bar
 - 2.2.1.3 Insulated Curtains
 - 2.2.1.4 Vision Panels
 - 2.2.1.5 Locks
 - 2.2.1.6 Weather Stripping
 - 2.2.1.7 Locking Devices
 - 2.2.1.8 Safety Interlock
 - 2.2.1.9 Overhead Drum
 - 2.2.1.10 Slats
 - 2.2.2 Hardware
 - 2.2.2.1 Guides
 - 2.2.2.2 Equipment Supports
 - 2.2.2.3 Hood
 - 2.2.3 Counterbalancing Mechanism
 - 2.2.3.1 Brackets
 - 2.2.3.2 Counterbalance Barrels
 - 2.2.3.3 Spring Balance
 - 2.2.3.4 Torsion Rod for Counter Balance
 - 2.2.3.5 Counterbalance Shaft Assembly
 - 2.2.4 Manual Door Operators
 - 2.2.4.1 Manual Crank-Hoist Door Operators
 - 2.2.5 Electric Door Operators
 - 2.2.5.1 Door-Operator Types
 - 2.2.5.2 Electric Motors
 - 2.2.5.3 Motor Bearings
 - 2.2.5.4 Motor Starters, Controls, and Enclosures
 - 2.2.5.5 Control Enclosures
 - 2.2.5.6 Transformer

- 2.2.5.7 Safety-Edge Device
- 2.2.5.8 Remote-Control Stations
- 2.2.5.9 Speed-Reduction Units
- 2.2.5.10 Chain Drives
- 2.2.5.11 Brakes
- 2.2.5.12 Clutches
- 2.2.5.13 Weather/Smoke Seal Sensing Edge
- 2.2.6 Surface Finishing

PART 3 EXECUTION

- 3.1 INSTALLATION
 - 3.1.1 Field Painted Finish
- 3.2 ADJUSTING AND CLEANING
 - 3.2.1 Acceptance Provisions
 - 3.2.1.1 Maintenance and Adjustment
 - 3.2.1.2 Cleaning
- 3.3 CLOSEOUT ACTIVITIES
 - 3.3.1 Warranty
 - 3.3.2 Operation And Maintenance

-- End of Section Table of Contents --

SECTION 08 33 23

OVERHEAD COILING DOORS

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF CIVIL ENGINEERS (ASCE)

ASCE 7 (2017) Minimum Design Loads for Buildings and Other Structures

ASME INTERNATIONAL (ASME)

ASME B29.400 (2001; (R 2008) (R 2013) (R 2018))
Combination, "H" Type Mill Chains, and Sprockets

ASTM INTERNATIONAL (ASTM)

ASTM A153/A153M (2016) Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware

ASTM A27/A27M (2017) Standard Specification for Steel Castings, Carbon, for General Application

ASTM A307 (2014; E 2017) Standard Specification for Carbon Steel Bolts, Studs, and Threaded Rod 60 000 PSI Tensile Strength

ASTM A36/A36M (2014) Standard Specification for Carbon Structural Steel

ASTM A48/A48M (2003; R 2012) Standard Specification for Gray Iron Castings

ASTM A53/A53M (2018) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless

ASTM A653/A653M (2018) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process

ASTM A666 (2015) Standard Specification for Annealed or Cold-Worked Austenitic Stainless Steel Sheet, Strip, Plate and Flat Bar

ASTM A780/A780M (2009; R 2015) Standard Practice for

	Repair of Damaged and Uncoated Areas of Hot-Dip Galvanized Coatings
ASTM A924/A924M	(2018) Standard Specification for General Requirements for Steel Sheet, Metallic-Coated by the Hot-Dip Process
ASTM B209	(2014) Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate
ASTM B221	(2014) Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes
ASTM D2000	(2012; R 2017) Standard Classification System for Rubber Products in Automotive Applications
ASTM E330/E330M	(2014) Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference
ASTM F568M	(2007) Standard Specification for Carbon and Alloy Steel Externally Threaded Metric Fasteners

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA ICS 2	(2000; R 2005; Errata 2008) Industrial Control and Systems Controllers, Contactors, and Overload Relays Rated 600 V
NEMA ICS 6	(1993; R 2016) Industrial Control and Systems: Enclosures
NEMA MG 1	(2016; SUPP 2018) Motors and Generators
NEMA ST 1	(1988; R 1994; R 1997) Specialty Transformers (Except General Purpose Type)

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2017; ERTA 1-2 2017; TIA 17-1; TIA 17-2; TIA 17-3; TIA 17-4; TIA 17-5; TIA 17-6; TIA 17-7; TIA 17-8; TIA 17-9; TIA 17-10; TIA 17-11; TIA 17-12; TIA 17-13; TIA 17-14; TIA 17-15; TIA 17-16; TIA 17-17) National Electrical Code
---------	--

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Overhead Coiling Doors
Counterbalancing Mechanism
Manual Door Operators
Electric Door Operators
Bottom Bars
Guides
Mounting Brackets
Overhead Drum
Hood
Installation Drawings

SD-03 Product Data

Overhead Coiling Doors
Hardware
Counterbalancing Mechanism
Manual Door Operators
Electric Door Operators
Recycled Content For Steel Curtain Slats

SD-05 Design Data

Overhead Coiling Doors
Hardware
Counterbalancing Mechanism
Manual Door Operators
Electric Door Operators

SD-10 Operation and Maintenance Data

Operation and Maintenance Manuals; G
Materials
Devices
Procedures

Manufacture's Brochures

Parts Lists; G

SD-11 Closeout Submittals

Warranty; G

1.3 QUALITY CONTROL

1.4 DELIVERY, STORAGE, AND HANDLING

Deliver doors to the jobsite wrapped in a protective covering with the brands and names clearly marked thereon. Store doors in an adequately ventilated dry location that is free from dirt and dust, water, or other contaminants. Store in a manner that permits easy access for inspection and handling.

PART 2 PRODUCTS

2.1 SYSTEM DESCRIPTION

Doors to be coiling type, with interlocking slats, complete with anchoring and door hardware, guides, hood, and operating mechanisms, and designed for use on openings as indicated. Use grease-sealed or self-lubricating bearings for rotating members.

2.1.1 Design Requirements

2.1.1.1 Overhead Coiling Door Detail Shop Drawings

Provide installation drawings for overhead coiling door assemblies which show: elevations of each door type, shape and thickness of materials, finishes, details of joints and connections, details of guides and fittings, rough opening dimensions, location and description of hardware, anchorage locations, and counterbalancing mechanism and door operator details. Show locations of replaceable fusible links on wiring diagrams for power, signal and controls. Include a schedule showing the location of each door with the drawings.

2.1.2 Performance Requirements

2.1.2.1 Wind Loading

Design and fabricate door assembly to withstand the wind loading pressure of at least 50 pounds per square foot with a maximum deflection of 1/120 of the opening width. Provide test data showing compliance with ASTM E330/E330M. Sound engineering principles may be used to interpolate or extrapolate test results to door sizes not specifically tested. Ensure complete assembly meets or exceeds the requirements of ASCE 7.

2.1.2.2 Operational Cycle Life

Design all portions of the door, hardware and operating mechanism that are subject to movement, wear, or stress fatigue to operate through a minimum number of 10 cycles per day. One complete cycle of door operation is defined as when the door is in the closed position, moves to the fully open position, and returns to the closed position.

2.2 COMPONENTS

2.2.1 Overhead Coiling Doors

2.2.1.1 Curtain Materials and Construction

~~Provide curtain slats fabricated from aluminum sheets conforming to ASTM B209, or ASTM B221 extrusions, alloy and tempering standard from manufacturer for type of use and finish indicated; with a thickness of 0.050 inch and as required to meet requirements. Provide slats filled with manufacturer's standard thermal insulation complying with maximum flame-spread and smoke-developed indexes of 75 and 450, respectively, according to ASTM E84. Enclose insulation completely within slat faces on interior surface of slats.~~ Provide curtain slats fabricated from Grade A steel sheets conforming to ASTM A653/A653M, with the additional requirement of a minimum yield point of 33,000 psi. Provide 18 gauge sheets, Grade 40 steel with galvanized steel zinc coating in conformance with ASTM A653/A653M and ASTM A924/A924M. Provide steel curtain slats containing a minimum of 20 percent recycled content. Submit data identifying percentage of recycled content for steel curtain slats.

Fabricate doors from interlocking cold-rolled slats, with section profiles as specified, designed to withstand the specified wind loading. Ensure the provided slats are continuous without splices for the width of the door.

2.2.1.2 Curtain Bottom Bar

Install curtain bottom bars as pairs of angles from the manufacturer's standard steel, stainless and aluminum extrusions not less than 2.0 by 2.0-inches by 0.188-inch. Ensure steel extrusions conform to ASTM A36/A36M. Stainless steel extrusions conforming to ASTM A666, Type 304. Aluminum extrusions conforming to ASTM B221. Galvanize angles and fasteners in accordance with ASTM A653/A653M and ASTM A924/A924M. Coat welds and abrasions with paint conforming to ASTM A780/A780M.

2.2.1.3 Insulated Curtains

Provide slats filled with manufacturer's standard thermal insulation complying with maximum flame-spread and smoke-developed indexes of 75 and 450, respectively, according to ASTM E84. Enclose insulation completely within slat faces on interior surface of slats

2.2.1.4 Vision Panels

Provide complete manufacturer's standard vision panels assembly consisting of clear acrylic glazing panels or fire-rated glass as required for the type door. Set panels in a neoprene channel with a galvanized-steel frame not less than 0.0359-inch uncoated thickness.

2.2.1.5 Locks

Provide end and/or wind locks of Grade B cast steel conforming to ASTM A27/A27M, galvanized in accordance with ASTM A653/A653M, ASTM A153/A153M and ASTM A924/A924M. Secure locks at every other curtain slat.

2.2.1.6 Weather Stripping

Ensure weather-stripping at the door-head and jamb is 1/8-inch thick sheet of natural or neoprene rubber with air baffles. Secure weather stripping to the insides of hoods with galvanized-steel fasteners through continuous galvanized-steel pressure bars at least 5/8-inch wide and 1/8-inch thick.

Ensure threshold weather-stripping is 1/8-inch thick sheet natural or neoprene rubber secured to the bottom bars.

Provide weather-stripping of natural or neoprene rubber conforming to ASTM D2000.

2.2.1.7 Locking Devices

Ensure slide bolt engages through slots in tracks for locking by padlock, located on both left and right jamb sides, operable from coil side.

Provide a locking device assembly which includes cylinder lock, spring-loaded dead bolt, operating handle, cam plate, and adjustable locking bars to engage through slots in tracks.

2.2.1.8 Safety Interlock

Equip power-operated doors with safety interlock switch to disengage power supply when door is locked.

2.2.1.9 Overhead Drum

Fabricate drums from nominal 0.040-inch thick aluminum sheet complying with ASTM B209. Aluminum of alloy and temper recommended by manufacturer. Select finish for type of use and finish indicated.

2.2.1.10 Slats

No. 5F, 18 gauge, Grade 40 steel, ASTM A653/A653M galvanized steel zinc coating.

2.2.2 Hardware

Ensure all hardware conforms to ASTM A153/A153M, ASTM A307, ASTM F568M, and ASTM A27/A27M.

2.2.2.1 Guides

Fabricate curtain jamb guides from the manufacturer's standard angles or channels of same material and finish as curtain slats unless otherwise indicated. Provide guides with sufficient depth and strength to retain curtain, and to withstand loading. Ensure curtain operates smoothly. Slot bolt holes for track adjustment.

2.2.2.2 Equipment Supports

Fabricate door-operating equipment supports from the manufacturer's standard steel shapes and plates conforming to ASTM A36/A36M, galvanized in accordance with ASTM A653/A653M and ASTM A924/A924M. Size the shapes and plates in accordance with the industry standards for the size, weight, and type of door installation.

2.2.2.3 Hood

Provide a hood with a minimum aluminum 22-gauge B&S sheet metal, flanged at top for attachment to header and flanged at bottom to provide longitudinal stiffness. The hood encloses the curtain coil and counterbalance mechanism.

Provide a 0.040-inch aluminum hood with reinforced top and bottom edges. Provide minimum 1/4-inch steel intermediate support brackets as required to prevent excessive sag.

2.2.3 Counterbalancing Mechanism

Counterbalance doors by means of manufacturer's standard mechanism with an adjustable-tension, steel helical torsion spring mounted, around a steel shaft and contained in a spring barrel connected to top of curtain with barrel rings. Use grease-sealed or self-lubricating bearings for rotating members.

2.2.3.1 Brackets

Provide the manufacturer's standard mounting brackets with one located at each end of the counterbalance barrel conforming to ASTM A48/A48M. Provide brackets of either cast iron or cold-rolled steel.

2.2.3.2 Counterbalance Barrels

Fabricate spring barrel of manufacturer's standard hot-formed, structural-quality, welded or seamless carbon-steel pipe, conforming to ASTM A53/A53M. Ensure the barrel is of sufficient diameter and wall thickness to support rolled-up curtain without distortion of slats. Limit barrel deflection to not more than 0.03 inch per foot of span under full load.

a. Barrel

Provide steel pipe capable of supporting curtain load with maximum deflection of 0.03 inches per foot of width.

b. Spring Balance

Provide an oil-tempered, heat-treated steel helical torsion spring assembly designed for proper balance of door. Ensure that effort to operate manually operated units does not exceed 25 lbs. Provide wheel for applying and adjusting spring torque.

2.2.3.3 Spring Balance

Install one or more oil-tempered, heat-treated steel helical torsion springs within the barrel, capable of producing sufficient torque to assure easy operation of the door curtain. Provide and size springs to counterbalance weight of curtain, with uniform adjustment accessible from outside barrel. Secure ends of springs to barrel and shaft with cast-steel barrel plugs.

2.2.3.4 Torsion Rod for Counter Balance

Fabricate rod from the manufacturer's standard cold-rolled steel, sized to

hold fixed spring ends and carry torsional load.

2.2.3.5 Counterbalance Shaft Assembly

a. Barrel

Provide steel pipe capable of supporting the curtain load with maximum deflection of 0.03 inches per foot of width.

b. Spring Balance

Provide an oil-tempered, heat-treated steel helical torsion spring assembly designed for proper balance of door. Ensure that maximum effort to operate does not exceed 25 pounds. Provide wheel for applying and adjusting spring torque.

2.2.4 Manual Door Operators

2.2.4.1 Manual Crank-Hoist Door Operators

Provide door operators which consist of crank and crank gearbox, steel crank drive shaft, and gear-reduction unit with a maximum 25 lbf force to turn crank. Fabricate gearbox to be oil tight and to completely enclose operating mechanism. Provide manufacturer's standard crank-locking device with a self-locking mechanism allowing the curtain to be stopped at any point in its upward or downward travel and remain in that position until moved to the fully open or closed position.

2.2.5 Electric Door Operators

Provide electrical wiring and door operating controls conforming to the applicable requirements of NFPA 70.

Electric door-operator assemblies needs to be the sizes and capacities recommended and provided by the door manufacturer for specified doors. Furnish complete assemblies with electric motors and factory-rewired motor controls, starter, gear reduction units, solenoid-operated brakes, clutch, remote-control stations, manual or automatic control devices, and accessories as required for proper operation of the doors.

Design the operators so that motors may be removed without disturbing the limit-switch adjustment and affecting the emergency auxiliary operators.

Provide a manual operator of crank-gear or chain-gear mechanisms with a release clutch to permit manual operation of doors in case of power failure. Arrange the emergency manual operator so that it may be put into and out of operation from floor level, and its use does not affect the adjustment of the limit switches. Provide an electrical or mechanical device that automatically disconnects the motor from the operating mechanism when the emergency manual operating mechanism is engaged.

2.2.5.1 Door-Operator Types

Provide an operator mounted to the right or left door head plate with the operator on top of the door-hood assembly and connected to the door drive shaft with drive chain and sprockets. Headroom is required for this type of mounting.

2.2.5.2 Electric Motors

Provide motors which are the high-starting-torque, reversible, constant-duty electrical type with overload protection of sufficient torque and horsepower to move the door in either direction from any position. Ensure they produce a door-travel speed of not less than 8 nor more than 12 inches per second without exceeding the horsepower rating.

Provide motors which conform to NEMA MG 1 designation, temperature rating, service factor, enclosure type, and efficiency to the requirements specified.

2.2.5.3 Motor Bearings

Select bearings with bronze-sleeve or heavy-duty ball or roller antifriction type with full provisions for the type of thrust imposed by the specific duty load.

Pre-lubricate and factory seal bearings in motors less than 1/2 horsepower.

Equip motors coupled to worm-gear reduction units with either ball or roller bearings.

Equip bearings in motors 1/2 horsepower or larger with lubrication service fittings. Fit lubrication fittings with color-coded plastic or metal dust caps.

In any motor, bearings that are lubricated at the factory for extended duty periods do not need to be lubricated for a given number of operating hours. Display this information on an appropriate tag or label on the motor with instructions for lubrication cycle maintenance.

2.2.5.4 Motor Starters, Controls, and Enclosures

Provide each door motor with: a factory-wired, unfused, disconnect switch; a reversing, across-the-line magnetic starter with thermal overload protection; 120-volt operating coils with a control transformer limit switch; and a safety interlock assembled in a NEMA ICS 6 type enclosure as specified herein. Ensure control equipment conforms to NEMA ICS 2.

Provide adjustable switches, electrically interlocked with the motor controls and set to stop the door automatically at the fully open and fully closed position.

2.2.5.5 Control Enclosures

Provide control enclosures that conform to NEMA ICS 6 for oil-tight and dust-tight NEMA Type 13.

2.2.5.6 Transformer

Provide starters with 230/460 to 115 volt control transformers with one secondary fuse when required to reduce the voltage on control circuits to 120 volts or less. Provide a transformer conforming to NEMA ST 1.

2.2.5.7 Safety-Edge Device

Provide each door with a pneumatic safety device extending the full width of the door and located within a U-section neoprene or rubber astragal,

mounted on the bottom rail of the bottom door section. Device needs to immediately stop and reverse the door upon contact with an obstruction in the door opening during downward travel and cause the door to return to full-open position. A safety device is not a substitute for a limit switch.

Connect safety device to the control circuit through a retracting safety cord and reel.

2.2.5.8 Remote-Control Stations

Provide interior remote control stations which are full-guarded, momentary-contact three-button, heavy-duty, surface-mounted NEMA ICS 6 type enclosures as specified. Mark buttons "OPEN," "CLOSE," and "STOP." Ensure the "CLOSE" button requires a constant pressure to maintain the closing motion of the door. When the door is in motion and the "STOP" button is pressed, ensure the door stops instantly and remains in the stopped position. From the stopped position, the door may then be operated in either direction.

2.2.5.9 Speed-Reduction Units

Provide speed-reduction units consisting of hardened-steel worm and bronze worm gear assemblies running in oil or grease and inside a sealed casing, coupled to the motor through a flexible coupling. Drive shafts need to rotate on ball- or roller-bearing assemblies that are integral with the unit.

Provide minimum ratings of speed reduction units in accordance with AGMA provisions for class of service.

Ground worm gears to provide accurate thread form; machine teeth for all other types of gearing. Surface harden all gears.

Provide antifriction type bearings equipped with oil seals.

2.2.5.10 Chain Drives

Provide roller chains that are a power-transmission series steel roller type conforming to ASME B29.400, with a minimum safety factor of 10 times the design load.

Heat-treat or otherwise harden roller-chain side bars, rollers, pins, and bushings.

Provide high-carbon steel chain sprockets with machine-cut hardened teeth, finished bore and keyseat, and hollow-head setscrews.

2.2.5.11 Brakes

Provide 360-degree shoe brakes or shoe and drum brakes. Ensure the brakes are solenoid-operated and electrically interlocked to the control circuit to set automatically when power is interrupted.

2.2.5.12 Clutches

Ensure clutches are either the 4-inch diameter, multiple face, externally adjustable friction type or adjustable centrifugal type.

2.2.5.13 Weather/Smoke Seal Sensing Edge

Provide automatic stop control by an automatic sensing switch within neoprene astragal extending the full width of door bottom bar.

Provide an electric sensing edge device. Ensure the door immediately stops downward travel when contact occurs before door fully closes. Provide a self-monitoring wireless sensing edge connection to the motor operator; eliminating the need for a physical traveling electric cord connection between bottom bar sensing edge device and motor operator. Supervised system alters normal door operation; preventing damage, injury or death due to an inoperable sensing edge system.

2.2.6 Surface Finishing

Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes. Noticeable variations in the same metal component are not acceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved samples and are assembled or installed to minimize contrast.

PART 3 EXECUTION

3.1 INSTALLATION

Install overhead coiling door assembly, anchors and inserts for guides, brackets, motors, switches, hardware, and other accessories in accordance with approved detail drawings and manufacturer's written instructions. Upon completion of installation, ensure doors are free from all distortion.

Install overhead coiling doors, motors, hoods, and operators at the mounting locations as indicated for each door in the contract documents and as required by the manufacturer.

Install overhead coiling doors, switches, and controls along accessible routes in compliance with regulatory requirements for accessibility and as required by the manufacturer.

3.1.1 Field Painted Finish

Ensure field painted steel doors and frames are in accordance with Section 09 90 00 PAINTS AND COATINGS and manufacturer's written instructions. Protect weather stripping from paint. Ensure finishes are free of scratches or other blemishes.

3.2 ADJUSTING AND CLEANING

3.2.1 Acceptance Provisions

After installation, adjust hardware and moving parts. Lubricate bearings and sliding parts as recommended by manufacturer to provide smooth operating functions for ease movement, free of warping, twisting, or distortion of the door assembly.

Adjust seals to provide weather-tight fit around entire perimeter.

Engage a factory-authorized service representative to perform startup service and checks according to manufacturer's written instructions.

Test the door opening and closing operation when activated by controls or alarm-connected fire-release system. Adjust controls and safeties. Replace damaged and malfunctioning controls and equipment. Reset door-closing mechanism after successful test.

Test and make final adjustment of new doors at no additional cost to the Government.

3.2.1.1 Maintenance and Adjustment

Not more than 90 calendar days after completion and acceptance of the project, examine, lubricate, test, and re-adjust doors as required for proper operation.

3.2.1.2 Cleaning

Clean doors in accordance with manufacturer's approved instructions.

3.3 CLOSEOUT ACTIVITIES

3.3.1 Warranty

Furnish a written guarantee that the helical spring and counterbalance mechanism are free from defects in material and workmanship for not less than two years after completion and acceptance of the project.

Warrant that upon notification by the Government, any defects in material, workmanship, and door operation are immediately correct within the same time period covered by the guarantee, at no cost to the Government.

3.3.2 Operation And Maintenance

Submit 6 copies of the Operation and Maintenance Manuals 30 calendar days prior to testing the Overhead Coiling Door Assemblies. Update and resubmit data for final approval no later than 30 calendar days prior to contract completion.

Submit Operation and Maintenance Manuals for Overhead Coiling Door Assemblies, including the following items:

Materials

Devices

Manual Door Operators

Electric Door Operators

Hood

Counterbalancing Mechanism

Painting

Procedures

Manufacture's Brochures

Parts Lists

Provide operation and maintenance manuals which are consistent with manufacturer's standard brochures, schematics, printed instructions, operating procedures, and safety precautions. Provide test data that is legible and of good quality.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 08 - OPENINGS

SECTION 08 71 00

DOOR HARDWARE

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 PRODUCT DATA
- 1.4 HARDWARE SCHEDULE
- 1.5 KEY BITTING CHART REQUIREMENTS
 - 1.5.1 Requirements
- 1.6 QUALITY CONTROL
 - 1.6.1 Hardware Manufacturers and Modifications
 - 1.6.2 Key Shop Drawings Coordination Meeting
- 1.7 DELIVERY, STORAGE, AND HANDLING

PART 2 PRODUCTS

- 2.1 TEMPLATE HARDWARE
- 2.2 HARDWARE FOR FIRE DOORS AND EXIT DOORS
- 2.3 HARDWARE ITEMS
 - 2.3.1 Hinges
 - 2.3.2 Locks and Latches
 - 2.3.2.1 Mortise Locks and Latches
 - 2.3.3 Exit Devices
 - 2.3.4 High Security Locks
 - 2.3.5 Cylinders and Cores
 - 2.3.6 Keying System
 - 2.3.7 Lock Trim
 - 2.3.7.1 Lever Handles
 - 2.3.7.2 Texture
 - 2.3.8 Keys
 - 2.3.9 Door Bolts
 - 2.3.10 Closers
 - 2.3.10.1 Identification Marking
 - 2.3.11 Overhead Holders
 - 2.3.12 Door Protection Plates
 - 2.3.12.1 Sizes of Kick Plates
 - 2.3.13 Door Stops and Silencers
 - 2.3.14 Thresholds
 - 2.3.15 Weatherstripping Gasketing
 - 2.3.15.1 Extruded Aluminum Retainers
 - 2.3.15.2 Interlocking Type
 - 2.3.15.3 Spring Tension Type
 - 2.3.16 Lightproofing and Soundproofing Gasketing
 - 2.3.17 Rain Drips
 - 2.3.17.1 Door Rain Drips
 - 2.3.17.2 Overhead Rain Drips
 - 2.3.18 Auxiliary Hardware (Other than locks)

- 2.3.19 Sliding and Folding Door Hardware
- 2.3.20 Special Tools
- 2.4 FASTENERS
- 2.5 FINISHES
- 2.6 KEY CABINET AND CONTROL SYSTEM

PART 3 EXECUTION

- 3.1 INSTALLATION
 - 3.1.1 Weatherstripping Installation
 - 3.1.1.1 Stop Applied Weatherstripping
 - 3.1.1.2 Interlocking Type Weatherstripping
 - 3.1.1.3 Spring Tension Type Weatherstripping
 - 3.1.2 Lightproofing and Soundproofing Installation
 - 3.1.3 Threshold Installation
- 3.2 FIRE DOORS AND EXIT DOORS
- 3.3 HARDWARE LOCATIONS
- 3.4 KEY CABINET AND CONTROL SYSTEM
- 3.5 FIELD QUALITY CONTROL
- 3.6 HARDWARE SETS

-- End of Section Table of Contents --

SECTION 08 71 00

DOOR HARDWARE

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM E283 (2004; R 2012) Determining the Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen

BUILDERS HARDWARE MANUFACTURERS ASSOCIATION (BHMA)

ANSI/BHMA A156.1 (2016) Butts and Hinges

ANSI/BHMA A156.13 (2017) Mortise Locks & Latches Series 1000

ANSI/BHMA A156.14 (2013) Sliding and Folding Door Hardware

ANSI/BHMA A156.16 (2018) Auxiliary Hardware

ANSI/BHMA A156.18 (2016) Materials and Finishes

ANSI/BHMA A156.21 (2014) Thresholds

ANSI/BHMA A156.22 (2017) Door Gasketing and Edge Seal Systems

ANSI/BHMA A156.3 (2014) Exit Devices

ANSI/BHMA A156.4 (2013) Door Controls - Closers

ANSI/BHMA A156.5 (2014) Cylinder and Input Devices for Locks

ANSI/BHMA A156.6 (2015) Architectural Door Trim

ANSI/BHMA A156.7 (2016) Template Hinge Dimensions

ANSI/BHMA A156.8 (2015) Door Controls - Overhead Stops and Holders

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 101 (2018; TIA 18-1; TIA 18-2; TIA 18-3) Life Safety Code

NFPA 252 (2017) Standard Methods of Fire Tests of Door Assemblies

NFPA 72	(2019; TIA 19-1; ERTA 2019) National Fire Alarm and Signaling Code
NFPA 80	(2016; TIA 16-1) Standard for Fire Doors and Other Opening Protectives
STEEL DOOR INSTITUTE (SDI/DOOR)	
SDI/DOOR A250.8	(2003; R2008) Recommended Specifications for Standard Steel Doors and Frames
UNDERWRITERS LABORATORIES (UL)	
UL Bld Mat Dir	(updated continuously online) Building Materials Directory

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance with Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Hardware Schedule; G

Keying System; G

SD-03 Product Data

Hardware Items; G

SD-08 Manufacturer's Instructions

Installation

SD-10 Operation and Maintenance Data

Hardware Schedule Items, Data Package 1; G

SD-11 Closeout Submittals

Key Bitting

1.3 PRODUCT DATA

Indicate fire-ratings at applicable components.

1.4 HARDWARE SCHEDULE

Prepare and submit hardware schedule in the following form:

Hardware Item	Quantity	Size	Reference Publication Type No.	Finish	Mfr Name and Catalog No.	Key Control Symbols	UL Mark (If fire-rated and listed)	BHMA Finish Designation

In addition, submit hardware schedule data package 1 in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA.

1.5 KEY BITTING CHART REQUIREMENTS

1.5.1 Requirements

Submit key bitting charts to the Contracting Officer prior to completion of the work. Include:

- a. Complete listing of all keys (e.g. AA1 and AA2).
- b. Complete listing of all key cuts (AA1-123456, AA2-123458).
- c. Tabulation showing which key fits which door.
- d. Copy of floor plan showing doors and door numbers.
- e. Listing of 20 percent more key cuts than are presently required in each master system.

1.6 QUALITY CONTROL

1.6.1 Hardware Manufacturers and Modifications

Provide, as far as feasible, locks, hinges, and closers of one lock, hinge, or closer manufacturer's make. Modify hardware as necessary to provide features indicated or specified.

1.6.2 Key Shop Drawings Coordination Meeting

Prior to the submission of the key shop drawing, the Contracting Officer, Contractor, Door Hardware Subcontractor, using Activity and Base Locksmith must meet to discuss and coordinate key requirements for the facility.

1.7 DELIVERY, STORAGE, AND HANDLING

Deliver hardware in original individual containers, complete with necessary appurtenances including fasteners and instructions. Mark each individual container with item number as shown on hardware schedule. Deliver permanent keys and removable cores to the Contracting Officer, either directly or by certified mail. Deliver construction master keys with the locks.

PART 2 PRODUCTS

2.1 TEMPLATE HARDWARE

Hardware applied to metal or to prefinished doors must be manufactured

using a template. Provide templates to door and frame manufacturers in accordance with ANSI/BHMA A156.7 for template hinges. Coordinate hardware items to prevent interference with other hardware.

2.2 HARDWARE FOR FIRE DOORS AND EXIT DOORS

Provide all hardware necessary to meet the requirements of NFPA 72 for door alarms, NFPA 80 for fire doors, NFPA 101 for exit doors, NFPA 252 for fire tests of door assemblies, ABA/ADA accessibility requirements, and all other requirements indicated, even if such hardware is not specifically mentioned in paragraph HARDWARE SCHEDULE. Provide Underwriters Laboratories, Inc. labels for such hardware in accordance with UL Bld Mat Dir or equivalent labels in accordance with another testing laboratory approved in writing by the Contracting Officer.

2.3 HARDWARE ITEMS

Clearly and permanently mark with the manufacturer's name or trademark, hinges, pivots, locks, latches, exit devices, bolts and closers where the identifying mark is visible after the item is installed. For closers with covers, the name or trademark may be beneath the cover. Coordinate electrified door hardware components with corresponding components specified in Division 28 ELECTRONIC SECURITY SYSTEMS (ESS).

2.3.1 Hinges

Provide in accordance with ANSI/BHMA A156.1. Provide hinges that are 4-1/2 by 4-1/2 inch unless otherwise indicated. Construct loose pin hinges for interior doors and reverse-bevel exterior doors so that pins are non-removable when door is closed. Other anti-friction bearing hinges may be provided in lieu of ball bearing hinges.

2.3.2 Locks and Latches

2.3.2.1 Mortise Locks and Latches

Provide in accordance with ANSI/BHMA A156.13, Series 1000, Operational Grade 1, Security Grade 2. Provide mortise locks with escutcheons not less than 7 by 2-1/4 inch with a bushing at least 1/4 inch long. Cut escutcheons to fit cylinders and provide trim items with straight, beveled, or smoothly rounded sides, corners, and edges. Provide knobs and roses of mortise locks with screwless shanks and no exposed screws.

2.3.3 Exit Devices

Provide in accordance with ANSI/BHMA A156.3, Grade 1. Provide adjustable strikes for rim type and vertical rod devices. Provide open back strikes for pairs of doors with mortise and vertical rod devices. Provide touch bars in lieu of conventional crossbars and arms. Provide escutcheons not less than 7 by 2-1/4 inch.

2.3.4 High Security Locks

A GSA-approved pedestrian door deadbolt meeting Federal Specification FF-L-2890.

2.3.5 Cylinders and Cores

Provide cylinders and cores with seven pin tumblers. Provide cylinders

from the products of one manufacturer, and provide cores from the products of one manufacturer. Rim cylinders, mortise cylinders, and knobs of bored locksets have interchangeable cores which are removable by special control keys. Stamp each interchangeable core with a key control symbol in a concealed place on the core.

2.3.6 Keying System

Provide master keying system extension of the existing keying system. Provide a construction master keying system and a construction interchangeable cores. Provide key cabinet as specified.

2.3.7 Lock Trim

Provide cast, forged, or heavy wrought construction and commercial plain design for lock trim.

2.3.7.1 Lever Handles

Provide lever handles where indicated in the Hardware Schedule. Provide in accordance with ANSI/BHMA A156.3 for mortise locks of lever handles for exit devices. Provide lever handle locks with a breakaway feature (such as a weakened spindle or a shear key) to prevent irreparable damage to the lock when force in excess of that specified in ANSI/BHMA A156.13 is applied to the lever handle. Provide lever handles return to within 1/2 inch of the door face.

2.3.7.2 Texture

Provide knurled or abrasive coated knobs or lever handles for doors which are accessible to blind persons and which lead to dangerous areas.

2.3.8 Keys

Furnish one file key, one duplicate key, and one working key for each key change. Furnish one additional working key for each lock of each keyed-alike group. Furnish a quantity of key blanks equal to 20 percent of the total number of file keys. Stamp each key with appropriate key control symbol and "U.S. property - do not duplicate." Do not place room number on keys.

2.3.9 Door Bolts

Provide in accordance with ANSI/BHMA A156.16. Provide dustproof strikes for bottom bolts, except at doors having metal thresholds. Provide automatic latching flush bolts in accordance with ANSI/BHMA A156.3, Type 25.

2.3.10 Closers

Provide in accordance with ANSI/BHMA A156.4, Series C02000, Grade 1, with PT 4C. Provide with brackets, arms, mounting devices, fasteners, full size covers, except at storefront mounting, and other features necessary for the particular application. Size closers in accordance with manufacturer's printed recommendations, or provide multi-size closers, Sizes 1 through 6, and list sizes in the Hardware Schedule. Provide manufacturer's 10 year warranty.

2.3.10.1 Identification Marking

Engrave each closer with manufacturer's name or trademark, date of manufacture, and manufacturer's size designation in locations that will be visible after installation.

2.3.11 Overhead Holders

Provide in accordance with ANSI/BHMA A156.8.

2.3.12 Door Protection Plates

Provide in accordance with ANSI/BHMA A156.6.

2.3.12.1 Sizes of Kick Plates

2 inch less than door width for single doors; 1 inch less than door width for pairs of doors. Provide 16 inch kick plates for flush doors and 1 inch less than height of bottom rail for panel doors.

2.3.13 Door Stops and Silencers

Provide in accordance with ANSI/BHMA A156.16. Silencers Type L03011. Provide three silencers for each single door, two for each pair.

2.3.14 Thresholds

Provide in accordance with ANSI/BHMA A156.21. Use J35100, with vinyl or silicone rubber insert in face of stop, for exterior doors opening out, unless specified otherwise.

2.3.15 Weatherstripping Gasketing

Provide in accordance with ANSI/BHMA A156.22. Provide the type and function designation where specified in paragraph HARDWARE SCHEDULE. Provide a set to include head and jamb seals, sweep strips, and, for pairs of doors, astragals. Air leakage of weatherstripped doors not to exceed 1.25 cubic feet per minute of air per square foot of door area when tested in accordance with ASTM E283. Provide weatherstripping with one of the following:

2.3.15.1 Extruded Aluminum Retainers

Extruded aluminum retainers not less than 0.050 inch wall thickness with vinyl, neoprene, silicone rubber, or polyurethane inserts. Provide clear (natural) anodized aluminum.

2.3.15.2 Interlocking Type

Zinc or bronze not less than 0.018 inch thick.

2.3.15.3 Spring Tension Type

Spring bronze or stainless steel not less than 0.008 inch thick.

2.3.16 Lightproofing and Soundproofing Gasketing

Provide in accordance with ANSI/BHMA A156.22. Provide adjustable doorstops at heads, jambs and automatic door bottoms in accordance with the

hardware set, of extruded aluminum, clear (natural) anodized, surface applied, with vinyl fin seals between plunger and housing. Provide doorstops with solid neoprene tube, silicone rubber, or closed cell sponge gasket. Provide door bottoms with adjustable operating rod and silicone rubber or closed cell sponge neoprene gasket. Provide doorstops that are mitered at corners. Provide type and function designation where specified in paragraph HARDWARE SETS.

2.3.17 Rain Drips

Provide in accordance with ANSI/BHMA A156.22. Provide extruded aluminum rain drips, not less than 0.08 inch thick, clear anodized finish. Provide the manufacturer's full range of color choices to the Contracting Officer for color selection. Provide rain drips with a 4 inch overlap on each side of each exterior door that is not protected by an awning, roof, eave or other horizontal projection. Set drips in sealant and fasten with stainless steel screws.

2.3.17.1 Door Rain Drips

Approximately 1-1/2 inch high by 5/8 inch projection. Align bottom with bottom edge of door.

2.3.17.2 Overhead Rain Drips

Approximately 1-1/2 inch high by 2-1/2 inch projection. Align bottom with door frame rabbet.

2.3.18 Auxiliary Hardware (Other than locks)

Provide in accordance with ANSI/BHMA A156.16, Grade 1.

2.3.19 Sliding and Folding Door Hardware

Provide in accordance with ANSI/BHMA A156.14, Grade 1. Finishes to match other hardware specified herein.

2.3.20 Special Tools

Provide special tools, such as spanner and socket wrenches and dogging keys, as required to service and adjust hardware items.

2.4 FASTENERS

Provide fasteners of type, quality, size, and quantity appropriate to the specific application. Fastener finish to match hardware. Provide stainless steel or nonferrous metal fasteners in locations exposed to weather. Verify metals in contact with one another are compatible and will avoid galvanic corrosion when exposed to weather.

2.5 FINISHES

Provide in accordance with ANSI/BHMA A156.18. Provide hardware in BHMA 630 finish (satin stainless steel), unless specified otherwise. Provide items not manufactured in stainless steel in BHMA 626 finish (satin chromium plated) over brass or bronze, except prime coat finish for surface door closers, and except BHMA 600 finish (primed for painting) for steel hinges. Provide hinges for exterior doors in stainless steel with BHMA 630 finish or chromium plated brass or bronze with BHMA 626 finish.

Furnish exit devices in BHMA 626 finish in lieu of BHMA 630 finish except where BHMA 630 is specified under paragraph HARDWARE SETS. Match exposed parts of concealed closers to lock and door trim. Match hardware finish for aluminum doors to the doors.

2.6 KEY CABINET AND CONTROL SYSTEM

Provide in accordance with ANSI/BHMA A156.5, Type required to yield a capacity (number of hooks) 50 percent greater than the number of key changes used for door locks.

PART 3 EXECUTION

3.1 INSTALLATION

Provide hardware in accordance with manufacturers' printed installation instructions. Fasten hardware to wood surfaces with full-threaded wood screws or sheet metal screws. Provide machine screws set in expansion shields for fastening hardware to solid concrete and masonry surfaces. Provide toggle bolts where required for fastening to hollow core construction. Provide through bolts where necessary for satisfactory installation.

3.1.1 Weatherstripping Installation

Provide full contact, weathertight seals that allow operation of doors without binding the weatherstripping.

3.1.1.1 Stop Applied Weatherstripping

Fasten in place with color matched sheet metal screws not more than 9 inch on center after doors and frames have been finish painted.

3.1.1.2 Interlocking Type Weatherstripping

Provide interlocking, self adjusting type on heads and jambs and flexible hook type at sills. Nail weatherstripping to door 1 inch on center and to heads and jambs at 4 inch on center.

3.1.1.3 Spring Tension Type Weatherstripping

Provide spring tension type on heads and jambs. Provide bronze nails with bronze. Provide stainless steel nails with stainless steel. Space nails not more than 1-1/2 inch on center.

3.1.2 Lightproofing and Soundproofing Installation

Provide as specified for stop applied weatherstripping.

3.1.3 Threshold Installation

Extend thresholds the full width of the opening and notch end for jamb stops. Set thresholds in a full bed of sealant and anchor to floor with cadmium-plated, countersunk, steel screws in expansion sleeves.

3.2 FIRE DOORS AND EXIT DOORS

Provide hardware in accordance with NFPA 72 for door alarms, NFPA 80 for fire doors, NFPA 101 for exit doors, and NFPA 252 for fire tests of door

assemblies. .

3.3 HARDWARE LOCATIONS

Provide in accordance with SDI/DOOR A250.8, unless indicated or specified otherwise.

- a. Kick and Armor Plates: Push side of single-acting doors. Both sides of double-acting doors.
- b. Mop Plates: Bottom flush with bottom of door.

3.4 KEY CABINET AND CONTROL SYSTEM

Locate where directed . Tag one set of file keys and one set of duplicate keys. Place other keys in appropriately marked envelopes, or tag each key. Provide complete instructions for setup and use of key control system. On tags and envelopes, indicate door and room numbers or master or grand master key.

3.5 FIELD QUALITY CONTROL

After installation, protect hardware from paint, stains, blemishes, and other damage until acceptance of work. Submit notice of testing 15 days before scheduled, so that testing can be witnessed by the Contracting Officer. Adjust hinges, locks, latches, bolts, holders, closers, and other items to operate properly. Demonstrate that permanent keys operate respective locks, and give keys to the Contracting Officer. Correct, repair, and finish, errors in cutting and fitting and damage to adjoining work.

3.6 HARDWARE SETS

Provide hardware for aluminum doors under this section. Deliver Hardware templates and hardware, except field applied hardware, to the aluminum door and frame manufacturer for use in fabricating doors and frames.

FINISH	FINISH DESCRIPTION	BASE METAL
600	PRIMED FOR PAINTING	STEEL
619	SATIN NICKEL	BRASS/BRONZE
626	SATIN CHROMIUM	BRASS/BRONZE
630	STAINLESS STEEL	STAINLESS STEEL
646	SATIN NICKEL	STEEL
689	PAINT	ALUMINUM
715	PRIMED FOR PAINTING	ALUMINUM
719	MILL FINISH UNCOATED	ALUMINUM

HW-1 (Door 101A,101B,103B FIRE RATED)IF OPTION 3 IS NOT AWARDED, DOOR 103B IS OMITTED IN HW-1 AND INCLUDED IN HW-4.

6	EA	HINGES, A5111 (4-1/2 X 4-1/2)	630
1	EA.	LOCKSET, F04 (W/ LEVER HANDLE)	626
1	EA	LEVER EXTENSION FLUSH BOLTS, L04081 (ONE AT TOP AND ONE AT BOTTOM OF INACTIVE LEAF)	646
2	EA	CLOSER, C02021 (PARALLEL ARM MOUNT) (PAINT TO MATCH ADJACENT DOOR FRAME)	600
1	EA	METAL ASTRAGAL (PAINT TO MATCH DOOR)	600
1	EA	COORDINATOR	
1	SET	SEAL (HEAD AND JAMB), R0Y154	
1	EA	THRESHOLD, J36133	719

HW-2 (101C,101H,101J,101O,109B,~~111~~
114B,114C,103C,103D,125,301B,301D,401A EXIT DOORS) DOOR 114B, 114C IS
OMITTED IF OPTION 3 IS NOT AWARDED. DOOR 10912C IS INCLUDED IN HW-2 AND
OMITTED IN HW-21 IF OPTION 3 IS NOT AWARDED.

DOOR 401A IS OMITTED IF OPTION 6 AND 7 IS NOT AWARDED.

DOOR 301B,301D IS OMITTED IF OPTION 8 IS NOT AWARDED

3	EA.	HINGES, A5111 (4-1/2 X 4-1/2 NRP)	630
1	EA.	EXIT DEVICE, TYPE 1/F08 (WITH LEVER HANDLE)	626**
1	EA.	CLOSER, C02021 (PARALLEL ARM MOUNT) (PAINT TO MATCH ADJACENT DOOR FRAME)	600
1	SET	WEATHERSTRIPPING	
1	EA.	THRESHOLD, J32130	719
1	EA	DOOR SWEEP, ROY435	
1	EA	RAIN DRIP (TOP)	

**EXIT DEVICE MANUFACTURER SHALL PROVIDE ALL NECESSARY TRIM (ESCUTCHEON PLATES, LEVER HANDLES, LOCK CYLINDERS, ETC.) FOR A COMPLETE AND USABLE EXIT DEVICE.

HW-3 (OVERHEAD DOORS
101D,101E,101F,101G,101K,101L,101M,101N,122B,127B,301A,301C,301E,401B)DOOR
401B IS OMITTED IF OPTION 6 AND 7 IS NOT AWARDED.
DOOR 301A,301C,301E IS OMITTED IF OPTION 8 IS NOT AWARDED.

ALL HARDWARE SHALL BE PROVIDED BY THE OVERHEAD COILINNG DOOR MANUFACTURER TO INCLUDE WEATHERSTRIPPING AND LOCKING DEVICE. ALL LOCKSETS SHALL HAVE INTERCHANGEABLE CORES THAT ARE COMPATIBLE WITH ALL OTHER DOOR LOCKSETS.

DOORS SHALL BE ELECTRIC OPERATION WITH MANUAL OPERATOR AS BACKUP (SEE SECTION 08 33 23).

HW-4 (Door 102,114A) DOOR 114A IS OMITTED IF OPTION 3 IS NOT AWARDED. ADDITIONALLY, DOOR 103B WILL BECOME AN EGRESS DOOR AND TO BE INCLUDED IN HW-4 IF OPTION 3 IS NOT AWARDED.

6	EA	HINGES, A5111 (4-1/2 X 4-1/2) NRP	630
1	EA	EXIT DEVICE, TYPE 3/F08 (W/ LEVER HANDLE) (AT ACTIVE LEAF)	626
1	EA	EXIT DDEVICE TYPE 8/F08 (W/LEVER HANDLE) (AT INACTIVE LEAF)	646
2	EA	CLOSER, C02021 (PARALLEL ARM MOUNT) (PAINT TO MATCH ADJACENT DOOR FRAME)	600
1	EA	METAL ASTRAGAL (PAINT TO MATCH DOOR)	600
1	EA	COORDINATOR	
1	SET	WEATHERSTRIPPING	
1	EA	THRESHOLD, J36133	719
2	EA	SWEEP SEAL (BOTTOM)	719

**EXIT DEVICE MANUFACTURER SHALLL PROVIDE ALLL NECESSARY TRIM (ESCUTCHEON PLATES, LEVER HANDLES, LOCK CYLINDERS, ETC.) FOR A COMPLETE AND USABLE EXIT DEVICE.

HW-5 (Door 103A,

6	EA	HINGES, A5111 (4-1/2 X 4-1/2) NRP	630
2	EA	EXIT DEVICE, TYPE 8/F08 (W/ LEVER HANDLE)	626
2	EA	CLOSER, C02021 (PARALLEL ARM MOUNT) (PAINT TO MATCH ADJACENT DOOR FRAME)	600
1	SET	SEAL (HEAD AND JAMB) ROY154	

**EXIT DEVICE MANUFACTURER SHALLL PROVIDE ALLL NECESSARY TRIM (ESCUTCHEON PLATES, LEVER HANDLES, LOCK CYLINDERS, ETC.) FOR A COMPLETE AND USABLE EXIT DEVICE.

HW-6 (104,106,115,116 RESTROOMS) DOOR 115,116 IS OMITTED IF OPTION 3 IS NOT AWARDED

3	EA	HINGES, A5111 (4-1/2 X 4-1/2)	630
1	EA	PUSH PLATE, J301	630
1	EA	PULL PLATE, J405	630
1	EA	DOOR STOP, L02251	630
1	EA	CLOSER, C02011 (HINGE SIDE MOUNT) (PAINT TO MATCH ADJACENT DOOR FRAME)	600
3	EA	SILENCERS, L03011	
1	EA	KICK PLATE	630

HW-7 (107 WOMEN SHOWER)

3	EA	HINGES, A5111 (4-1/2 X 4-1/2)	630
1	EA	LOCKSET, F02 (W/ LEVER HANDLE)	626
1	CLOSER,	C02021 (PARALLEL ARM MOUNT) (PAINT TO MATCH ADJACENT DOOR FRAME)	600
1	EA	DOOR STOP, L02251 (DRS 111 & 310 ONLY)	630

	3 EA SILENCERS, L03011	
HW-8	(105 MEN SHOWER)	
	3 EA HINGES, A5111 (4-1/2 X 4-1/2)	630
	1 EA LATCHSET, F01 (W/ LEVER HANDLE)	626
	1 CLOSER, C02021 (PARALLEL ARM MOUNT)	600
	(PAINT TO MATCH ADJACENT DOOR FRAME)	
	1 EA DOOR STOP, L02251	630
	3 EA SILENCERS, L03011	
HW-9	(110 NURSING MOTHER'S ROOM)	
	3 EA HINGES, A5111 (4-1/2 X 4-1/2)	630
	1 EA LOCKSET, F02 (W/ LEVER HANDLE)	626
	1 CLOSER, C02021 (PARALLEL ARM MOUNT)	600
	(PAINT TO MATCH ADJACENT DOOR FRAME)	
	1 EA DOOR STOP, L02251 (DRS 111 & 310 ONLY)	630
	3 EA SILENCERS, L03011	
HW-10	(108 JANITOR)	
	3 EA HINGES, A5111 (4-1/2 X 4-1/2)	630
	1 EA LOCKSET, F07 (W/ LEVER HANDLE)	626
	1 EA DOOR STOP, L02251	630
	3 EA SILENCERS, L03011	
HW-11	(109A)	
	3 EA HINGES, A5111 (4-1/2 X 4-1/2)	630
	1 EA LATCHSET, F01 (W/ LEVER HANDLE)	626
	1 CLOSER, C02021 (PARALLEL ARM MOUNT)	600
	(PAINT TO MATCH ADJACENT DOOR FRAME)	
	1 EA DOOR STOP, L02251	630
	3 EA SILENCERS, L03011	
HW-12	(111 2B)	
	3 EA HINGES, A5111 (4-1/2 X 4-1/2)	630
	1 EA LOCKSET, F06 (W/ LEVER HANDLE)	626
	1 CLOSER, C02021 (PARALLEL ARM MOUNT)	600
	(PAINT TO MATCH ADJACENT DOOR FRAME)	
	1 EA DOOR STOP, L02251	630
	3 EA SILENCERS, L03011	
HW-13	(117) DOOR 117 IS OMITTED IF OPTION 3 IS NOT AWARDED	
	3 EA HINGES, A5111 (4-1/2 X 4-1/2)	630
	1 EA LOCKSET, F07 (W/ LEVER HANDLE)	626
	1 EA DOOR STOP, L02251	630
	3 EA SILENCERS, L03011	
HW-14	(SIPR DOOR 119)	
	2 EA HINGES, A5111 (4-1/2 X 4-1/2) NRP	630
**	1 EA CDX-09 DOOR LOCK	
	1 EA CLOSER, C02021 (PARALLEL ARM MOUNT)	600
	(PAINT TO MATCH ADJACENT DOOR FRAME)	
	1 EA AUTOMATIC DOOR BOTTOM, ROY336	
	1 SET SEAL (HEAD AND JAMB), ROY156	

	1 EA	THRESHOLD, J32130	719
** X-09 SHALL MEET FEDERAL SPECIFICATION FF-L-2890			
HW-15	(131)		
	6 EA	HINGES, A5111 (4-1/2 X 4-1/2) NRP	630
	1 EA	LOCKSET, F07 (W/ LEVER HANDLE)	626
	2 EA	LEVER EXTENSION FLUSH BLOTS, L04081	646
		(ONE AT TOP AND ONE AT BOTTOM OF INACTIVE LEAF)	
	2 EA	CLOSER, C02021 (PARALLEL ARM MOUNT)	
		(PAINT TO MATCH ADJACENT DOOR FRAME)	600
	1 EA	METAL ASTRAGAL (PAINT TO MATCH DOOR)	600
	1 EA	COORDINATOR	
	1 SET	WEATHERSTRIPPING	
	1 EA	THRESHOLD, J32130	719
	1 EA	DOOR SWEEP, ROY435	
	1 EA	RAIN DRIP (TOP)	
HW-16	(111 ,120)		
	3 EA	HINGES, A5111 (4-1/2 X 4-1/2) NRP)	630
	1 EA	LOCKSET, F07 (W/ LEVER HANDLE)	626
	1 SET	WEATHERSTRIPPING	
	1 EA	THRESHOLD, J32130	719
	1 EA	DOOR SWEEP, ROY435	
	1 EA	RAIN DRIP (TOP)	
HW-17	(121,128A)		
	3 EA	HINGES, A5111 (4-1/2 X 4-1/2)	630
	1 EA	LOCKSET, F04 (W/ LEVER HANDLE)	626
	1 EA	CLOSER, C02021 (PARALLEL ARM MOUNT)	600
		(PAINT TO MATCH ADJACENT DOOR FRAME)	
	1 EA	DOOR STOP, L02251	630
	3 EA	SILENCERS, L03011	
HW-18	(122A,128B)		
	6 EA	HINGES, A5111 (4-1/2 X 4-1/2)	630
	1 EA	LOCKSET, F04 (W/ LEVER HANDLE)	626
	1 EA	LEVER EXTENSION FLUSH BLOTS, L04081	646
		(ONE AT TOP AND ONE AT BOTTOM OF INACTIVE LEAF)	
	2 EA	CLOSER, C02021 (PARALLEL ARM MOUNT)	
		(PAINT TO MATCH ADJACENT DOOR FRAME)	600
	1 EA	METAL ASTRAGAL (PAINT TO MATCH DOOR)	600
	1 EA	COORDINATOR	
	3 EA	SILENCERS, L03011	
	1 EA	THRESHOLD, J32130	719
HW-19	(126)		
	6 EA	HINGES, A5111 (4-1/2 X 4-1/2)	630
	1 EA	PUSH PLATE, J301	630
	1 EA	PULL PLATE, J405	630
	2 EA	CLOSER, C02021 (PARALLEL ARM MOUNT)	
		(PAINT TO MATCH ADJACENT DOOR FRAME)	600
	1 SET	SEAL (HEAD AND JAMB), ROY154	

HW-20	(129,130 OFFICE)		
	3 EA	HINGES, A5111 (4-1/2 X 4-1/2)	630
	1 EA	LOCKSET, F04 (W/ LEVER HANDLE)	626
	1 EA	DOOR STOP, L02251	630
	3 EA	SILENCERS, L03011	
HW-21	(10912C ,123,127A FIRE RATED)IF OPTION 3 IS NOT AWARDED. DOOR 10912C		
	IS OMITTED IN HW-21 AND INCLUDED IN HW-2.		
	3 EA	HINGES, A5111 (4-1/2 X 4-1/2)	630
	1 EA	LOCKSET, F07 (W/ LEVER HANDLE)	626
	1 EA	DOOR STOP, L02251	630
	3 EA	SILENCERS, L03011	
	1 EA	CLOSER, C02021 (PARALLEL ARM MOUNT)	
		(PAINT TO MATCH ADJACENT DOOR FRAME)	600
	1 SET	SEAL (HEAD AND JAMB), R0Y154	
HW-22	(124)		
	3 EA	HINGES, A5111 (4-1/2 X 4-1/2)	630
	1 EA	LOCKSET, F07 (W/ LEVER HANDLE)	626
	1 EA	DOOR STOP, L02251	630
	3 EA	SILENCERS, L03011	
	1 EA	CLOSER, C02021 (PARALLEL ARM MOUNT)	
		(PAINT TO MATCH ADJACENT DOOR FRAME)	600
	1 SET	SEAL (HEAD AND JAMB), R0Y154	
	1 SET	WEATHERSTRIPPING	
	1 EA	THRESHOLD, J32130	719
	1 EA	DOOR SWEEP, ROY435	
	1 EA	RAIN DRIP (TOP)	
HW-23	(301F,302,303,304)		
	DOOR 301F,302,303,304 IS OMITTED IF OPTION 8 IS NOT AWARDED.		
	6 EA	HINGES, A5111 (4-1/2 X 4-1/2) NRP	630
	1 EA	EXIT DEVICE, TYPE 3/F08 (W/ LEVER HANDLE)	626
		(AT ACTIVE LEAF)	
	1 EA	LEVER EXTENSION FLUSH BOLTS, L04081	646
		(ONE AT TOP AND ONE AT BOTTOM OF INACTIVE LEAF)	
	2 EA	CLOSER, C02021 (PARALLEL ARM MOUNT)	
		(PAINT TO MATCH ADJACENT DOOR FRAME)	600
	1 SET	WEATHERSTRIPPING	
	1 EA	THRESHHOLD, J36133	719
	1 EA	RAINDRIP (TOP)	
	1 EA	METAL ASTRAGAL (PAINT TO MATCH DOOR)	600
	1 EA	COORDINATOR	

**EXIT DEVICE MANUFACTURER SHALL PROVIDE ALL NECESSARY TRIM (ESCUTCHEON PLATES, LEVER HANDLES, LOCK CYLINDERS, ETC.) FOR A COMPLETE AND USABLE EXIT DEVICE.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 32 - EXTERIOR IMPROVEMENTS

SECTION 32 01 19.61

SEALING OF JOINTS IN RIGID PAVEMENT

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 QUALITY ASSURANCE
 - 1.3.1 Test Requirements
 - 1.3.2 Trial Joint Sealant Installation
- 1.4 DELIVERY, STORAGE, AND HANDLING
- 1.5 ENVIRONMENTAL REQUIREMENTS
- 1.6 TRAFFIC CONTROL

PART 2 PRODUCTS

- 2.1 SEALANTS
- 2.2 PRIMERS
- 2.3 BOND BREAKERS
 - 2.3.1 Blocking Media/Backup Materials
 - 2.3.2 Bond Breaking Tapes

PART 3 EXECUTION

- 3.1 EXECUTING EQUIPMENT
 - 3.1.1 Joint Cleaning Equipment
 - 3.1.1.1 Tractor-Mounted Routing and Plowing Tool
 - 3.1.1.2 Concrete Saw
 - 3.1.1.3 Sandblasting Equipment
 - 3.1.1.4 Waterblasting Equipment
 - 3.1.1.5 Air Compressor
 - 3.1.1.6 Vacuum Sweeper
 - 3.1.1.7 Hand Tools
 - 3.1.2 Sealing Equipment
 - 3.1.2.1 Cold-Applied, Single-Component Sealing Equipment
- 3.2 SAFETY
- 3.3 PREPARATION OF JOINTS
 - 3.3.1 Sawing
 - 3.3.1.1 Facing of Joints
 - 3.3.1.2 Refacing of Random Cracks
 - 3.3.2 Final Cleaning of Joints
 - 3.3.2.1 Sandblasting
 - 3.3.3 Bond Breaker
 - 3.3.3.1 Blocking Media (Backer Rod) (Except for Expansion Joints)
 - 3.3.3.2 Bond Breaking Tape
 - 3.3.4 Rate of Progress of Joint Preparation
 - 3.3.5 Disposal of Debris
- 3.4 PREPARATION OF SEALANT
 - 3.4.1 Single-Component, Cold-Applied Sealants

- 3.5 INSTALLATION OF SEALANT
 - 3.5.1 Time of Application
 - 3.5.2 Sealing Joints
- 3.6 INSPECTION/FIELD QUALITY CONTROL
 - 3.6.1 Joint Cleaning
 - 3.6.2 Sampling Sealant
 - 3.6.3 Sealant Application Equipment
 - 3.6.4 Joint Sealant
- 3.7 ACCEPTANCE
- 3.8 CLEAN-UP

-- End of Section Table of Contents --

SECTION 32 01 19.61

SEALING OF JOINTS IN RIGID PAVEMENT

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM C1016	(2014) Standard Test Method for Determination of Water Absorption of Sealant Backing (Joint Filler) Material
ASTM D5249	(2010; R 2016) Standard Specification for Backer Material for Use with Cold-and Hot-Applied Joint Sealants in Portland-Cement Concrete and Asphalt Joints
ASTM D5893/D5893M	(2016) Standard Specification for Cold Applied, Single Component, Chemically Curing Silicone Joint Sealant for Portland Cement Concrete Pavements

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Sealants; G

Submit catalog cuts, specifications, Safety Data Sheets and other information documenting conformance to Contract requirements.

Manufacturer's Recommendations; G

SD-04 Samples

Sealants

Provide for possible Government testing a 5-gal sample of each sealant with associated primer to the Contracting Officer a minimum of 60 days prior to its use on the job. Provide factory-sealed containers with a factory applied label showing the following information:

Name of sealant

Identification of component, or primer

Specification number and type

Manufacturer's name

Manufacturer's lot and batch number

Date of Manufacture (month and year)

Shelf life retest date (month and year)

List of hazardous components

Quantity of material in container (volume)

Storage instructions

Instructions for use

Blocking Media/Backup Materials

Backer Rod

Bond Breaking Tapes

SD-06 Test Reports

Sealant

SD-07 Certificates

Equipment List

SD-08 Manufacturer's Instructions

Sealants

Provide instructions that include, but not limited to: storage requirements, ambient temperature and humidity ranges, and moisture condition of joints for successful installation; requirements for preparation of joints; safe heating temperature; mixing instructions; installation equipment and procedures; application and disposal requirements; compatibility of sealant with filler material; curing requirements; and restrictions to be adhered to in order to reduce hazards to personnel or to the environment. Submit instructions at least 30 days prior to use.

1.3 QUALITY ASSURANCE

1.3.1 Test Requirements

Test the sealant and backup or separating material for conformance with the referenced material specification. Perform testing of the materials in an approved independent or Manufacturer laboratory and submit certified copies of the sealant test reports for approval 60 days prior to the use of the materials at the job site. Submit samples to be retained by the Government for possible future testing if the materials appear defective

during or after application. Conformance with the requirements of the laboratory tests specified does not constitute final acceptance of the materials. Base final acceptance on the performance of the in-place materials. Submit samples of the materials (sealant, primer if required, and backup material), in sufficient quantity for testing and approval 90 days prior to the beginning of work. Do not use material until it has been approved.

1.3.2 Trial Joint Sealant Installation

Prior to cleaning and sealing the joints for the entire project, prepare a test section in location approved by the Contracting Officer and at least 100 ft long using the specified materials and approved equipment, so as to demonstrate the proposed joint preparation and sealing of the types of joints in the project. Following the completion of the test section and before any other joint is sealed, inspect the test section to determine that the materials and installation meet the requirements specified. Inspect joint seal test section. Correct deficiencies and obtain approval of test section prior to installing joint seals. If it is determined that the materials or installation do not meet the requirements, remove the materials, and reclean and reseal the joints at no cost to the Government. Permit the test section meeting the requirements to be incorporated into the permanent work. Prepare and seal other joints in the manner approved for sealing the test section. Notify the Contracting Officer upon completion of the test section.

1.4 DELIVERY, STORAGE, AND HANDLING

Inspect materials delivered to the site for visible damage, and unload and store with a minimum of handling. Deliver joint materials in original sealed containers and protect from freezing or overheating. Provide jobsite storage facilities capable of maintaining temperature ranges within manufacturers recommendations.

1.5 ENVIRONMENTAL REQUIREMENTS

Do not proceed with work when weather conditions detrimentally affect the quality of cleaning joints or applying sealants. Proceed with joint preparation and sealing only when weather conditions are in accordance with manufacturer's instructions. Install joint sealant to dry surfaces and protect sealant and bond breakers from moisture.

1.6 TRAFFIC CONTROL

Do not permit vehicular or heavy equipment traffic on the pavement in the area of the joints being sealed during the protection and curing period of the sealant. Permit traffic on the pavement at the end of the curing period.

PART 2 PRODUCTS

2.1 SEALANTS

All areas indicated in the drawings that will not receive preformed compression seals, shall be sealed with non-sag silicone conforming to ASTM D5893/D5893M.

2.2 PRIMERS

Use primers in accordance with the recommendation of the manufacturer.

2.3 BOND BREAKERS

2.3.1 Blocking Media/Backup Materials

Provide backup (joint filler) material that is a compressible, nonshrinking, nonstaining, nonabsorbing, nonreactive material with the sealant. Use backup material compliant with ASTM D5249. Use material with a water absorption of not more than 5 percent of the sample weight when tested in accordance with ASTM C1016. Use backup (joint filler) material that is 25 plus or minus 5 percent larger in diameter than the nominal width of the crack. Use blocking media consistent with the sealant manufacturer's installation instructions.

2.3.2 Bond Breaking Tapes

Provide a bond breaking tape or separating material that is a flexible, nonshrinkable, nonabsorbing, nonstaining, and nonreacting adhesive-backed tape. Use bond breaker tape approximately 1/8 in wider than the nominal width of the joint and that does not bond to the sealant. Use bond breaking tape shall be consistent with the sealant manufacturer's installation instructions.

PART 3 EXECUTION

Joint preparation and sealant storage and installation shall be performed in accordance with the drawings and specifications and as modified by the joint sealant Manufacturer's recommendations.

3.1 EXECUTING EQUIPMENT

Submit equipment list and description of the equipment to be used and a statement from the supplier of the sealant that the proposed equipment is acceptable for installing the specified sealant. Use equipment for heating, mixing, and installing seals in accordance with the instructions provided by the sealant manufacturer. Provide equipment, tools, and accessories necessary to clean existing joints and install liquid joint sealants. Maintain machines, tools, and other equipment in proper working condition. Submit a list of proposed equipment to be used in performance of construction work including descriptive data, 60 days prior to use on the project.

3.1.1 Joint Cleaning Equipment

3.1.1.1 Tractor-Mounted Routing and Plowing Tool

Use equipment capable of maintaining accurate cutting depth and width control. Use a joint plow equipped with a spring or hydraulic mechanism to release pressure on the tool prior to spalling the concrete. Do not permit the use of V-shaped tools or rotary impact routing devices. Permit the use of hand-operated spindle routing devices to clean and enlarge random cracks.

3.1.1.2 Concrete Saw

Provide a self-propelled power saw, with water-cooled diamond or abrasive

saw blades, for cutting joints to the depths and widths specified, for refacing joints, cleaning sawed joints where sandblasting does not provide a clean joint, widening, or deepening existing joints as specified without damaging the sides, bottom, or top edge of joints. Permit single or gang type blades with one or more blades mounted in tandem for fast cutting. Select saw adequately powered and sized to cut specified opening with not more than two passes of the saw through the joint.

3.1.1.3 Sandblasting Equipment

Include with the sandblasting equipment an air compressor, hose, and long-wearing venturi-type nozzle of proper size, shape and opening. Do not permit the maximum nozzle opening to exceed 1/4 in. Use a portable air compressor capable of providing not less than 150 cfm and maintaining a line pressure of not less than 90 psi at the nozzle while in use. Demonstrate compressor capability, under job conditions, before approval. Use a compressor equipped with traps that maintain the compressed air free of oil and water. Use a nozzle with an adjustable guide that holds the nozzle aligned with the joint approximately 1 in above the pavement surface. Adjust the height, angle of inclination and the size of the nozzle to secure satisfactory results.

3.1.1.4 Waterblasting Equipment

Include with the waterblasting equipment a trailer-mounted water tank, pumps, high-pressure hose, wand with safety release cutoff control, nozzle, and auxiliary water resupply equipment. Provide water tank and auxiliary resupply equipment of sufficient capacity to permit continuous operations. Use a nozzle with an adjustable guide that holds the nozzle aligned with the joint approximately 1 in above the pavement surface. Adjust the height, angle of inclination and the size of the nozzle to obtain satisfactory results. Use a pressure gauge mounted at the pump that shows the pressure in psi at which the equipment is operating.

3.1.1.5 Air Compressor

Use a portable air compressor capable of operating the sandblasting equipment and capable of blowing out sand, water, dust adhering to sidewalls of concrete, and other objectionable materials from the joints. Use a compressor that provides air at a pressure not less than 90 psi and a minimum rate of 150 cubic ft of air per minute at the nozzles and free of oil.

3.1.1.6 Vacuum Sweeper

Use a self-propelled, vacuum pickup sweeper capable of completely removing loose sand, water, joint material, and debris from pavement surface.

3.1.1.7 Hand Tools

Permit the use of hand tools, such as brooms and chisels, when approved, for removing defective sealant from a crack and repairing or cleaning the crack faces.

3.1.2 Sealing Equipment

Use joint sealing equipment of a type required by the sealant manufacturer's installation instructions. Use equipment capable of installing sealant to the depths, widths and tolerances indicated. Do not

proceed with joint sealing when malfunctions are noted until the malfunctions are corrected.

3.1.2.1 Cold-Applied, Single-Component Sealing Equipment

Use equipment for installing ASTM D5893/D5893M single component joint sealants that consists of an extrusion pump, air compressor, following plate, hoses, and nozzle for transferring the sealant from the storage container into the joint opening. Use a nozzle with dimensions that allows the tip of the nozzle to extend into the joint to allow sealing from the bottom of the joint to the top. Maintain the initially approved equipment in good working condition, serviced in accordance with the supplier's instructions, and unaltered in any way without obtaining prior approval. Use Teflon-lined hoses and seals to prevent premature curing and moisture penetration and to withstand pumping pressures. Use equipment free of contamination from previously used or other type sealant. Permit use of small hand-held air-powered equipment (i.e., caulking guns) for small applications.

3.2 SAFETY

Do not place sealant within 25 ft of LOX equipment, LOX storage, or LOX piping. Clean joints in this area and leave them unsealed.

In accordance with the provisions of the Contract respecting "Accident Prevention," take appropriate measures to control worker exposure to toxic substances during the work. Provide personnel protective equipment as required. Make Material Safety Data Sheets (Department of Labor Form OSHA-20 or comparable form) available on the site.

Perform sandblasting operations in accordance to applicable provisions in paragraph entitled "Abrasive Blasting" of Section 01 57 19 TEMPORARY ENVIRONMENTAL CONTROLS.

3.3 PREPARATION OF JOINTS

Do not proceed with final cleaning operations by more than one working day in advance of sealant. Clean joints by removing existing joint sealing compound, bond-breakers, dirt, laitance, curing compound, filler, and protrusions of hardened concrete from the sides and upper edges of the joint space to be sealed and other foreign material with the equipment. Do not permit cleaning procedures that damage joints or previously repaired patches by chipping or spalling. Precise shape and size of existing joints vary, and conditions of joint walls and edges vary and include but are not limited to rounding, square edges, sloping, chips, voids, depressions, and projections.

3.3.1 Sawing

3.3.1.1 Facing of Joints

Accomplish facing of joints using a concrete saw as specified in paragraph EQUIPMENT to saw through sawed and filler-type joints to loosen and remove material until the joint is clean and open to the full specified width and depth. Provide exposure of newly clean concrete through removal. Remove burrs and irregularities from sides of joint faces. Stiffen the blade with a sufficient number of dummy (used) blades or washers. Clean, immediately following the sawing operation, the joint opening using a water jet to remove saw cuttings and debris and adjacent concrete

surface. Protect adjacent previously cleaned joint spaces from receiving water and debris during the cleaning operation.

- a. Joint Widening (Except Expansion Joints): Saw joints having grooves less than 3/8 in wide and less than 1 in deep to a minimum width and to the minimum depth, as indicated.

3.3.1.2 Refacing of Random Cracks

Accomplish sawing of the cracks using a power-driven concrete saw as specified in paragraph EQUIPMENT. Use a saw blade 6 in or less in diameter to enable the saw to follow the trace of the crack. Stiffen the blade with dummy (or used) blades or washers. Immediately following the sawing operation, clean the crack opening using a water jet to remove saw cuttings and debris.

3.3.2 Final Cleaning of Joints

3.3.2.1 Sandblasting

Following removal of existing sealant, and sawing, and immediately before resealing, clean newly exposed concrete joint faces and pavement surface extending to a minimum of 1/2 in up to 2 in from each joint edge by sandblasting until concrete surfaces in the joint space are free of sealants, dust, dirt, water and other foreign materials that prevent bonding of new sealants to the concrete. Use sand particles of the proper size and quality for the work. Perform sandblasting with specified nozzles, air compressor, and other appurtenant equipment. Position nozzles to clean the joint faces. Make at least two passes; one for each joint face. Make as many passes as required for proper cleaning. Immediately prior to sealing the joint, blow out the joint spaces with compressed air until completely free of sand, water, and dust. Install joint sealants to dry joints. Replace expansion joint filler material damaged in performing the work with new materials of the same type and dimensions as the existing material, or with appropriate blocking media.

3.3.3 Bond Breaker

At the time the joints receive the final cleaning and are dry, install bond breaker material as indicated with a steel wheel or other approved device.

3.3.3.1 Blocking Media (Backer Rod) (Except for Expansion Joints)

When the joint opening is of a greater depth than indicated for the sealant depth, plug or seal off the lower portion of the joint opening using a blocking media/back-up material to prevent the entrance of the sealant below the specified depth. Take care to ensure that the blocking media/backup material is placed at the specified depth and is not stretched or twisted during installation.

3.3.3.2 Bond Breaking Tape

Where inserts or filler materials contain bitumen, or the depth of the joint opening does not allow for the use of a backup material, insert a bond breaker separating tape to prevent incompatibility with the filler materials and three-sided adhesion of the sealant. Bond the tape to the bottom of the joint opening to prevent it from floating up into the new sealant.

3.3.4 Rate of Progress of Joint Preparation

Limit the stages of joint preparation, including sandblasting, air pressure cleaning and placing of the back-up material to only that lineal footage that can be sealed during the same day.

3.3.5 Disposal of Debris

Sweep pavement surface to remove excess joint material, dirt, water, sand, and other debris by vacuum sweepers or hand brooms. Remove the debris immediately and properly dispose of off Government property.

3.4 PREPARATION OF SEALANT

3.4.1 Single-Component, Cold-Applied Sealants

Inspect the ASTM D5893/D5893M sealant and containers prior to use. Reject materials that contain water, hard caking of any separated constituents, nonreversible jell, or materials that are otherwise unsatisfactory. Do not reject sealants that exhibit settlement of constituents in a soft mass that can be readily and uniformly remixed in the field with simple tools.

3.5 INSTALLATION OF SEALANT

3.5.1 Time of Application

After approval of the test section, seal joints immediately following final cleaning and placing of bond breakers. Commence sealing joints when walls are dust free and dry, and when weather conditions meet sealant manufacturer's instructions. If the above conditions cannot be met, or when rain interrupts sealing operations, reclean and permit the joints to dry prior to installing the sealant.

3.5.2 Sealing Joints

Do not install joint sealant until joints to be sealed have been inspected and approved. Install bond breaker just prior to pouring sealant. Fill the joints with sealant from bottom up until joints are uniformly filled solid from bottom to top using the specified equipment for the type of sealant required. Fill joints to 1/4 in plus or minus 1/16 in below top of pavement, and without formation of voids or entrapped air. Do not permit gravity methods or pouring pots to be used to install the sealant material. Except as otherwise permitted, tool the sealant immediately after application to provide firm contact with the joint walls and to form the indicated sealant profile below the pavement surface. Remove excess sealant that has been inadvertently spilled on the pavement surface. Do not permit traffic over newly sealed pavement until authorized. When a primer is recommended by the manufacturer, apply it evenly to the joint faces in accordance with the manufacturer's recommendations. Check sealed joints frequently to ensure that newly installed sealant is cured to a tack-free condition within the specified time. Protect new sealant from rain during curing period.

3.6 INSPECTION/FIELD QUALITY CONTROL

3.6.1 Joint Cleaning

Inspect joints during the cleaning process to correct improper equipment

and cleaning techniques that damage the concrete pavement in any manner. Approve cleaned joints prior to installation of the separating or back-up material and joint sealant.

3.6.2 Sampling Sealant

Obtain a one gal sample of each type of sealant on the project from material used for each 10,000 linear ft or less of joints sealed. Store samples according to sealant manufacturer's instructions. Retain samples until final acceptance of the work.

3.6.3 Sealant Application Equipment

Inspect the application equipment to ensure conformance to temperature requirements, proper proportioning and mixing (if two-component sealant) and proper installation. Suspend operations if there is evidences of bubbling, improper installation, or failure to cure or set until causes of the deficiencies are determined and corrected.

3.6.4 Joint Sealant

Inspect the joint sealant for proper rate of cure and set, bonding to the joint walls, cohesive separation within the sealant, reversion to liquid, entrapped air and voids. Remove sealants exhibiting these deficiencies prior to the final acceptance of the project from the joint, wasted, and replace at no additional cost to the Government. Obtain approval for each joint seal installation.

3.7 ACCEPTANCE

Reject sealer that fails to cure properly, or fails to bond to joint walls, or reverts to the uncured state, or fails in cohesion, or shows excessive air voids, blisters, surface defects, swelling, or other deficiencies, or is not properly recessed within indicated tolerances. Remove rejected sealer and reclean and reseal joints. Perform removal and reseal work promptly by and at the expense of the Contractor.

3.8 CLEAN-UP

Upon completion of the project, remove unused materials from the site and leave the pavement in a clean condition.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 32 - EXTERIOR IMPROVEMENTS

SECTION 32 13 13.06

PORTLAND CEMENT CONCRETE PAVEMENT FOR ROADS AND SITE FACILITIES

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 DESIGN
- 1.3 RELATED SECTIONS
- 1.4 SUBMITTALS
- 1.5 QUALITY CONTROL
 - 1.5.1 NRMCA Certificate of Conformance
 - 1.5.2 Qualifications
 - 1.5.2.1 Laboratory Accreditation
 - 1.5.2.2 Field Technicians
 - 1.5.3 Batch Tickets
- 1.6 DELIVERY, STORAGE, AND HANDLING
- 1.7 ACCEPTANCE
 - 1.7.1 Tolerances
 - 1.7.2 Test Section

PART 2 PRODUCTS

- 2.1 MATERIALS
 - 2.1.1 Cementitious Materials
 - 2.1.1.1 Portland Cement
 - 2.1.1.2 Fly Ash and Pozzolan
 - 2.1.1.3 Slag
 - 2.1.1.4 Supplementary Cementitious Materials (SCM) Content
 - 2.1.2 Water
 - 2.1.3 Aggregate
 - 2.1.3.1 Durability
 - 2.1.3.2 Alkali Reactivity Test
 - 2.1.3.3 Fine Aggregates
 - 2.1.3.4 Coarse Aggregates
 - 2.1.4 Chemical Admixtures
 - 2.1.4.1 Water Reducing Admixtures
 - 2.1.4.2 Air Entraining Admixture
 - 2.1.5 Reinforcement
 - 2.1.5.1 Dowel Bars
 - 2.1.5.2 Tie Bars
 - 2.1.5.3 Reinforcement
 - 2.1.6 Curing Materials
 - 2.1.6.1 White-Burlap-Polyethylene Sheet
 - 2.1.6.2 Liquid Membrane-Forming Compound
 - 2.1.7 Joint Fillers and Sealants
 - 2.1.8 Epoxy Resin
 - 2.1.9 Joint Materials
 - 2.1.9.1 Expansion Joint Materials
 - 2.1.9.2 Slip Joint Material

- 2.2 CONCRETE PAVEMENT
 - 2.2.1 Joint, Dowel and Reinforcement Layout Drawings
- 2.3 MIX DESIGN
 - 2.3.1 Specified Concrete Properties
 - 2.3.1.1 Flexural Strength
 - 2.3.1.2 Air Entrainment
 - 2.3.1.3 Slump
 - 2.3.1.4 Water/Cementitious Materials Ratio
 - 2.3.2 Mix Design Report
 - 2.3.3 Mix Verification
- 2.4 EQUIPMENT
 - 2.4.1 Batching and Mixing
 - 2.4.2 Transporting Equipment
 - 2.4.3 Delivery Equipment
 - 2.4.4 Paver-Finisher
 - 2.4.4.1 Paver-Finisher with Fixed Forms
 - 2.4.4.2 Slipform Paver-Finisher
 - 2.4.4.3 Other Types of Finishing Equipment
 - 2.4.4.4 Work Bridge
 - 2.4.5 Texturing Equipment
 - 2.4.5.1 Fabric Drag
 - 2.4.6 Curing Equipment
 - 2.4.7 Sawing Equipment
 - 2.4.8 Straightedge

PART 3 EXECUTION

- 3.1 PREPARATION FOR PAVING
 - 3.1.1 Weather Limitations
 - 3.1.1.1 Inclement Weather
 - 3.1.1.2 Hot Weather
 - 3.1.1.3 Prevention of Plastic Shrinkage Cracking
 - 3.1.1.4 Cold Weather
 - 3.1.2 Conditioning of Underlying Material
 - 3.1.3 Forms
 - 3.1.4 Reinforcement
 - 3.1.4.1 Dowel Bars
 - 3.1.4.2 Tie Bars
 - 3.1.4.3 Setting Slab Reinforcement
- 3.2 MEASURING, MIXING, CONVEYING, AND PLACING CONCRETE
 - 3.2.1 Measuring
 - 3.2.2 Mixing
 - 3.2.3 Conveying
 - 3.2.4 Placing
- 3.3 PAVING
 - 3.3.1 Paving Plan
 - 3.3.2 Required Results
 - 3.3.3 Operation
 - 3.3.4 Consolidation
 - 3.3.5 Fixed Form Paving
 - 3.3.6 Slipform Paving
- 3.4 JOINTS
 - 3.4.1 General Requirements for Joints
 - 3.4.2 Longitudinal Construction Joints
 - 3.4.3 Transverse Construction Joints
 - 3.4.4 Expansion Joints
 - 3.4.5 Contraction Joints
 - 3.4.6 Thickened Edge Joints
 - 3.4.7 Dowels Installed In Hardened Concrete

- 3.5 FINISHING CONCRETE
 - 3.5.1 Machine Finishing
 - 3.5.1.1 Equipment Operation
 - 3.5.1.2 Joint Finish
 - 3.5.1.3 Hand Finishing
 - 3.5.2 Texturing
 - 3.5.2.1 Burlap Drag Finish
 - 3.5.3 Edging
- 3.6 CURING AND PROTECTION
 - 3.6.1 White-Burlap-Polyethylene Sheet
 - 3.6.2 Liquid Membrane-Forming Compound Curing
 - 3.6.3 Protection of Treated Surfaces
- 3.7 REPAIR, REMOVAL AND REPLACEMENT OF NEWLY CONSTRUCTED SLABS
 - 3.7.1 General Criteria
 - 3.7.2 Slabs with Cracks
 - 3.7.3 Removal and Replacement of Full Slabs
 - 3.7.4 Repairing Spalls Along Joints
 - 3.7.5 Repair of Weak Surfaces
 - 3.7.6 Repair of Pilot Lane Vertical Faces
- 3.8 FIELD QUALITY CONTROL
 - 3.8.1 Sampling
 - 3.8.2 Consistency Tests
 - 3.8.3 Flexural Strength Tests
 - 3.8.4 Air Content Tests
 - 3.8.5 Surface Testing
 - 3.8.5.1 Straightedge Testing Method
 - 3.8.5.2 Profilograph Testing Method
 - 3.8.5.3 "Bumps" (Must Grind Areas)
 - 3.8.5.4 Diamond Grinding
 - 3.8.6 Plan Grade Testing and Conformance
 - 3.8.7 Edge Slump
 - 3.8.8 Test for Pavement Thickness
 - 3.8.9 Reinforcement
 - 3.8.10 Dowels

-- End of Section Table of Contents --

SECTION 32 13 13.06

PORTLAND CEMENT CONCRETE PAVEMENT FOR ROADS AND SITE FACILITIES

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN CONCRETE INSTITUTE (ACI)

ACI 211.1	(1991; R 2009) Standard Practice for Selecting Proportions for Normal, Heavyweight and Mass Concrete
ACI 305R	(2010) Guide to Hot Weather Concreting
ACI 306R	(2016) Guide to Cold Weather Concreting
ACI 330R	(2008; E 2016) Guide for the Design and Construction of Concrete Parking Lots
ACI 325.12R	(2002; R 2013) Guide for Design of Jointed Concrete Pavements for Streets and Local Roads

ASTM INTERNATIONAL (ASTM)

ASTM A184/A184M	(2019) Standard Specification for Welded Deformed Steel Bar Mats for Concrete Reinforcement
ASTM A615/A615M	(2020) Standard Specification for Deformed and Plain Carbon-Steel Bars for Concrete Reinforcement
ASTM A966/A966M	(2015; R 2020) Standard Test Method for Magnetic Particle Examination of Steel Forgings Using Alternating Current
ASTM C31/C31M	(2019a) Standard Practice for Making and Curing Concrete Test Specimens in the Field
ASTM C33/C33M	(2018) Standard Specification for Concrete Aggregates
ASTM C42/C42M	(2020) Standard Test Method for Obtaining and Testing Drilled Cores and Sawed Beams of Concrete
ASTM C78/C78M	(2018) Standard Test Method for Flexural Strength of Concrete (Using Simple Beam with Third-Point Loading)

ASTM C88	(2018) Standard Test Method for Soundness of Aggregates by Use of Sodium Sulfate or Magnesium Sulfate
ASTM C94/C94M	(2020) Standard Specification for Ready-Mixed Concrete
ASTM C143/C143M	(2015) Standard Test Method for Slump of Hydraulic-Cement Concrete
ASTM C150/C150M	(2020) Standard Specification for Portland Cement
ASTM C171	(2016) Standard Specification for Sheet Materials for Curing Concrete
ASTM C172/C172M	(2017) Standard Practice for Sampling Freshly Mixed Concrete
ASTM C231/C231M	(2017a) Standard Test Method for Air Content of Freshly Mixed Concrete by the Pressure Method
ASTM C260/C260M	(2010a; R 2016) Standard Specification for Air-Entraining Admixtures for Concrete
ASTM C309	(2011) Standard Specification for Liquid Membrane-Forming Compounds for Curing Concrete
ASTM C494/C494M	(2019) Standard Specification for Chemical Admixtures for Concrete
ASTM C618	(2019) Standard Specification for Coal Fly Ash and Raw or Calcined Natural Pozzolan for Use in Concrete
ASTM C881/C881M	(2015) Standard Specification for Epoxy-Resin-Base Bonding Systems for Concrete
ASTM C989/C989M	(2018a) Standard Specification for Slag Cement for Use in Concrete and Mortars
ASTM C1017/C1017M	(2013; E 2015) Standard Specification for Chemical Admixtures for Use in Producing Flowing Concrete
ASTM C1077	(2017) Standard Practice for Agencies Testing Concrete and Concrete Aggregates for Use in Construction and Criteria for Testing Agency Evaluation
ASTM C1260	(2014) Standard Test Method for Potential Alkali Reactivity of Aggregates (Mortar-Bar Method)
ASTM C1542/C1542M	(2019) Standard Test Method for Measuring

Length of Concrete Cores

ASTM C1567	(2013) Standard Test Method for Potential Alkali-Silica Reactivity of Combinations of Cementitious Materials and Aggregate (Accelerated Mortar-Bar Method)
ASTM C1602/C1602M	(2018) Standard Specification for Mixing Water Used in Production of Hydraulic Cement Concrete
ASTM D1751	(2004; E 2013; R 2013) Standard Specification for Preformed Expansion Joint Filler for Concrete Paving and Structural Construction (Nonextruding and Resilient Bituminous Types)
ASTM D1752	(2018) Standard Specification for Preformed Sponge Rubber, Cork and Recycled PVC Expansion Joint Fillers for Concrete Paving and Structural Construction
ASTM D2995	(1999; R 2009) Determining Application Rate of Bituminous Distributors
ASTM E1274	(2018) Standard Test Method for Measuring Pavement Roughness Using a Profilograph

NATIONAL READY MIXED CONCRETE ASSOCIATION (NRMCA)

NRMCA QC 3	(2015) Quality Control Manual: Section 3, Plant Certifications Checklist: Certification of Ready Mixed Concrete Production Facilities
------------	---

U.S. DEPARTMENT OF DEFENSE (DOD)

UFC 3-250-01	(2016) Pavement Design For Roads And Parking Areas
--------------	--

1.2 DESIGN

This materials and construction specification is intended to be used on projects where the design was completed using UFC 3-250-01 Pavement Design for Roads, Streets, Walks, and Open Storage Areas, ACI 330R, Guide for the Design and Construction of Concrete Parking Lots or ACI 325.12R, Guide for Design of Jointed Concrete Pavements for Streets and Local Roads, or equivalent.

1.3 RELATED SECTIONS

Portland cement concrete pavement must use Section 32 11 23 AGGREGATE BASE COURSE and Section 32 11 23 AGGREGATE SUBBASE COURSE, in addition to this section.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When

used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance with Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Joint, Dowel and Reinforcement Layout Drawings; G

SD-03 Product Data

Curing Materials

Reinforcement

Epoxy Resin

Dowel Bars

Expansion Joint Filler

Cementitious Materials

SD-04 Samples

Test Section; G

SD-05 Design Data

Mix Design Report; G

SD-06 Test Reports

Concrete Slump Tests; G

Concrete Uniformity; G

Flexural Strength; G

Air Content; G

Surface Smoothness Report; G

Repair Recommendations Plan; G

SD-07 Certificates

Batch Tickets

NRMCA Certificate Of Conformance

SD-08 Manufacturer's Instructions

Diamond Grinding Plan

1.5 QUALITY CONTROL

1.5.1 NRMCA Certificate of Conformance

Provide a batching and mixing plant consisting of a stationary-type central mix plant, including permanent installations and portable or relocatable plants installed on stable foundations. Provide a plant designed and operated to produce concrete within the specified tolerances, with a minimum capacity of 250 cubic yards per hour. Submit NRMCA Certificate of Conformance that conforms to the requirements of NRMCA QC 3 including provisions addressing:

1. Material Storage and Handling
2. Batching Equipment
3. Central Mixer
4. Ticketing System
5. Delivery System

1.5.2 Qualifications

1.5.2.1 Laboratory Accreditation

Perform sampling and testing using an approved commercial testing laboratory or on-site facilities that are accredited in accordance with ASTM C1077 and that meets all applicable requirements in SECTION 01 45 00 QUALITY CONTROL. Do not start work requiring testing until the facilities have been inspected and approved. The Government will inspect all laboratories requiring validation for equipment and test procedures prior to the start of any concreting operations for conformance to ASTM C1077. Schedule and provide payment for laboratory inspections. Additional payment or a time extension due to failure to acquire the required laboratory validation is not allowed. Maintain this certification for the duration of the project.

1.5.2.2 Field Technicians

Provide field technicians meeting one of the following criteria:

- a. Have at least one National Ready Mixed Concrete Association (NRMCA) certified concrete craftsman and at least one American Concrete Institute (ACI) Flatwork Finisher Certified craftsman on site, overseeing each placement crew during all concrete placement.
- b. Have no less than three NRMCA certified concrete installers and at least two American Concrete Institute (ACI) Flatwork Finisher Certified installers on site working as members of each placement crew during all concrete placement.

1.5.3 Batch Tickets

Submit batch tickets for each load of ready-mixed concrete in accordance with ASTM C94/C94M.

1.6 DELIVERY, STORAGE, AND HANDLING

Deliver concrete paving in accordance with ASTM C94/C94M.

1.7 ACCEPTANCE

1.7.1 Tolerances

Acceptance of Portland cement concrete pavement is based on compliance with the tolerances presented in Table 1. Remove and replace concrete pavement represented by the failing tests or submit repair plan for approval.

Table 1	
Measurement	Tolerance
PLASTIC CONCRETE	
Slump	plus 0, minus 1.5 inches
Air Content	plus/minus 1.5 percent
Flexural Strength	No individual specimen less than 100 psi below specified strength.
HARDENED CONCRETE	
Grade	plus/minus 0.05 feet from plan
Smoothness	No abrupt change exceeding 1/8 inch
Straightedge	Not more than 1/8 in for roads. Not more than 1/4 in for open storage areas.
Profilograph	Not more than 9 inches/mile
Thickness	minus 3/4 inch for pavement equal to/greater than 8 inches thick, minus 1/2 inch for pavement less than 8 inches thick.
Edge Slump	85 percent less than 1/4 inch and 100 percent less than 3/8 inch.

1.7.2 Test Section

Construct a minimum 400 square feet test section to demonstrate typical joints, surface finish, texture, color, thickness, and standard of workmanship using the mixture proportions, materials, and equipment as proposed for the project. Location of test section shall be approved by the Contracting Officer. Test in accordance with requirements in FIELD QUALITY CONTROL.

When a test section does not meet one or more of the tolerances in Table 1, remove and reconstruct the test section. If the test section is acceptable, it may be incorporated into the project.

PART 2 PRODUCTS

2.1 MATERIALS

2.1.1 Cementitious Materials

Cementitious materials in concrete mix must be 20 to 50 percent non-portland cement pozzolanic materials or slag by weight.

2.1.1.1 Portland Cement

Conforming to ASTM C150/C150M, Type I or II or V low alkali.

2.1.1.2 Fly Ash and Pozzolan

Conforming to ASTM C618, Type F, with a loss on ignition not exceeding 6 percent. Include test results in accordance with ASTM C618.

2.1.1.3 Slag

Conforming to ASTM C989/C989M, Slag Cement (formerly Ground Granulated Blast Furnace Slag) Grade 100 or 120. Include test results in accordance with ASTM C989/C989M.

2.1.1.4 Supplementary Cementitious Materials (SCM) Content

Include one of the SCMs listed in Table 2 within the range specified therein, whether or not the aggregates are found to be reactive in accordance with the paragraph Alkali Reactivity Test.

TABLE 2 SUPPLEMENTARY CEMENTITIOUS MATERIALS CONTENT		
Supplementary Cementitious Material	Minimum Content (percent)	Maximum Content (percent)
Class F Fly Ash		
SiO ₂ + Al ₂ O ₃ + Fe ₂ O ₃ greater than 70 percent	25	35
SiO ₂ + Al ₂ O ₃ + Fe ₂ O ₃ greater than 80 percent	20	35
SiO ₂ + Al ₂ O ₃ + Fe ₂ O ₃ greater than 90 percent	15	35
GGBF Slag	40	50

2.1.2 Water

Water conforming to ASTM C1602/C1602M.

2.1.3 Aggregate

2.1.3.1 Durability

Evaluate and test all fine and coarse aggregates to be used in all concrete for durability in accordance with ASTM C88. Provide fine and coarse aggregates with a maximum of 18 percent loss when subjected to 5 cycles using Magnesium Sulfate or a maximum of 12 percent loss when subjected to 5 cycles of Sodium Sulfate.

2.1.3.2 Alkali Reactivity Test

Evaluate and test fine and coarse aggregates to be used in all concrete for alkali-aggregate reactivity. Test all size groups and sources proposed for use.

- a. Evaluate the fine and coarse aggregates separately, using ASTM C1260. Reject individual aggregates with test results that indicate an expansion of greater than 0.08 percent after 28 days of immersion in 1N NaOH solution, or perform additional testing as follows: utilize the proposed low alkali portland cement or SCM in combination with each individual aggregate. Test in accordance with ASTM C1567. Determine the quantity that meets all the requirements of these specifications and that lowers the expansion equal to or less than 0.08 percent after 28 days of immersion in a 1N NaOH solution. Base the mixture proportioning on the highest percentage of SCM required to mitigate ASR-reactivity.
- b. If any of the above options does not lower the expansion to less than 0.08 percent after 28 days of immersion in a 1N NaOH solution, reject the aggregate(s) and submit new aggregate sources for retesting. Submit the results of testing for evaluation and acceptance.

2.1.3.3 Fine Aggregates

Conforming to the quality and gradation of ASTM C33/C33M.

2.1.3.4 Coarse Aggregates

Coarse aggregate consisting of crushed or uncrushed gravel, crushed stone, or a combination thereof. Provide aggregates, as delivered to the mixers, consisting of clean, hard, uncoated particles. Wash coarse aggregate sufficient to remove dust and other coatings. Provide fine aggregate consisting of natural sand, manufactured sand, or a combination of the two, and composed of clean, hard, durable particles. Provide both coarse and fine aggregates meeting the requirements of ASTM C33/C33M.

- a. Gradation: Provide coarse aggregate with a nominal maximum size of 1.5 inches. Grade and provide the individual aggregates in two or more size groups meeting the individual grading requirements of ASTM C33/C33M, Size No. 4 (1.5 to 0.75 inch) and Size No. 67 (0.75 inch to No. 4).
- b. Quality: Conforming to ASTM C33/C33M, Class 4M.

2.1.4 Chemical Admixtures

2.1.4.1 Water Reducing Admixtures

Provide admixture conforming to ASTM C494/C494M: Type A, water reducing; Type B, retarding; Type D, water-reducing and retarding; and Type E, water-reducing and accelerating admixture. Do not use calcium chloride admixtures. ASTM C494/C494M Type S specific performance admixtures and ASTM C1017/C1017M flowable admixtures are not allowed.

2.1.4.2 Air Entraining Admixture

Conforming to ASTM C260/C260M: Air-entraining.

2.1.5 Reinforcement

2.1.5.1 Dowel Bars

Dowel bars conforming to ASTM A615/A615M, Grade 60 for plain billet-steel bars of the size and length indicated. Remove all burrs and projections from the bars.

2.1.5.2 Tie Bars

Billet or axle steel deformed bars conforming to ASTM A615/A615M or ASTM A966/A966M Grade 60.

2.1.5.3 Reinforcement

Deformed steel bar mats conforming to ASTM A184/A184M. Bar reinforcement conforming to ASTM A615/A615M, Grade 60.

2.1.6 Curing Materials

Provide curing materials consisting of:

2.1.6.1 White-Burlap-Polyethylene Sheet

Conforming to ASTM C171, 0.004 inch thick white opaque polyethylene bonded to 10 oz/linear yard (40 inch) wide burlap.

2.1.6.2 Liquid Membrane-Forming Compound

Conforming to ASTM C309, white pigmented, Type 2, Class B, free of paraffin or petroleum.

2.1.7 Joint Fillers and Sealants

Provide as specified in Section 32 01 19.61 SEALING OF JOINTS IN RIGID PAVEMENT.

2.1.8 Epoxy Resin

Provide epoxy-resin materials that consist of two-component materials conforming to the requirements of ASTM C881/C881M, Class as appropriate for each application temperature to be encountered, except that in addition, the materials meet the following requirements:

- a. Type IV, Grade 3, for use for embedding dowels and anchor bolts.

- b. Type III, Grade as approved, for use as patching materials for complete filling of spalls and other voids and for use in preparing epoxy resin mortar.
- c. Type IV, Grade 1, for use for injecting cracks.
- d. Type V, Grade as approved, for bonding freshly mixed portland cement concrete or mortar or freshly mixed epoxy resin concrete or mortar to hardened concrete.

2.1.9 Joint Materials

2.1.9.1 Expansion Joint Materials

Provide preformed expansion joint filler material conforming to ASTM D1751 or ASTM D1752. Provide expansion joint filler that is 3/4 inch thick, unless otherwise indicated, and provided in a single full depth piece.

2.1.9.2 Slip Joint Material

Provide slip joint material that is 1/4 inch thick expansion joint filler, unless otherwise indicated, conforming to paragraph EXPANSION JOINT MATERIAL.

2.2 CONCRETE PAVEMENT

2.2.1 Joint, Dowel and Reinforcement Layout Drawings

Submit joint, dowel, and reinforcement layout drawings to the Contracting Officer for approval. No work must be allowed to start until the drawings are approved. The drawings must indicate and describe in detail the proposed jointing and doweling plan for contraction joints, expansion joints, and construction joints in accordance with UFC 3-250-01 Chapter 16, and the proposed reinforcing plan for odd-shaped slabs in accordance with UFC 3-250-01 Chapter 14, and the following:

- a. Indicate locations of contraction joints, construction joints, and expansion joints. Spacing between contraction joints must not exceed 15 feet.
- b. The larger dimension of a panel must not be greater than 125% of the smaller dimension.
- c. The minimum angle between two intersecting joints must be 80 degrees, unless noted otherwise or approved by the Contracting Officer.
- d. Joints must intersect pavement-free edges at a 90 degree angle the pavement edge and must extend straight for a minimum of 1.5 feet from the pavement edge, where possible.
- e. Align joints of adjacent panels.
- f. Align joints in attached curbs with joints in pavement when possible.
- g. Ensure joint depth, widths, and dimensions are specified.
- h. Minimum contraction joint depth must be 1/4 of the pavement thickness. The minimum joint width must be 1/8 inch.

- i. Use expansion joints only where pavement abuts buildings, foundations, manholes, and other fixed objects.

2.3 MIX DESIGN

Proportion concrete mix in accordance with ACI 211.1 except as modified herein.

2.3.1 Specified Concrete Properties

2.3.1.1 Flexural Strength

Provide concrete with a minimum flexural strength of 650 psi at 28 days of age.

2.3.1.2 Air Entrainment

Provide an entrained air content of 5.5 percent.

2.3.1.3 Slump

For fixed form and hand placement, provide a maximum slump of 3 inches. For slipformed pavement, at the start of the project, select a maximum allowable slump which will produce in-place pavement meeting the specified tolerances for control of edge slump. The selected slump is applicable to both pilot and fill-in lanes.

2.3.1.4 Water/Cementitious Materials Ratio

Maximum allowable water-cementitious material ratio is 0.40. The water-cementitious material ratio is based on absolute volume equivalency, where the ratio is determined using the weight of cement for a cement only mix, or using the total volume of cement plus pozzolan converted to an equivalent weight of cement by the absolute volume equivalency method described in ACI 211.1.

2.3.2 Mix Design Report

Perform trial design batches, mixture proportioning studies, testing, and include test results demonstrating that the proposed mixture proportions produce concrete of the qualities indicated. An existing mix design may be submitted if developed within the previous 12 months. Submit test results in a mix design report to include:

- a. Coarse and fine aggregate gradations and plots.
- b. Coarse and fine aggregate quality test results, include deleterious materials and ASR testing.
- c. Mill certificates for cement and supplemental cementitious materials.
- d. Certified test results for all proposed admixtures.
- e. Specified flexural strength, slump, and air content.
- f. Recommended proportions and volumes for proposed mixture and each of three trial water-cementitious materials ratios.

- g. Individual beam breaks.
- h. Flexural strength summaries and plots.
- i. Historical record of test results, documenting production standard deviation (if available).
- j. Narrative discussing methodology on how the mix design was developed.

2.3.3 Mix Verification

Mix verification tests may be performed by the Government. Provide quantities of cementitious materials, aggregates and admixtures as requested.

2.4 EQUIPMENT

2.4.1 Batching and Mixing

Provide stationary mixers or truck mixers as applicable. Provide a batch plant conforming to ASTM C94/C94M and as specified. Do not weigh water or measure cumulatively with another ingredient. Batch all concrete materials in accordance with ASTM C94/C94M requirements. Verify batching, mixers, mixing time, permitted reduction of mixing time, and concrete uniformity in accordance with the requirements of ASTM C94/C94M, and document in the initial weekly QC Report. Do not use truck mixers for mixing slipformed concrete. Provide only truck mixers designed for mixing or transporting paving concrete with extra large blading and rear opening specifically for low-slump paving concrete and conforming to the requirements of ASTM C94/C94M.

2.4.2 Transporting Equipment

Provide transporting equipment in conformance with ASTM C94/C94M and as specified herein. Transport concrete to the paving site in rear-dump trucks, in truck mixers designed with extra large blading and rear opening specifically for low slump concrete, or in agitators. Do not permit bottom-dump trucks for delivery of concrete.

2.4.3 Delivery Equipment

When concrete transport equipment cannot operate on the paving lane, provide side-delivery transport equipment consisting of self-propelled moving conveyors to deliver concrete from the transport equipment and discharge it in front of the paver. Do not permit front-end loaders, dozers, or similar equipment to distribute the concrete.

2.4.4 Paver-Finisher

Provide a heavy-duty, self-propelled paver-finisher machine designed specifically for paving and finishing high quality pavement and capable of spreading, consolidating, and shaping the plastic concrete to the desired cross section in one pass. Equip the paver-finisher with a full width "knock-down" auger, capable of operating in both directions, which will evenly spread the fresh concrete in front of the screed or extrusion plate. Gang-mount immersion vibrators at the front of the paver on a frame equipped with suitable controls so that all vibrators can be operated at any desired depth within the slab or completely withdrawn from the concrete. Automatically control the vibrators so they will be

immediately stopped as forward motion of the paver ceases. Space the immersion vibrators across the paving lane as necessary to properly consolidate the concrete, but limit the clear distance between vibrators not to exceed 30 inches, and the outside vibrators not to exceed 12 inches from the edge of the lane. For pavements less than 10 inches thick, operate vibrators at mid-depth parallel with or at a slight angle to the underlying base or subbase. Vibrators may be pneumatic, gas driven, or electric, and operated at frequencies within the concrete between 6,000 and 7,000 vibrations per minute, with an amplitude of vibration such that noticeable vibrations occur at 1.5 foot radius when the vibrator is inserted in the concrete to the depth specified. Equip the paver-finisher with a transversely oscillating screed or an extrusion plate to shape, compact, and smooth the surface.

2.4.4.1 Paver-Finisher with Fixed Forms

Equip the paver-finisher with wheels designed to ride the forms, keep it aligned with the forms, and to prevent deformation of the forms.

2.4.4.2 Slipform Paver-Finisher

Provide a track-mounted slipform paver-finisher with automatic controls and padded tracks. Electronically reference horizontal alignment to a taut wire guideline. Electronically reference vertical alignment on both sides of the paver to a taut wire guideline, to an approved laser control system, or to a ski operating on a completed lane. Do not control from a slope-adjustment control or from the underlying material.

2.4.4.3 Other Types of Finishing Equipment

Bridge deck finishers are permitted for pavements 10 inches or less in thickness. Heavy duty vibratory truss screeds may be approved for use if successfully demonstrated on the test section to consolidate the slab full depth and without segregation. Clary screeds, rotating tube floats, or laser screeds will not be allowed on the project. Provide hand floats that are not less than 12 feet long and 6 inches wide and stiffened to prevent flexing and warping.

2.4.4.4 Work Bridge

Provide a self-propelled work bridge capable of spanning the paving lane and supporting the workmen without excessive deflection.

2.4.5 Texturing Equipment

Provide texturing equipment as specified below.

2.4.5.1 Fabric Drag

Clean, reasonably new burlap measuring from 3 to 10 feet long, 2 feet wider than the width of the pavement, and securely attached to a separate wheel mounted frame spanning the paving lane or to one of the other similar pieces of equipment. Select dimension of burlap drag so that at least 3 feet of the material is in contact with the pavement.

2.4.6 Curing Equipment

Provide equipment for applying membrane-forming curing compound mounted on a self-propelled frame that spans the paving lane. Constantly agitate the

curing compound reservoir mechanically (not air) during operation and provide a means for completely draining the reservoir. Provide a spraying system that consists of a mechanically powered pump which maintains constant pressure during operation, an operable pressure gauge, and either a series of spray nozzles evenly spaced across the lane to provide uniformly overlapping coverage or a single spray nozzle which is mounted on a carriage which automatically traverses the lane width at a speed correlated with the forward movement of the overall frame. Protect all spray nozzles with wind screens. Calibrate the spraying system in accordance with ASTM D2995, Method A, for the rate of application required in subpart CURING AND PROTECTION. Provide hand-operated sprayers powered by compressed air supplied by a mechanical air compressor. Immediately replace curing equipment if it fails to apply an even coating of compound at the specified rate.

2.4.7 Sawing Equipment

Provide equipment for sawing joints and for other similar sawing of concrete consisting of standard diamond-type concrete saws mounted on a wheeled chassis which can be easily guided to follow the required alignment. Provide diamond tipped blades. If demonstrated to operate properly, abrasive blades may be used. Provide spares as required to maintain the required sawing rate. Early-entry saws may be used, subject to demonstration and approval. No change to the initial sawcut depth is permitted.

2.4.8 Straightedge

Furnish one 12 foot straightedge constructed of aluminum or magnesium alloy, having blades of box or box-girder cross section with flat bottom, adequately reinforced to insure rigidity and accuracy. Provide handles for operation on the pavement.

PART 3 EXECUTION

3.1 PREPARATION FOR PAVING

3.1.1 Weather Limitations

When windy conditions during paving appear probable, have equipment and material at the paving site to provide windbreaks, shading, fogging, or other action to prevent plastic shrinkage cracking or other damaging drying of the concrete.

3.1.1.1 Inclement Weather

Do not commence placing operations when heavy rain or other damaging weather conditions appear imminent. At all times when placing concrete, maintain on-site sufficient waterproof cover and means to rapidly place it over all unhardened concrete or concrete that might be damaged by rain. Suspend placement of concrete whenever rain, high winds, or other damaging weather commences to damage the surface or texture of the placed unhardened concrete, washes cement out of the concrete, or changes the water content of the surface concrete. Immediately cover and protect all unhardened concrete from the rain or other damaging weather. Completely remove and replace any slab damaged by rain or other weather full depth, by full slab width, to the nearest original joint.

3.1.1.2 Hot Weather

Maintain required concrete temperature in accordance with ACI 305R to prevent evaporation rate from exceeding 0.2 pound of water per square foot of exposed concrete per hour. Cool ingredients before mixing, place concrete during cooler night time hours, or use other suitable means to control concrete temperature and prevent rapid drying of newly placed concrete. Water is not allowed to be added after the initial introduction of mixing water except, when on arrival at the job site, the slump is less than specified and the water-cement ratio is less than that given as a maximum in the approved mixture. Additional water may be added to bring the slump within the specified range provided the approved water-cement ratio is not exceeded. Inject water into the head of the mixer (end opposite the discharge opening) drum under pressure, and turn the drum or blades a minimum of 30 additional revolutions at mixing speed. The addition of water to the batch at any later time is not allowed. After placement, use fog spray, apply monomolecular film, or use other suitable means to reduce the evaporation rate. Start curing when surface of fresh concrete is sufficiently hard to permit curing without damage. Cool underlying material by sprinkling lightly with water before placing concrete. Follow practices found in ACI 305R.

3.1.1.3 Prevention of Plastic Shrinkage Cracking

During weather with low humidity, and particularly with high temperature and appreciable wind, develop and institute measures to prevent plastic shrinkage cracks from developing. If plastic shrinkage cracking occurs, halt further placement of concrete until protective measures are in place to prevent further cracking. Periods of high potential for plastic shrinkage cracking can be anticipated by use of ACI 305R. In addition to the protective measures specified in the previous paragraph, the concrete placement may be further protected by erecting shades and windbreaks and by applying fog sprays of water, the addition of monomolecular films, or wet covering. Apply monomolecular films after finishing is complete, do not use in the finishing process. Immediately commence curing procedures when such water treatment is stopped.

3.1.1.4 Cold Weather

Do not place concrete when ambient temperature is below 40 degrees F or when concrete is likely to be subjected to freezing temperatures within 24 hours. When authorized, when concrete is likely to be subjected to freezing within 24 hours after placing, heat concrete materials so that temperature of concrete when deposited is between 65 and 80 degrees F. Methods of heating materials are subject to approval. Do not heat mixing water above 165 degrees F. Remove lumps of frozen material and ice from aggregates before placing aggregates in mixer. Follow practices found in ACI 306R.

3.1.2 Conditioning of Underlying Material

Verify the underlying material, upon which concrete is to be placed is clean, damp, and free from debris, waste concrete or cement, frost, ice, and standing or running water. Prior to setting forms or placement of concrete, verify the underlying material is well drained and has been satisfactorily graded by string-line controlled, automated, trimming machine and uniformly compacted in accordance with the applicable Section of these specifications. Test the surface of the underlying material to crown, elevation, and density in advance of setting forms or of concrete

placement using slip-form techniques. Trim high areas to proper elevation. Fill and compact low areas to a condition similar to that of surrounding grade, or fill with concrete monolithically with the pavement. Low areas filled with concrete are not to be cored for thickness to avoid biasing the average thickness used for evaluation and payment adjustment. Rework and compact any underlying material disturbed by construction operations to specified density immediately in front of the paver. If a slipform paver is used, continue the same underlying material under the paving lane beyond the edge of the lane a sufficient distance that is thoroughly compacted and true to grade to provide a suitable trackline for the slipform paver and firm support for the edge of the paving lane.

3.1.3 Forms

Use steel forms, except that wood forms may be used for curves having a radius of 150 feet or less, and for fillets. Forms may be built up with metal or wood, added only to the base, to provide an increase in depth of not more than 25 percent. Provide forms with the base width not less than eight-tenths of the vertical height of the form, except that for forms 8 inches or less in vertical height, provide forms with a base width not less than the vertical height of the form. Provide wood forms adequate in strength and rigidly braced for curves and fillets. Set forms on firm material cut true to grade so that each form section when placed will be firmly in contact with the underlying layer for its entire base. Do not set forms on blocks or on built-up spots of underlying material. Before placing the concrete, coat the contact surfaces of forms with a non-staining mineral oil, non-staining form coating compound, biodegradable form release agent, or two coats of nitro-cellulose lacquer. Check and correct grade elevations and alignment of the forms immediately before placing concrete.

3.1.4 Reinforcement

3.1.4.1 Dowel Bars

Install dowels with horizontal and vertical alignment plus or minus 1 inch. Except as otherwise specified, maintain location of dowels within a skew alignment of 1/4 inch over 1 foot length. Omit Dowels and tie bars when the center of the dowel or tie bar is located within a horizontal distance from an intersecting joint equal to or less than one-fourth of the slab thickness. Maintain dowels in position during concrete placement and curing. Before concrete placement, thoroughly grease the entire length of each dowel secured in a dowel basket or fixed form.

3.1.4.2 Tie Bars

Install bars, accurately aligned horizontally and vertically, and to the tolerances shown on the approved joint layout shop drawings, at indicated locations. For slipform construction, insert bent tie bars by hand or other approved means.

3.1.4.3 Setting Slab Reinforcement

Position reinforcement on suitable chairs prior to concrete placement. At expansion, contraction and construction joints, place the reinforcement as indicated on the approved joint layout shop drawings. Clean reinforcement free of mud, oil, scale or other foreign materials. Place reinforcement accurately and wire securely. Lap splices 12 inches minimum. Maintain

the bar spacing from ends and sides of slabs and joints as indicated.

3.2 MEASURING, MIXING, CONVEYING, AND PLACING CONCRETE

3.2.1 Measuring

Conform to ASTM C94/C94M.

3.2.2 Mixing

Conform to ASTM C94/C94M, except as modified herein. Begin mixing within 30 minutes after cement has been added to aggregates. When the air temperature is greater than 85 degrees F, place concrete within 60 minutes. With approval, a hydration stabilizer admixture meeting the requirements of ASTM C494/C494M Type D, may be used to extend the placement time to 90 minutes. Additional water may be added to bring slump within required limits as specified in ASTM C94/C94M, provided that the specified water-cement ratio is not exceeded.

3.2.3 Conveying

Conform to ASTM C94/C94M.

3.2.4 Placing

Do not exceed a free vertical drop of 5 feet from the point of discharge. Deposit concrete either directly from the transporting equipment or by conveyor on to the pre-wetted subgrade or subbase, unless otherwise specified. Deposit the concrete between the forms to an approximately uniform height. Place concrete continuously at a uniform rate, without damage to the grade and without unscheduled stops except for equipment failure or other emergencies. If an unscheduled stop occurs within 10 feet of a previously placed expansion joint, remove concrete back to joint, repair any damage to grade, install a construction joint and continue placing concrete only after cause of the stop has been corrected.

3.3 PAVING

Construct pavement with paving and finishing equipment utilizing fixed forms or slipforms as approved.

3.3.1 Paving Plan

Submit for approval a paving plan identifying the following items:

- a. A description of the placing and protection methods proposed when concrete is to be placed in or exposed to hot, cold, or rainy weather conditions.
- b. A detailed paving sequence plan and proposed paving pattern showing all planned construction joints.
- c. Plan and equipment proposed to control alignment of formed or sawn joints within the specified tolerances.

3.3.2 Required Results

Operate the paver-finisher to produce a thoroughly consolidated slab throughout, true to line and grade within specified tolerances. Adjust

the paver-finishing operation to produce a surface finish free of irregularities, tears, voids of any kind, and other discontinuities, with only a minimum of paste at the surface. Do not permit multiple passes of the paver-finisher. Produce a finished surface requiring no hand finishing, other than the use of cutting straightedges, except in very infrequent instances. Do not apply water, other than true fog sprays (mist), to the concrete surface during paving and finishing.

3.3.3 Operation

When the paver is operated between or adjacent to previously constructed pavement fill-in lanes, make provisions to prevent damage to the previously constructed pavement, including keeping the existing pavement surface free of debris, and placing rubber mats beneath the paver tracks. Operate transversely oscillating screeds and extrusion plates to overlap the existing pavement the minimum possible, but in no case more than 8 inches.

3.3.4 Consolidation

Immediately after spreading concrete, consolidate full depth with internal type vibrating equipment along the boundaries of all slabs regardless of slab thickness, and interior of all concrete slabs. For pavements less than 10 inches thick, operate vibrators at mid-depth parallel with or at a slight angle to the base course. For thicker pavements, angle vibrators toward the vertical, with vibrator tip preferably about 2 inches above the base course, and top of vibrator a few inches below pavement surface. Automatically control the vibrators or tamping units in front of the paver so that they stop immediately as forward motion ceases. Limit duration of vibration to that necessary to produce consolidation of concrete. Do not permit excessive vibration. Vibrate concrete in small, odd-shaped slabs or in locations inaccessible to the paver mounted vibration equipment with a hand-operated immersion vibrator operated from a bridge spanning the area. Do not operate vibrators at one location for more than 15 seconds. Do not use vibrators to transport or spread the concrete.

3.3.5 Fixed Form Paving

Spread and strike off concrete with with the paver. Shape the concrete to the specified and indicated cross section in one pass, and finish the surface and edges so that only a very minimum amount of hand finishing is required. Use single spud hand vibrators to consolidate the concrete adjacent to fixed forms as required to achieve a void-free formed edge. Do not allow vibrators to contact reinforcement, forms, or the grade during vibration.

3.3.6 Slipform Paving

Shape the concrete to the specified and indicated cross section in one pass, and finish the surface and edges so that only a very minimum amount of hand finishing is required. Do not install dowels by dowel inserters attached to the paver or by any other means of inserting the dowels into the plastic concrete. If a keyway is required, install a 26 gauge thick metal keyway liner as the keyway is extruded. Protect the keyway liner to remain in place and become part of the joint.

3.4 JOINTS

3.4.1 General Requirements for Joints

Construct joints that conform to the locations and details indicated on the approved joint layout shop drawings and are perpendicular to the finished grade of the pavement. Provide joints that are straight and continuous from edge to edge or end to end of the pavement with no abrupt offset and no gradual deviation greater than 1/2 inch. Where any joint fails to meet these tolerances, remove and replace the slabs adjacent to the joint at no additional cost to the Government. Change from the jointing pattern shown on the drawings is not allowed without written approval. Seal joints immediately following curing of the concrete or as soon thereafter as weather conditions permit as specified in Section 32 01 19.61 SEALING OF JOINTS IN RIGID PAVEMENT.

3.4.2 Longitudinal Construction Joints

Install dowels in the longitudinal construction joints, or thicken the edges as indicated. Install dowels as specified above. After the end of the curing period, saw longitudinal construction joints to provide a groove at the top for sealant conforming to the details and dimensions indicated.

3.4.3 Transverse Construction Joints

Install transverse construction joints at the end of each day's placing operations and at any other points within a paving lane when concrete placement is interrupted for 30 minutes or longer. Install the transverse construction joint at a planned transverse joint. Provide transverse construction joints by utilizing headers or by paving through the joint, then full-depth sawcutting the excess concrete. Construct pavement with the paver as close to the header as possible, with the paver run out completely past the header. Provide transverse construction joints at a planned transverse joint constructed as shown or, if not shown otherwise, dowelled in accordance with paragraph DOWELS INSTALLED IN HARDENED CONCRETE.

3.4.4 Expansion Joints

Provide expansion joints where indicated on the approved joint layout shop drawings, and about any structures and features that project through or into the pavement, using joint filler of the type, thickness, and width indicated, and installed to form a complete, uniform separation between the structure and the pavement or between two pavements. Attach the filler to the original concrete placement with adhesive and mechanical fasteners and extend the full slab depth. After placement and curing of the adjacent slab, sawcut the sealant reservoir depth from the filler. Tightly fit adjacent sections of filler together, with the filler extending across the full width of the paving lane or other complete distance in order to prevent entrance of concrete into the expansion space. Finish edges of the concrete at the joint face with an edger with a radius of 1/8 inch.

3.4.5 Contraction Joints

Construct transverse and longitudinal contraction joints by sawing an initial groove in the concrete with a 1/8 inch blade to the indicated depth. During sawing of joints, and again 24 hours later, the CQC team is

required to inspect all exposed lane edges for development of cracks below the saw cut, and immediately report results. If there are more than six consecutive uncracked joints after 48 hours, saw succeeding joints 25 percent deeper than originally indicated at no additional cost to the Government. The time of initial sawing varies depending on existing and anticipated weather conditions and be such as to prevent uncontrolled cracking of the pavement. Commence sawing of the joints as soon as the concrete has hardened sufficiently to permit cutting the concrete without chipping, spalling, or tearing. The sawed faces of joints will be inspected for undercutting or washing of the concrete due to the early sawing, and sawing delayed if undercutting is sufficiently deep to cause structural weakness or excessive roughness in the joint. Continue the sawing operation as required during both day and night regardless of weather conditions. Saw the joints at the required spacing consecutively in the sequence of the concrete placement. Provide adequate lighting for night work. Illumination using vehicle headlights is not permitted. Provide a chalk line or other suitable guide to mark the alignment of the joint. Before sawing a joint, examine the concrete closely for cracks, and do not saw the joint if a crack has occurred near the planned joint location. Discontinue sawing when a crack develops ahead of the saw cut. Immediately after the joint is sawed, thoroughly flush the saw cut and adjacent concrete surface with water and vacuumed until all waste from sawing is removed from the joint and adjacent concrete surface. Respray the surface with curing compound as soon as free water disappears. Take necessary precautions to insure that the concrete is properly protected from damage and cured at sawed joints. Tightly seal the top of the joint opening and the joint groove at exposed edges with cord backer rod before the concrete in the region of the joint is resprayed with curing compound, and be maintained until removed immediately before sawing the joint sealant reservoir. Seal the exposed saw cuts on the faces of pilot lanes with bituminous mastic or masking tape. After expiration of the curing period, widen the upper portion of the groove by sawing with ganged diamond saw blades to the width and depth indicated for the joint sealer. Center the reservoir over the initial sawcut.

3.4.6 Thickened Edge Joints

Construct thickened edge joints as indicated on the approved joint layout shop drawings. Grade the underlying material in the transition area as shown and meet the requirements for smoothness and compaction specified for all other areas of the underlying material.

3.4.7 Dowels Installed In Hardened Concrete

Install by bonding the dowels into holes drilled into the hardened concrete. Before drilling commences, cure the concrete for 7 days or until it has reached a minimum flexural strength of 450 psi. Drill holes into the hardened concrete approximately 1/8 inch greater in diameter than the dowels. Bond the dowels in the drilled holes using epoxy resin injected at the back of the hole before installing the dowel and extruded to the collar during insertion of the dowel so as to completely fill the void around the dowel. Application by buttering the dowel is not permitted. Hold the dowels in alignment at the collar of the hole, after insertion and before the epoxy resin hardens, by means of a suitable metal or plastic collar fitted around the dowel. Check the vertical alignment of the dowels by placing the straightedge on the surface of the pavement over the top of the dowel and measuring the vertical distance between the straightedge and the beginning and ending point of the exposed part of the dowel. Where tie bars are required in longitudinal construction joints of

slipform pavement, install bent tie bars at the paver, in front of the transverse screed or extrusion plate. If tie bars are required, construct a standard keyway and install the bent tie bars into the plastic concrete through a 26 gauge thick metal keyway liner. Do not install tie bars in preformed holes. Protect the keyway liner and maintain in place and become part of the joint. Before placement of the adjoining paving lane, straighten the tie bars, without spalling the concrete around the bar.

3.5 FINISHING CONCRETE

Start finishing operations immediately after placement of concrete. Use finishing machine, except hand finishing may be used in emergencies and for concrete slabs in inaccessible locations or of such shapes or sizes that machine finishing is impracticable. Immediately halt any operations which produce more than 1/8 inch of mortar-rich surface (defined as deficient in plus U.S. No. 4 sieve size aggregate) and modify the equipment, mixture, or procedures. Finish pavement surface on both sides of a joint to the same grade. Finish formed joints from a securely supported transverse bridge. Provide hand finishing equipment for use at all times.

3.5.1 Machine Finishing

Strike off and screed concrete to the required crown or slope and cross-section by a power-driven transverse finishing machine. A transverse rotating tube or pipe is not permitted. Maintain elevation of concrete such that, when consolidated and finished, pavement surface will be adequately consolidated and at the required grade. Equip finishing machine with a screed which is readily and accurately adjustable for changes in pavement crown or slope and compensation for wear and other causes. Do not permit excessive operation over an area, which will result in an excess of mortar and water being brought to the surface.

3.5.1.1 Equipment Operation

Maintain the travel of machine on the forms without lifting, wobbling, or other variation of the machine which tend to affect the precision of concrete finish. Keep the tops of the forms clean by a device attached to the machine. Maintain a uniform ridge of concrete ahead of the front screed for its entire length.

3.5.1.2 Joint Finish

Before concrete is hardened, correct edge slump of pavement, exclusive of edge rounding, in excess of 0.25 inches. Finish concrete surface on each side of construction joints to the same plane, and correct deviations before newly placed concrete has hardened.

3.5.1.3 Hand Finishing

Strike-off and screed surface of concrete to elevations slightly above finish grade so that when concrete is consolidated and finished, the pavement surface is at the indicated elevation. Vibrate entire surface until required compaction and reduction of surface voids is secured with a strike-off template. After initial finishing, further smooth and consolidate concrete by means of hand-operated longitudinal floats.

3.5.2 Texturing

Before the surface sheen has disappeared and before the concrete hardens, provide a texture to the surface of the pavement as described herein. After curing is complete, thoroughly broom all textured surfaces to remove all debris. Finish the concrete in areas of recesses for tie-down anchors, lighting fixtures, and other outlets in the pavement to provide a surface of the same texture as the surrounding area.

3.5.2.1 Burlap Drag Finish

Before concrete becomes non-plastic, finish the surface of the slab by dragging a strip of clean, wet burlap on the surface. Drag the surface so as to produce a finished surface with a fine granular or sandy texture without leaving disfiguring marks. Keep the burlap clean and saturated during use.

3.5.3 Edging

At the time the concrete has attained a degree of hardness suitable for edging, carefully finish slab edges, including edges at formed joints, with an edge having a maximum radius of 1/8 inch. Clean by removing loose fragments and soupy mortar from corners or edges of slabs which have crumbled and areas which lack sufficient mortar for proper finishing. Refill voids solidly with a mixture of suitable proportions and consistency and refinish. Remove unnecessary tool marks and edges. Smooth remaining edges true to line.

3.6 CURING AND PROTECTION

Protect concrete adequately from injurious action by sun, rain, flowing water, frost, mechanical injury, tire marks and oil stains, and do not allow it to dry out from the time it is placed until the expiration of the minimum curing periods specified herein. Do not use membrane-forming compound on surfaces where its appearance would be objectionable, on surfaces to be painted, where coverings are to be bonded to concrete, or on concrete to which other concrete is to be bonded.

3.6.1 White-Burlap-Polyethylene Sheet

Wet entire exposed surface thoroughly with a fine spray of water, saturate burlap but do not have excessive water dripping off the burlap and then cover concrete with White-Burlap-Polyethylene Sheet, burlap side down. Lay sheets directly on concrete surface and overlap 12 inches. Make sheeting not less than 18 inches wider than concrete surface to be cured, and weight down on the edges and over the transverse laps to form closed joints. Repair or replace sheets when damaged during curing. Check daily to assure burlap has not lost all moisture. If moisture evaporates, resaturate burlap and re-place on pavement (limit re-saturation and re-placing to less than 10 minutes per sheet). Leave sheeting on concrete surface to be cured for at least 7 days.

3.6.2 Liquid Membrane-Forming Compound Curing

Apply compound immediately after surface loses its water sheen and has a dull appearance and before joints are sawed. Agitate curing compound thoroughly by mechanical means during use and apply uniformly in a two-coat continuous operation by suitable power-spraying equipment. Apply a total coverage for the two coats at least one gallon of undiluted

compound per 200 square feet to produce a uniform, continuous, coherent film that will not check, crack, or peel and free from pinholes or other imperfections. The application of curing compound by hand-operated, mechanical powered pressure sprayers is permitted only on odd widths or shapes of slabs and on concrete surfaces exposed by the removal of forms. When the application is made by hand-operated sprayers, apply a second coat in a direction approximately at right angles to the direction of the first coat. Apply an additional coat of compound immediately to areas where film is defective. Respray concrete surfaces that are subject to heavy rainfall within 3 hours after curing compound has been applied in the same manner.

3.6.3 Protection of Treated Surfaces

After the initial saw cut is complete and the slurry has been removed, respray the area with curing compound or restore the white burlap polyethylene sheet to maintain a continuous curing environment in the area of the sawn joints. Keep concrete surfaces to which liquid membrane-forming compounds have been applied free from vehicular traffic and other sources of abrasion for not less than 72 hours. Foot traffic is allowed after 24 hours for inspection purposes. Maintain continuity of coating for entire curing period and repair damage to coating immediately.

3.7 REPAIR, REMOVAL AND REPLACEMENT OF NEWLY CONSTRUCTED SLABS

3.7.1 General Criteria

Repair or remove and replace new pavement slabs as specified at no cost to the Government. Removal of partial slabs is not permitted. Prior to any repairs, submit a Repair Recommendations Plan detailing areas exceeding the specified limits as well as repair recommendations required to bring these areas within specified tolerances.

3.7.2 Slabs with Cracks

The Government may require cores to be taken over cracks to determine depth of cracking. Such cores are to be drilled with a minimum diameter of 6 inches, and be backfilled with an approved non-shrink concrete. Perform drilling of cores and filling of holes at no expense to the Government. Clean cracks that do not exceed 2 inches in depth; then pressure injected full depth with epoxy resin, Type IV, Grade 1. Remove and replace slabs containing cracks deeper than 2 inches.

3.7.3 Removal and Replacement of Full Slabs

Remove and replace slabs containing more than 15.0 percent of any longitudinal or transverse joint edge spalled. Where it is necessary to remove full slabs, remove in accordance with paragraph REMOVAL OF EXISTING PAVEMENT SLAB below. Remove and replace full depth, by full width of the slab, and the limit of removal normal to the paving lane and extend to each original joint. Compact and shape the underlying material as specified in the appropriate section of these specifications, and clean the surfaces of all four joint faces of all loose material and contaminants and coated with a double application of membrane forming curing compound as bond breaker. Install dowels of the size and spacing as specified for other joints in similar pavement by epoxy grouting them into holes drilled into the existing concrete using procedures as specified in paragraph Dowel Bars above. Provide dowels for all four edges of the new slab. Cut off original damaged dowels flush with the

joint face. Lightly oil or grease protruding portions of new dowels. Place concrete as specified for original construction. Take care to prevent any curing compound from contacting dowels. Prepare and seal the resulting joints around the new slab as specified for original construction.

3.7.4 Repairing Spalls Along Joints

Repair spalls along joints to be sealed to a depth to restore the full joint-face support prior to placing adjacent pavement. Where directed, repair spalls along joints of new slabs, along edges of adjacent existing concrete, and along parallel cracks by first making a vertical saw cut at least 3 inches outside the spalled area and to a depth of at least 2 inches. Provide saw cuts consisting of straight lines forming rectangular areas without sawing beyond the intersecting saw cut. Chip out the concrete between the saw cut and the joint, or crack, to remove all unsound concrete and into at least 1/2 inch of visually sound concrete. Thoroughly clean the cavity thus formed with high pressure water jets supplemented with oil-free compressed air to remove all loose material. Immediately before filling the cavity, apply a prime coat to the dry cleaned surface of all sides and bottom of the cavity, except any joint face. Apply the prime coat in a thin coating and scrubbed into the surface with a stiff-bristle brush. Provide prime coat for portland cement repairs consisting of a neat cement grout and for epoxy resin repairs consisting of epoxy resin, Type III, Grade 1. Fill the prepared cavity with material identified in the following table based on the cavity volume.

Spall Repairs	
Volume of Prepared Cavity After Removal Operations	Material
less than 0.03 cubic foot	epoxy resin mortar or epoxy resin or latex modified mortar
0.03 cubic foot and 1/3 cubic foot	Portland cement mortar
more than 1/3 cubic foot	Portland cement concrete or latex modified mortar

Provide portland cement concretes and mortars that consist of very low slump mixtures, 1/2 inch slump or less, proportioned, mixed, placed, consolidated by tamping, and cured, all as directed. Provide epoxy resin mortars made with Type III, Grade 1, epoxy resin, using proportions and mixing and placing procedures as recommended by the manufacturer and approved. Proprietary patching materials may be used, subject to Government approval. Place the epoxy resin materials in the cavity in layers with a maximum thickness of 2 inches. Provide adequate time between placement of additional layers such that the temperature of the epoxy resin material does not exceed 140 degrees F at any time during hardening. Provide mechanical vibrators and hand tampers to consolidate the concrete or mortar. Remove any repair material on the surrounding surfaces of the existing concrete before it hardens. Where the spalled area abuts a joint, provide an insert or other bond-breaking medium to prevent bond at the joint face. Saw a reservoir for the joint sealant to the dimensions required for other joints. Thoroughly clean the reservoir and then sealed with the sealer specified for the joints. In lieu of

sawing, spalls not adjacent to joints and popouts, both less than 6 inches in maximum dimension, may be prepared by drilling a core 2 inches in diameter greater than the size of the defect, centered over the defect, and 2 inches deep or 1/2 inch into sound concrete, whichever is greater. Repair the core hole as specified above for other spalls.

3.7.5 Repair of Weak Surfaces

Weak surfaces are defined as mortar-rich, rain-damaged, uncured, or containing exposed voids or deleterious materials. Diamond grind slabs containing weak surfaces less than 1/4 inch thick to remove the weak surface. Diamond grind in accordance with paragraph Diamond Grinding. All diamond ground areas are required to meet the thickness, smoothness and grade criteria specified in PART 1 GENERAL. Remove and replace slabs containing weak surfaces greater than 1/4 inch thick.

3.7.6 Repair of Pilot Lane Vertical Faces

Repair excessive edge slump and joint face deformation while concrete is in a plastic state by approved methods.

3.8 FIELD QUALITY CONTROL

3.8.1 Sampling

Collect samples of fresh concrete in accordance with ASTM C172/C172M during each working day as required to perform tests specified herein. Make test specimens in accordance with ASTM C31/C31M.

3.8.2 Consistency Tests

Perform concrete slump tests in accordance with ASTM C143/C143M. Take samples for slump determination from concrete during placement. Perform tests at the beginning of a concrete placement operation and for each batch (minimum) or every 20 cubic yards (maximum) of concrete to ensure that specification requirements are met. In addition, perform tests each time test beams are made. When slump is outside target limits, test every load until two consecutive tests indicate that the slump is within target limits.

3.8.3 Flexural Strength Tests

Test for flexural strength in accordance with ASTM C78/C78M. Fabricate and cure four test specimens in accordance with ASTM C31/C31M for each set of tests. Test two specimens at 7 days, and the other two at 28 days. Concrete strength will be considered satisfactory when the minimum of the 28-day test results equals or exceeds the specified 28-day flexural strength, and no individual strength test is less than the tolerance indicated on Table 1. If the ratio of the 7-day strength test to the specified 28-day strength is less than 65 percent, make necessary adjustments for conformance. Fabricate, cure and test a minimum of one set of four beams for each shift of concrete placement. Remove concrete which is determined to be defective, based on the strength acceptance criteria therein, and replace with acceptable concrete.

3.8.4 Air Content Tests

Test air-entrained concrete for air content at the same frequency as specified for slump tests. Determine percentage of air in accordance with

ASTM C231/C231M on samples taken during placement of concrete in forms. When air content is outside target limits, test every load until two consecutive tests indicate that the air content is within target limits.

3.8.5 Surface Testing

Surface testing for surface smoothness, edge slump and plan grade must be performed as indicated below by the Testing Laboratory. The measurements must be properly referenced in accordance with paving lane identification and stationing, and a report given to the Contracting Officer within 24 hours after measurement is made. Use the profilograph method for all longitudinal testing, except for paving lanes less than 200 feet in length. Use the straightedge method for transverse testing, for longitudinal testing where the length of each pavement lane is less than 200 feet, and at the ends of the paving limits for the project. Smoothness requirements do not apply over crowns, drainage structures, or similar penetrations. A final Surface Smoothness Report of surface testing, signed by a Registered Engineer, containing all surface measurements and a description of all actions taken to correct deficiencies, must be provided to the Contracting Officer upon conclusion of surface testing..

3.8.5.1 Straightedge Testing Method

Test the surface of the pavement with the straightedge to identify all surface irregularities exceeding the tolerances specified in Table 1. Test the entire area of the pavement in both a longitudinal and a transverse direction on parallel lines approximately 15 feet apart. Hold the straightedge in contact with the surface and move ahead one-half the length of the straightedge for each successive measurement. Determine the amount of surface irregularity by placing the straightedge on the pavement surface and allowing it to rest upon the two highest spots covered by its length and measuring the maximum gap between the straightedge and the pavement surface, in the area between these two high points.

3.8.5.2 Profilograph Testing Method

Perform profilograph testing using approved California profilograph and procedures described in ASTM E1274. Utilize electronic recording and automatic computerized reduction of data equipment to indicate "must-grind" bumps and the Profile Index for each 0.1 mile segment of the day's paving. Accommodate grade breaks on parking lots by breaking the profile segment into short sections and repositioning the blanking band on each section. Provide the "blanking band" of 0.2 inch wide and the "bump template" span 1 inch with an offset of 0.4 inch. Count the profilograph testing of the last 30 feet of a paving lane in the longitudinal direction from each day's paving operation on the following day's continuation lane. Compute the profile index for each pass of the profilograph (3 per lane) in each 0.1 mile segment. The profile index for each segment is the average of the profile indices for each pass in each segment. Scale and proportion profilographs of unequal lengths to an equivalent 0.1 mile as outlined in the ASTM E1274. Submit a copy of the reduced tapes to the Government at the end of each day's testing.

3.8.5.3 "Bumps" (Must Grind Areas)

Reduce any bumps ("must grind" areas) shown on the profilograph trace which exceed 0.4 inch in height by diamond grinding in accordance with subparagraph Diamond Grinding until they do not exceed 0.3 inch when

retested. Taper such diamond grinding in all directions to provide smooth transitions to areas not requiring diamond grinding.

3.8.5.4 Diamond Grinding

Those performing diamond grinding are required to have a minimum of three years experience in diamond grinding of rigid concrete pavements. In areas not meeting the specified limits for surface smoothness and plan grade, reduce high areas to attain the required smoothness and grade, except as depth is limited below. Reduce high areas by diamond grinding the hardened concrete with an approved equipment after the concrete is at a minimum age of 14 days. Perform diamond grinding by sawing with an industrial diamond abrasive which is impregnated in the saw blades. Assemble the saw blades in a cutting head mounted on a machine designed specifically for diamond grinding that produces the required texture and smoothness level without damage to the concrete pavement or joint faces. Provide diamond grinding equipment with saw blades that are 1/8-inch wide, a minimum of 60 blades per 12 inches of cutting head width, and capable of cutting a path a minimum of 3 ft wide. Diamond grinding equipment that causes ravels, aggregate fractures, spalls or disturbance to the joints is not permitted. The maximum area corrected by diamond grinding the surface of the hardened concrete is 10 percent of the total area of a day's production. The maximum depth of diamond grinding is 1/4 inch. Provide diamond grinding machine equipped to flush and vacuum the pavement surface. Dispose of all debris from diamond grinding operations off Government property. Prior to diamond grinding, submit a Diamond Grinding Plan for review and approval. At a minimum, include the daily reports for the deficient areas, the location and extent of deficiencies, corrective actions, and equipment. Remove and replace all pavement areas requiring plan grade or surface smoothness corrections in excess of the limits specified in Table 1. All areas in which diamond grinding has been performed are subject to the thickness tolerances specified in Table 1.

3.8.6 Plan Grade Testing and Conformance

Within 5 days after each day's paving, test the finished surface of the pavement area by running lines of levels at intervals corresponding with every longitudinal and transverse joint to determine the elevation at each joint intersection. Record the results of this survey and submit a copy to the Government at the completion of the survey.

3.8.7 Edge Slump

Test the pavement surface to determine edge slump immediately after the concrete has hardened sufficiently to permit walking thereon. Perform testing with a minimum 12 foot straightedge to reveal irregularities exceeding the edge slump tolerance specified in Table 1. Determine the vertical edge slump at each free edge of each slipformed paving lane constructed. Place the straightedge transverse to the direction of paving and the end of the straightedge located at the edge of the paving lane. Record measurements at 5 to 10 foot spacings, as directed, commencing at the header where paving was started. Initially record measurements at 5 foot intervals in each lane. When no deficiencies are present after 5 measurements, the interval may be increased. The maximum interval is 10 feet. When any deficiencies exist, return the interval to 5 feet. In addition to the transverse edge slump determination above, at the same time, record the longitudinal surface smoothness of the joint on a continuous line 1 inch back from the joint line using the minimum 12 foot straightedge advanced one-half its length for each reading. Perform other

tests of the exposed joint face to ensure that a uniform, true vertical joint face is attained. Properly reference all recorded measurements in accordance with paving lane identification and stationing, and submit a report within 24 hours after measurement is made. Identify areas requiring replacement within the report.

3.8.8 Test for Pavement Thickness

Take full depth cores of 4 inch diameter of concrete pavement every 4000 square feet in accordance with ASTM C42/C42M. Measure thickness in accordance with ASTM C1542/C1542M. Record and submit testing, inspection, and evaluation of each core for surface paste, uniformity of aggregate distribution, segregation, voids, cracks, and depth of reinforcement or dowel (if present). Moisten the core with water to visibly expose the aggregate and take a minimum of three photographs of the sides of the core, rotating the core approximately 120 degrees between photographs. Include a ruler for scale in the photographs. Submit plan view of location for each core.

3.8.9 Reinforcement

Inspect reinforcement prior to installation to verify it is free of loose flaky rust, loose scale, oil, mud, or other objectionable material.

3.8.10 Dowels

Inspect dowel placement prior to placing concrete to verify that dowels are of the size indicated, and are spaced, aligned and painted and oiled as specified. Do not permit dowels to exceed the tolerances shown in paragraph: DOWEL BARS.

-- End of Section --

Pavement Thickness Report
U.S. Army Corps of Engineers
PCASE Version 2.09.06
Date : 10/27/2020

Design Name : COMPOUND PCC
 Design Type : Roads
 Pavement Type : Rigid
 Road Type : Road
 Terrain Type : Flat
 Analysis Type : K
 Depth of Frost (in) : 0
 Wander Width (in) : 33.35
 % Load Transfer : 0
 Effective K (pci) : 262
 Reduced Sub Effective K (pci) : 0
 Joint Spacing : 10 to 15 ft
 Dowel Spacing : 12.00 in
 Dowel Length : 16.00 in
 Dowel Diameter: .75 in

Use 7.5" PCC on 6" ABC on 6" Subbase on Compacted Subgrade

NOTE: the M1070 Tractor with M1000 Trailer carrying an M1A1 Abrams tank governs the design

NOTE: car & pickup traffic are irrelevant to the result, therefore were not listed.

NOTE: Design subgrade K=150 is conservative, and based on limited CBR testing; PCASE model run with historical value of k=200 results in 7.14" PCC

Layer Information

Layer Type	Material Type	Frost Code	Moisture Content	Dry Unit Weight (lb/ft ³)	Flexural Strength (lb/ft ³)	CbCr (psi)	% Steel	Analysis	Non frost Design Thickness (in)	K Strength (pci)
PCC	NA	NFS	0	145	650	0	0	Compute	7.38	0
BASE	BASCA	NFS	5	135	0	0	0	Manual	12	0
SUBG	COHCUT	F3/F4	18	100	0	0	0	Manual	0	150

Traffic Information

Pattern Name	FIO'S FGR		
Vehicles	Weight (lb)	Passes per Life Span"	Equivalent Passes
M1070 HET TRACTOR W/M1000	229750	403000	403000
M1074 LOAD SYSTEM W/CRANE	140859	403000	19494
M1A1, MAIN TANK TRACKED	126000	403000	42631
M2A3, BRADLEY VEHICLE TRA	58200	403000	1322
P-23 CRASH TRUCK (FIRE TR	77880	300	142
STRYKER, RECON VEHICLE	43352	403000	310
M1070 HET TRACTOR W/M1000 TRL W/M1A1 TANK	229750		466899

HOT WATER BOILER SCHEDULE

Table with 15 columns: MARK, LOCATION (ROOM), TYPE, FUEL TYPE, MAX INPUT (MBH), MIN OUTPUT (MBH), RATED EFFICIENCY (%), GPM, EWT (°F), LWT (°F), MAX P.D. (FT H2O), MIN GPM, AIR INTAKE DIA. (IN), VENT DIA. (IN), ELECTRICAL, NOTES. Rows include B-1 and B-1*.

- 1. PROVIDE WITH CONDENSATE NEUTRALIZING FILTER KIT ROUTED TO NEARBY FLOOR SINK.
2. SIZE INTAKE AND VENT DIAMETERS BASED ON CHOSEN MANUFACTURER'S WRITTEN RECOMMENDATIONS.
3. MINIMUM OUTPUT SHOWN ASSUMES BOILER MUST BE DE-RATED 2% PER 1,000 FT ABOVE SEA LEVEL. PROJECT ELEVATION = 4,900 FT.
4. PROVIDE UNIT IF OPTION 3 IS NOT EXERCISED.
5. PROVIDE UNIT IF OPTION 3 IS EXERCISED.

NOTE: UNITS DESIGNATED WITH (*) SHALL BE PROVIDED IN PLACE OF COUNTERPART IF OPTION 3 IS NOT EXERCISED.

VAV TERMINAL UNIT SCHEDULE

Table with 14 columns: MARK, AIRFLOW (COOLING, HEATING, MAX AIR PRESSURE DROP, INLET SIZE), REHEAT COIL (MIN COIL CAPACITY, ENTERING AIR TEMP, LEAVING AIR TEMP, GPM, MAX WATER PRESSURE DROP, EWT), CONTROL VALVE, VALVE CV, NOTES. Rows include ATU-101 through ATU-112.

- 1. PROVIDE UNIT IF OPTION 3 IS EXERCISED.

AIR-COOLED CHILLER SCHEDULE

Table with 18 columns: MARK, LOCATION, MIN CAPACITY (TONS), MIN IPLV (EER), EVAPORATOR DATA (GPM, EWT, LWT, MAX P.D.), CONDENSER DATA (AMBIENT TEMP, FAN QTY, REFRIGERANT TYPE), COMPRESSOR TYPE, COMPRESSOR QTY, MAX POWER (KW), ELECTRICAL, WEIGHT (LBS), NOTES. Rows include CH-1 and CH-1*.

- 1. MINIMUM CAPACITY SHOWN IS REQUIRED AFTER TAKING INTO ACCOUNT PERFORMANCE AT 4,900 FT ELEVATION. SELECT UNIT THAT CAN MEET OUTPUT BASED ON MANUFACTURER'S RECOMMENDATIONS FOR ELEVATION LOSSES.
2. PROVIDE UNIT IF OPTION 3 IS NOT EXERCISED.
3. PROVIDE UNIT IF OPTION 3 IS EXERCISED.

HYDRONIC WATER PUMP SCHEDULE

Table with 11 columns: MARK, TYPE, SERVICE, GPM, HEAD (FT H2O), PROPYLENE GLYCOL (%), MOTOR (RPM, HP, ELECTRICAL), MIN. EFFICIENCY, VFD / ECM, NOTES. Rows include BP-1, BP-1*, HWP-1, HWP-1*, HWP-2, HWP-2*, CWP-1, CWP-1*, CWP-2, CWP-2*.

- 1. PROVIDE UNIT IF OPTION 3 IS EXERCISED.

AIR SEPARATOR SCHEDULE

Table with 6 columns: MARK, LOCATION (ROOM), GPM, MAX. WATER PRESSURE DROP (FT WC), SERVICE, NOTES. Rows include AST-1, AST-1*, AST-2, AST-2*.

- 1. PROVIDE UNIT IF OPTION 3 IS EXERCISED.

CHILLED WATER BUFFER TANK SCHEDULE

Table with 6 columns: MARK, LOCATION, CAPACITY (GAL), TYPE, SYSTEM, NOTES. Row includes BT-1.

- 1. ASME STAMPED, 125 PSI RATED WORKING PRESSURE.

HYDRONIC EXPANSION TANK SCHEDULE

Table with 10 columns: MARK, LOCATION (ROOM), SERVICE, TYPE, MIN VOLUME (GAL), MIN ACCEPT. VOLUME (GAL), CHARGE PRESSURE (PSI), MAX OPERATING TEMP (°F), MAX OPERATING PRESSURE (PSI), NOTES. Rows include ET-1 and ET-2.



US Army Corps of Engineers

Vertical table with columns: MARK, DESCRIPTION, DATE. Includes project details and revision notes.

Vertical table with columns: DESIGNED BY, CHECKED BY, SUBMITTED BY, REVIEWED BY, DATE. Includes names and dates for project milestones.

FT. HUACHUCA GROUND TRANSPORT EQUIPMENT BUILDING HVAC SCHEDULES

SHEET IDENTIFICATION M-602



Polarized Light Microscope (PLM) Analysis for Asbestos in Bulk Sample

JobNumber: 202009616

Client: FACILITY SERVICES MANAGEMENT

CLARKSTON RD BLDG 30033

FT HUACHUCA, AZ 85613-0000

Office Phone: (520) 533-5906

FAX:

Samples: 4 PLM **Rec:** 10/21/2020 **Method:** EPA 600/R-93/116 The "New" Method; see below
Client Job: 1-9625624 **PO Number:** 68048
Report Date: 10/26/2020 **Date Analyzed:** 10/26/2020 **Routing Number:** -

Method and Analysis Information: Fiberquant Internal SOP: PLMn

Each bulk sample is first dissected under a 7-30x magnification stereo-microscope. This examination is used to determine the general type of sample, how many and what type of layers it has, and initial estimates of fiber types and quantities. Second, liquid media mounts are made of each layer - such mounts may be of selected fibers (used solely for identification purposes) or may be representative of the layer as a whole (used for quantitation purposes). The mounts may be made in a synthetic Canadian balsam, one of several solvents, or in refractive index oils (media of known refractive index). Generally, a variety of different mounts are made: some optimized for fiber visibility, some optimized for fiber identification, and some optimized for fiber quantitation. The mounted slides are then examined at 50-400x magnification on a Nikon Labphot-pol microscope. Optical characteristics are used to identify each observed fiber type; the optical data are contained for each sample on its detail analysis sheet, attached.

Current EPA and NESHAP regulations designate a result of $\leq 1\%$ asbestos as "negative" or "non-regulated" and $> 1\%$ asbestos as "positive" or "regulated." Samples containing layers that have been determined to be "positive" may have to be handled differently during a renovation or demolition than samples whose layers have been determined to be "negative." OSHA under CFR 1926.1101 regulates work done involving any detectable concentration of asbestos.

The method of fiber identification and quantitation is the "Standard Operating Procedures for the Analysis of Asbestos in Bulk Samples using Polarized Light Microscopy", Chapter 7 of the Quality Assurance and Management Manual. This SOP and its associated reporting have been designed to satisfy all requirements in both EPA Method 600/M4-82-020 (The Interim Method) and EPA Method 600/R-93/116 (The New Method). The Interim Method is the required method for AHERA (US EPA 40 CFR Pt. 763), but this method calls for the reporting of composited results of multi-layered samples that is no longer an acceptable reporting practice in most circumstances. Current EPA rules, such as NESHAP (US EPA 40 CFR Pt. 61), as well as NVLAP accreditation policies, call for separate reporting for each layer of multi-layered samples. The New Method contains the same procedures for identification and quantitation of asbestos as does the Interim Method, except that multi-layered samples are reported to comply with the latest US EPA rule. Fiberquant not only reports the asbestos content of each layer of multi-layered samples separately (satisfying current EPA and NVLAP reporting requirements), but Fiberquant also reports what percentage of the sample each layer comprises. Therefore, the results may be arithmetically composited to satisfy the reporting requirements of the Interim Method. The method of fiber quantitation is an estimation technique in which the analysts quantitation is routinely calibrated by reference quantitation standards, and which has been shown to be equivalent in precision and accuracy to point counting. Friability is estimated for the purposes of deciding when to point count. Friabilities determined in the field take precedence over those determined in the laboratory. Those sample layers which are friable and estimated by the analyst to contain $\leq 1\%$ asbestos are point counted using 400 points. Such point counting is required by NESHAP (National Emission Standards for Hazardous Air Pollutants, Nov. 1990) in order to rely on analytical results that are $\leq 1\%$. The coefficient of variation for the estimation quantitation technique is 100% in the range 0-5%. This means that PLM analysis is not capable of conclusively determining whether a layer containing close to 1% asbestos is actually "positive" or "negative". For this reason, Fiberquant refers to results where asbestos was detected but $\leq 1\%$ as "borderline negative", and results where asbestos was $> 1\%$ but $\leq 2\%$ as "borderline positive" to indicate the uncertainty in assigning a "positive" or "negative" label. In the sample summary, "ND" means that no asbestos was detected during the analysis. A "Tr" or "Trace" of asbestos reported is defined for our purposes as the detection of several asbestos fibers during the analysis; this level would be right at the limit of detection for the method. Trace is only reported on the analysis detail - in the summary a trace would be reported as $\leq 1\%$. The limit of detection (the smallest % of asbestos that can be detected) varies greatly depending on the matrix in which the asbestos is found. As little as 0.001% asbestos can be detected in favorable samples, while detection in unfavorable samples may approach the detection limit of 1% stated in the method. During the analysis, the analyst, for Fiberquant identification purposes only, determines the "apparent sample type" and "apparent layer types." It must be emphasized that these types are only what is apparent. Often, different materials appear similar or identical after sampling, so the analyst may assign a type other than what was sampled.

Floor tiles present a special problem for PLM asbestos analysis. Floor tile can contain chrysotile fibers so thin that they cannot be resolved by optical methods. In such a case, we may observe a percentage of asbestos which is lower than the actual percentage, or not observe asbestos at all when some is present. For this reason, floor tiles reported as negative should be confirmed to be negative using transmission electron microscope (TEM) analysis. Likewise, vermiculite insulation materials containing traces of asbestiform asbestos present a problem for routine PLM analysis - the amphiboles are sometimes present in trace amounts inhomogeneously distributed. For this reason, loose vermiculite samples reported as negative should be confirmed to contain no amphibole using hydroseparation techniques.

The samples were analyzed under the following ongoing quality assurance program: Blank samples are routinely analyzed to maintain contamination-free materials. Each analyst has at least a bachelor's degree in physical science, and has also completed extensive training specific to asbestos analysis for 1-3 months before being allowed to analyze client samples. Qualitative reference samples are routinely analyzed to assure that analysts

PLM Analysis Details

Job Number: 202009616 1-9625624

Sample 68048-01 **Lab Number** 2020-09616- 1 **Sampled:** 10/20/2020 **Condition:** acceptable
Analyzed By MCJ 10/26/2020 **An?** OK **Apparent Smp Type** Cementitious Non-fibrous Solid
Homogeneous Yes **# Layers** 1 **Asbestos Detected?** No
Non-Fibrous Components (in approx. decreasing order): powder, rock,

Layers					Calibrated Visual Estimate of Percents of Each Fiber					
#	Layer Type	%	Color	Friability	Fib 1	Fib 2	Fib 3	Fib 4	Fib 5	Fib 6
1	concrete	100	gray	1	n.d.	-	-	-	-	-
Total %		100	Overall %		n.d.	-	-	-	-	-
Fiber Identification:					none					

Fibers								Refractive Index Determinations				
#	Color	Mrph	Iso	Pleo	Bi	Elg	Ext	Oil	Col Par	Col Per	RI Par	RI Per
1	none											
2												
3												
4												
5												
6												

Sample Analytical Note
 Procedure: tweased apart using forceps. Procedure: dissolution of matrix using dilute HCl acid.

Sample 68048-02 **Lab Number** 2020-09616- 2 **Sampled:** 10/20/2020 **Condition:** acceptable
Analyzed By MCJ 10/26/2020 **An?** OK **Apparent Smp Type** Insulation Fibrous Mat
Homogeneous No **# Layers** 2 **Asbestos Detected?** No
Non-Fibrous Components (in approx. decreasing order): polymer, powder, metal

Layers					Calibrated Visual Estimate of Percents of Each Fiber					
#	Layer Type	%	Color	Friability	Fib 1	Fib 2	Fib 3	Fib 4	Fib 5	Fib 6
1	insulation wrap	50	off-white	2	40-50%	5-10%	-	-	-	-
2	insulation	50	yellow	3	n.d.	90-100%	-	-	-	-
Total %		100	Overall %		20-30%	50-60%	-	-	-	-
Fiber Identification:					cellulose fiber	glass fiber				

Fibers								Refractive Index Determinations				
#	Color	Mrph	Iso	Pleo	Bi	Elg	Ext	Oil	Col Par	Col Per	RI Par	RI Per
1	cellulose fiber	W	F	N	N	H	+	U				
2	glass fiber	CL	D	Y								
3												
4												
5												
6												

Sample Analytical Note
 Procedure: tweased apart using forceps. Procedure: dissolution of polymer matrix using solvent.

Sample 68048-03 Lab Number 2020-09616- 3 Sampled: 10/20/2020 Condition: acceptable
 Analyzed By MCJ 10/26/2020 An? OK Apparent Smp Type Wall System Fibrous Solid
 Homogeneous No # Layers 4 Asbestos Detected? No
 Non-Fibrous Components (in approx. decreasing order): powder, binder,

Layers					Calibrated Visual Estimate of Percents of Each Fiber					
#	Layer Type	%	Color	Friability	Fib 1	Fib 2	Fib 3	Fib 4	Fib 5	Fib 6
1	paint	1	various	1	n.d.	n.d.	-	-	-	-
2	texture/joint compound	15	white	3	n.d.	n.d.	-	-	-	-
3	paper/cardboard	5	tan	2	90-100%	n.d.	-	-	-	-
4	drywall core	79	white	3	n.d.	<=1%	-	-	-	-
Total %		100	Overall %		2-5%	<=1%	-	-	-	-

Fiber Identification: cellulose fiber cellulose fiber

Fibers									Refractive Index Determinations				
	Color	Mrph	Iso	Pleo	Bi	Elg	Ext		Oil	Col Par	Col Per	RI Par	RI Per
1	cellulose fiber	W	F	N	N	H	+	U					
2	cellulose fiber	W	F	N	N	H	+	U					
3													
4													
5													
6													

Sample Analytical Note
 Procedure: tweased apart using forceps. Procedure: dissolution of paint matrix using solvent. Procedure: dissolution of joint compound/texture matrix using acid.

Sample 68048-04 Lab Number 2020-09616- 4 Sampled: 10/20/2020 Condition: acceptable
 Analyzed By MCJ 10/26/2020 An? OK Apparent Smp Type Miscellaneous Rubbery
 Homogeneous No # Layers 2 Asbestos Detected? No
 Non-Fibrous Components (in approx. decreasing order): polymer, filler,

Layers					Calibrated Visual Estimate of Percents of Each Fiber					
#	Layer Type	%	Color	Friability	Fib 1	Fib 2	Fib 3	Fib 4	Fib 5	Fib 6
1	base cove	90	tan	1	n.d.	-	-	-	-	-
2	mastic	10	off-white	1	n.d.	-	-	-	-	-
Total %		100	Overall %		n.d.	-	-	-	-	-

Fiber Identification: none

Fibers									Refractive Index Determinations				
	Color	Mrph	Iso	Pleo	Bi	Elg	Ext		Oil	Col Par	Col Per	RI Par	RI Per
1	none												
2													
3													
4													
5													
6													

Sample Analytical Note
 Procedure: tweased apart using forceps. Procedure: dissolution of polymer matrix using solvent. Minor adhering wall paint and/or texture, etc. not analyzed.

Fr=Friability: 1=very non-friable; 2= non-friable; 3=friable; 4=highly friable
 Colors: B=black;BL=blue;BR=brown;CL=clear;G=Green;GY=gray;OR=orange;OW=off-white;PN=pink;PU=purple;R=red;TN=tan;W=white;Y=yellow;V=various
 Fiber Morphology: A=fine fibers/bundles, white, sinewy, flexible; B=fine fibers/bundles, w-br, straight, broomed ends; C=fine fibers/bundles, blue, straight, broomed ends;
 D=fine to coarse fibers, CL-B, brittle; E=coarse fibers,CL or dyed, striated; F=coarse fibers or splinters, W-BR, ribbon-like; G=lath-like or shards, low aspect ratio, may taper
 Iso=isotropism - may be yes or no; Pleo=pleochroism - may be yes or no; Bi=birefringence - may be None, Low, Medium or High
 Elg=sign of elongation - may be +, - or B (both); Ext=extinction - may be Parallel, Oblique, None or Undulating; Oil=medium used to for dispersion staining
 Col Par=dispersion staining colors parallel to the fiber (fiber/halo): b/w=black/white; dg/py=dark gray/pale yellow; vg/y=violet gray/yellow; db/ly=dark blue/lemon yellow; vb/g= vivid blue/gold; sb/o=sky blue/orange; pb/r=pale blue/red; gb/dr=gray blue/dark red; w/b=white/black. Col Perp=same only perpendicular to fiber.
 RI Par=refractive index parallel to fiber; RI Perp=refractive index perpendicular to fiber



Analyst: MARK C. JEFFERSON

Printed: 26-Oct-20

Original Print Date: 26-Oct-20



Larry S. Pierce, Approved Accreditation Signatory

FIBERQUANT

ANALYTICAL SERVICES

Fiberquant Analytical Services 5025 S. 33rd St.;
Phoenix, AZ 85040; Phone: 602-276-6139; FAX: 602-276-4558;
info@fiberquant.com

Analysis Request/Chain-of-Custody Form

Submitted by (Company)	Facility Services Management		
Address	Clarkson RD Building 30033		
City, State, Zip Code	Fort Huachuca, AZ 85613		
Phone	520-533-5906	FAX	N/A
Email	william.j.barnes88.ctr@mail.mil		

Invoice to (Company)	Department of Public Works		
Address	3040 Butler Road Building 22422		
City, State, Zip Code	Fort Huachuca, AZ 85613		
Phone	520-533-2837	FAX	520-533-2227

Contact (print)	Billy Barnes		
Sampled by (signature)			
Job Number or Project Name	1-9625624		
PO Number	68048		

Analysis Method Requested ONLY ONE METHOD per COC		Turn-around-time (single pass)		
		Rush	Norm	Ext
Asbestos by PLM	Improved <input type="checkbox"/> Interim <input type="checkbox"/>	Urg. Rush <3 hrs <input type="checkbox"/>	<6 hrs <input type="checkbox"/>	1-3 days <input checked="" type="checkbox"/>
	Analyze: <input checked="" type="checkbox"/> All or <input type="checkbox"/> ATPF If ATPF then by: Layer <input type="checkbox"/> or Sample <input type="checkbox"/> Single Layer Protocol: Yes <input type="checkbox"/> No <input type="checkbox"/>			15-30 days <input type="checkbox"/>
Fibers by PCM	7400(Area) <input type="checkbox"/> ORM (Personal) <input type="checkbox"/>	<4 hr <input type="checkbox"/>	24hr <input type="checkbox"/>	-
Asbestos by TEM	AIR: AHERA <input type="checkbox"/> Mod. AHERA <input type="checkbox"/>	<6hr <input type="checkbox"/>	24 hr <input type="checkbox"/>	3-5d <input type="checkbox"/>
	Water*: Water <input type="checkbox"/> Sludge <input type="checkbox"/>	1-2d <input type="checkbox"/>	3-5d <input type="checkbox"/>	N/A
	Annex2: Chatfield <input type="checkbox"/> Full <input type="checkbox"/>			
	Vacuum Dust (ASTM)	3-5d <input type="checkbox"/>	5-10d <input type="checkbox"/>	N/A
Pb by FLAA	Analyte: Pb Other <input type="checkbox"/>	<6 hrs <input type="checkbox"/>	2-3 days <input type="checkbox"/>	N/A
	Filter: MCE <input type="checkbox"/>			
	Matrix: Paint: by Area <input type="checkbox"/> by Weight <input type="checkbox"/>			
	Soil <input type="checkbox"/>			
	Wipe <input type="checkbox"/>			
Initial here certifying wipes used are ASTM E1792 compliant <input type="checkbox"/>				
Fungi	Air Sample: Zef <input type="checkbox"/> Aller <input type="checkbox"/> Oth <input type="checkbox"/>	<6 hrs <input type="checkbox"/>	1-2 days <input type="checkbox"/>	N/A
	Bulk: Sample <input type="checkbox"/> Swab <input type="checkbox"/>			
	Tape: Quantitative (%) <input type="checkbox"/> or Quantitative (cm2) <input type="checkbox"/>			
Soot	ASTM D6602-03B	Optical <input type="checkbox"/>	<6r <input type="checkbox"/>	1-2 days <input type="checkbox"/>
		Optical & TEM <input type="checkbox"/>	1-2 days <input type="checkbox"/>	3-5days <input type="checkbox"/>
Other		Call	Call	

Sample Number	Description/Location (include assr type/maker/exp. Date)	Sample Date	Sample Time	Vol/Area
1) 68048-01	CONCRETE SLAB, FOUNDATION		20-OCT-2020	
2) ↓	-02 INSULATION COVER/INT. WALL INSULATION		↓	
3) ↓	-03 DRYWALL+MUDD+TEXT./INT. OFFICE WALL		↓	
4) ↓	-04 COVE BASE + MASTIC/INT. OFFICE		↓	
5)				
6)				
7)				
8)				
9)				
10)				
11)				
12)				
13)				
14)				
15)				
16)				
17)				
18)				
19)				
20)				

1) Relinquished by:	Date: 20-OCT-2020	Time: 1100	3) Relinquished by:	Date:	Time:
2) Received by:	Date: 20-21-2020	Time: 1015	4) Received by:	Date:	Time:
* TEM Water Sampler's name Required by State of Arizona	Print Name		EX Standard 2 of 2		

Review of Analysis Request (Initials) ET

Note: Data completed by client (including number and identity of samples) is assumed to be correct until it is verified at time of sample preparation.

**AMENDMENT 4 APPENDIX 1 HAZMAT TESTING
ASBESTOS SAMPLE PLAN**

Page 1 of 1

DATE: 20-Oct-2020		SO #: 1-9625624		BLDG #: 68048	
Work Description: Demo building, WO #FEE18079-8J					
Sample #	Description	Location			
68048-01	Concrete	Slab, foundation			
68048-02	Insulation cover	Interior wall insulation			
68048-03	Drywall + mud + texture	Interior office wall			
68048-04	Cove base + mastic	Interior office			

LEAD SAMPLE PLAN

Page 1 of 1

DATE: 20-Oct-2020		SO #: 1-9625624		BLDG #: 68048	
Work Description: Demo building, WO #FEE18079-8J					
Sample #	Description	Location			Result
-1	White, metal	Roll up door frame, west side			Neg
-2	Red, steel	Beam structure			Neg
-3	White, wood	Interior plywood wall panel			Neg
-4	White, metal	Door frame, west side			Neg
-5	White, metal	Door, west side			Neg
-6	Tan, metal	Exterior sheet metal wall siding			Neg
-7	White, metal	Door frame, interior office			Neg
-8	White, drywall	Interior office wall			Neg
-9	Gray, metal	Roll up door, east side			Neg
-10	White, metal	Hand rail, exterior stairs, NE corner			Neg

Appendix 3-PCC Pavement Details

Pavement Thickness Report
U.S. Army Corps of Engineers
PCASE Version 2.09.06
Date : 10/27/2020

Design Name : COMPOUND PCC
 Design Type : Roads
 Pavement Type : Rigid
 Road Type : Road
 Terrain Type : Flat
 Analysis Type : K
 Depth of Frost (in) : 0
 Wander Width (in) : 33.35
 % Load Transfer : 0
 Effective K (pci) : 262
 Reduced Sub Effective K (pci) : 0
 Joint Spacing : 10 to 15 ft
 Dowel Spacing : 12.00 in
 Dowel Length : 16.00 in
 Dowel Diameter: .75 in

Use 7.5" PCC on 6" ABC on 6" Subbase on Compacted Subgrade

NOTE: the M1070 Tractor with M1000 Trailer carrying an M1A1 Abrams tank governs the design

NOTE: car & pickup traffic are irrelevant to the result, therefore were not listed.

NOTE: Design subgrade K=150 is conservative, and based on limited CBR testing; PCASE model run with historical value of k=200 results in 7.14" PCC

Layer Information

Layer Type	Material Type	Frost Code	Moisture Content	Dry Unit Weight (lb/ft ³)	Flexural Strength (lb/ft ³)	CbCr (psi)	% Steel	Analysis	Non frost Design Thickness (in)	K Strength (pci)
PCC	NA	NFS	0	145	650	0	0	Compute	7.38	0
BASE	BASCA	NFS	5	135	0	0	0	Manual	12	0
SUBG	COHCUT	F3/F4	18	100	0	0	0	Manual	0	150

Traffic Information

Pattern Name	FIO'S FGR		
Vehicles	Weight (lb)	Passes per Life Span"	Equivalent Passes
M1070 HET TRACTOR W/M1000	229750	403000	403000
M1074 LOAD SYSTEM W/CRANE	140859	403000	19494
M1A1, MAIN TANK TRACKED	126000	403000	42631
M2A3, BRADLEY VEHICLE TRA	58200	403000	1322
P-23 CRASH TRUCK (FIRE TR	77880	300	142
STRYKER, RECON VEHICLE	43352	403000	310
M1070 HET TRACTOR W/M1000 TRL W/M1A1 TANK	229750		466899