



COUNTY OF TULARE



General Services Department Capital Projects Division

2637 W. BURREL AVE. SUITE 200
VISALIA, CA. 93291
PHONE (559) 205-1100

June 14, 2024

**Addendum No. 5
COUNTY OF TULARE – Springville Library**

Please see the attached Addendum No. 5

Mark Van Fossen

**Mark Van Fossen
Capital Project Coordinator III**



ADDENDUM

**Springville Library
County of Tulare
569-0003**

Date: June 13, 2024

To: All Bidders

Subject: Addendum # 5

*Total Addendum includes:
[15] 8.5x11*

NOTICE TO CONTRACTORS FIGURING THIS WORK

You are hereby notified of the following changes in the Plans and Specifications, which shall take precedence over anything to the contrary therein.

Item # Description

5.1 General questions asked and answered during Bidding:

- 5.1.1 Question: Interior Finish Schedule for room 104 Community room & 109 office on DWG sheet A2.00 refers for wall tag 2-GWT1 which is Glazed Wall Tile beside GYP BD, but interior elevations on DWG sheet A6.00 & A6.01 don't refer for any wall tile in these two rooms. Please Confirm/Suggest/Guide.

Answer: See Addendum 05, Item 5.2.

5.2 Refer to Sheet A6.00, Sheet A6.01 and Sheet A2.00:

- 5.2.1 Refer to Sheet A6.00, 104 Community Room, N Elevation. GWT-1 finish shall be installed between top of counter splash and bottom of cabinets. GWT-1 shall also be installed on both sides of counter above splash return. Tile trim piece(s) required at exposed tile ends.
- 5.2.2 Refer to Sheet A6.01, 109 Office, S Elevation. GWT-1 finish shall be installed between top of counter splash and bottom of cabinets. GWT-1 shall also be installed on both sides of counter above splash return. Tile trim piece(s) required at exposed tile ends.
- 5.2.3 Refer to Sheet A2.00 INTERIOR FINISH SCHEDULE. Refer to 109 Office. Change North Wall Finish to MTL 1, FIN 1. Change South Wall Finish to MTL 1/2, FIN A/C.

End of addendum