



LIMITED ASBESTOS AND LEAD COATED MATERIAL SURVEY

Performed at the

Inglewood Library
101 Manchester Blvd.
Inglewood, CA 90301

Performed on August 2, 3, and 4, 2023

Submitted to

Dustin Alamo
Griffin Structures
1 Technology Drive
Building 1, Suite 829

Irvine, CA 92618

HSA Project Number 230201LA

September 19, 2023

Prepared By:

Devin S. Berman, CAC, CDPH I/A
Project Manager

Reviewed By:

Joel I. Berman, CIH, CSP, CAC, CIAQM, CDPH I/A/PM
President





Executive Summary

Pursuant to your request, Health Science Associates (HSA) performed a limited asbestos and lead material survey at the Inglewood Library, located at 101 Manchester Blvd., Inglewood, CA 90301 on August 2, 3 and 4, 2023.

The purpose of the survey is to perform interior asbestos bulk and XRF sampling of the interior and exterior of the building to determine if asbestos abatement is required prior to an upcoming demolition/renovation to the building and if lead coated components were present.

Bulk Asbestos Sample Results

HSA collected 167 suspect bulk asbestos samples totaling in 414 analyses by layer. Of these, 40 samples were determined to be asbestos containing material (ACM) and 48 samples were determined to be asbestos containing construction material (ACCM) per the PLM method. 18 of the ACCM samples were further analyzed by the Point Count method and the majority of those samples were confirmed to be ACCM. Additionally, there were samples with a trace results where there lab determined that there was not enough of the material to perform follow-up point counting. Prior to any impact of these materials, follow-up bulk sampling should be performed or the materials must be assumed to be ACM.

Listed on Table IB are the materials that were determined to be ACM/ACBM and/or ACCM per laboratory analysis, or assumed to be ACM/ACBM/ACCM where bulk sampling was not possible. The samples identified as ACM are in bold and shaded. The samples identified as ACCM are in bold.

The assumed ACM/ACBMs, such as the mirror mastic, should either be sampled prior to any disturbance or treated as ACM/ACBM during the demolition activities and for waste purposes.

Finally, the high ceiling area in the northeast corner of the building was in-accessible for bulk asbestos sampling due to the inability for a lift to access the area. For this area to be impacted, a scaffold will need to be erected. When this occurs, HSA recommends that prior to any impact of the high ceiling material (which appears to be fiberglass), bulk asbestos samples shall be collected to determine the asbestos content, if any, of this material.

Lead Sample Results

Results for the lead X-Ray Fluorescence (XRF) survey are presented in Table IIA. A total of 402 measurements were taken using a Niton XRF Analyzer, including pre and post calibration measurements for quality control. Of these, 57 XRF measurements were identified as lead-based paint (LBP) in accordance with the requirements of HUD and the CDPH, and 10 XRF measurements were determined to be lead-containing paint (LCP). In addition, four paint chip samples were collected and confirmed to be LCP.



Executive Summary - Continued

Finally, the mural on the west wall of the high ceiling area in the northeast corner of the building, was also in-accessible for LBP measurements. For this area to be impacted, a scaffold will need to be erected. When this occurs, HSA recommends that prior to any impact of the mural, XRF sampling be performed to determine the lead content, if any, of this material.

While ACM/ACCM and LBP/LCP were identified in the materials sampled at the Inglewood Library located at 101 Manchester Blvd., Inglewood, CA, the results are considered to be normal for a building of this age. Additionally, the materials (ACMs/ACCMs and LBPs/LCPs) present in the building were observed to be in good condition at the time of HSA's survey.

It is HSA's understanding that the property will undergo maintenance/renovation and/or demolition work that may require asbestos and/or lead abatement or impact at some future date. All contractors performing asbestos and/or lead related work at this location must perform their work pursuant to appropriate Asbestos and/or Lead specifications. The project should be monitored under the direction of a Certified Industrial Hygienist (CIH), who is also a State of California Certified Asbestos Consultant (CAC) and Certified Lead Project Designer

Lead waste should be segregated and a waste profile should be conducted on porcelain sinks and toilets, ceramic tile, paint chips, and other wastes possibly contaminated with or containing lead to comply with all local, State, and Federal laws by the contractor at the conclusion of the demolition of these materials.

Care should be taken when performing any activities (e.g. manually dry sanding or scraping surfaces) to prepare any of the component(s) either determined to be coated with or which are suspected of containing lead for repainting.

Due to the nature, age, and use of the structure, hidden or unknown suspect ACM/ACCM, lead or other hazardous materials may be uncovered during renovation/maintenance activities. Therefore, all contractors working on the project should be informed of policies with regard to notifying management if previously unidentified suspect hazardous materials are discovered during the project.

This report was prepared for use by Griffin Structures in evaluating the subject site. The information contained within this report is as factual as possible and the opinions related herein are based on HSA's experience in similar investigations. Therefore, no warranty is made to any persons other than Griffin Structures regarding the conclusions or recommendations included within this report. HSA will not release copies to a third party without prior written consent of Griffin Structures. Please contact HSA at hsa@healthscience.com for any questions or concerns about the contents of this report.

TABLE OF CONTENTS

	Page
Executive Summary	ii
1.0 INTRODUCTION	1
2.0 SITE DESCRIPTION	1
3.0 METHODOLOGY	1
4.0 STANDARDS AND GUIDELINES	4
5.0 RESULTS	8
6.0 RECOMMENDATIONS	9
TABLE IA - BULK ASBESTOS SAMPLING RESULTS	11
TABLE IB - ACM/ACCM ASBESTOS SAMPLING RESULTS	37
TABLE IIA - LEAD BASED PAINT XRF RESULTS	53
TABLE IIB - LBP and LCP XRF RESULTS	78
TABLE III - LEAD BASED PAINT RESULTS	84
Appendix A - Laboratory Reports	
Appendix B - Figures	
Appendix C - Photo Exhibit	
Appendix D - Licenses	
Appendix E - Notifications	

1.0 INTRODUCTION

- 1.1 Pursuant to your request, Health Science Associates (HSA) performed a limited asbestos and lead material survey at the Inglewood Library, located at 101 Manchester Blvd., Inglewood, CA 90301 on August 2, 3 and 4, 2023.
- 1.2 This project was performed by Devin S. Berman, California Certified Asbestos Consultant (CAC - 15-5418), California Department of Public Health (CDPH) Certified Lead Inspector/Assessor (I/A LRC 00002357) and Rodica Dullabaun, Master in Science (MS), CAC (11-4716), CDPH I/A (LRC 00009201). Assistance was provided by Anahi Rizo-Zhang, Industrial Hygienist in Training (IHIT) and Rene Medina, CDPH Lead Sampling Technician (LST LRC 00002314), Industrial Hygiene Field Technician (IHFT). Report preparation was performed by Devin S. Berman.
- 1.3 Project Management and report review was provided by Joel I. Berman, Certified Industrial Hygienist (CIH), Certified Safety Professional (CSP), CAC (92-0838), Certified Indoor Air Quality Manager (CIAQM), CDPH I/A (LRC 00003608) and Project Monitor (PM LRC 00003607), President.
- 1.4 The purpose of the survey is to perform interior asbestos bulk and XRF sampling of the interior and exterior of the building to determine if asbestos abatement is required prior to an upcoming demolition/renovation to the building and if lead coated components were present.

2.0 SITE DESCRIPTION

- 2.1 The subject building contains a four stories (three above grade and one lower level) with a roof penthouse, housing a library along with office spaces.
- 2.2 The building is constructed on a concrete slab foundation and it is a steel and concrete structure, without fireproofing. The exterior building materials include, but were not limited to, stucco and concrete block.
- 2.3 Interior building materials include gypsum and concrete walls and ceilings, carpet, ceramic tiles and vinyl floor tiles, and ceiling tile. The roofing system was shake rock along with penetration mastics. The year of construction was reported to be 1973.

3.0 METHODOLOGY

3.1 Asbestos

- 3.1.1 The collection of bulk samples from suspect ACMs was performed to determine if the materials were either ACM, defined by the Environmental Protection

Agency (EPA) as any building material containing greater than one percent (>1%) asbestos, or asbestos containing construction material (ACCM), defined by the State of California as any construction material containing greater than 0.1 percent (>0.1%) asbestos. In general, bulk sampling guidelines outlined in the Asbestos Hazard Emergency Response Act (AHERA) were followed, but actual sample locations and total number of samples were determined by the technician that conducted the survey.

- 3.1.2 The suspect asbestos samples were analyzed via polarized light microscopy (PLM) with dispersion staining in accordance with EPA method 600/R-93-116. The lower limit of reliable quantification for this method is 1%. When any trace level of asbestos was detected (often even one fiber) by the PLM analyst, the sample result were reported as “<1%” or trace, i.e. ACCM, along with an identification of the type of asbestos that was detected. Subsequently, where ACCM was reported, further analysis via PLM 1000 point counting was typically performed to quantify the asbestos levels down to 0.1%, the quantification limit where the material is considered non-asbestos containing for most regulatory purposes. Point count analysis was performed on representative samples that were determined to contain “Trace,” or less than 1%, amounts of asbestos. The majority of these samples were determined to be ACCM.

3.2 Lead

- 3.2.1 The lead survey included non-destructive testing with an X-Ray Fluorescence (XRF) lead paint analyzer to identify surfaces coated with lead-based paint (LBP) or lead-containing paint (LCP). In conjunction with the XRF sampling, limited collection of confirmation paint chip samples was performed for those materials considered inconclusive via the XRF. The lead survey was performed for the purpose of contractor notification for Cal/OSHA compliance, and may not fulfill all requirements under the Housing and Urban Development (HUD) guidelines and/or waste disposal regulations.

- 3.2.2 The XRF analyzer is a direct-read instrument that provides instant results for lead reported in milligrams per square centimeter (mg/cm²). HSA categorizes the readings as follows:

Greater than or equal to (\geq) 1.0 mg/cm² = Lead-Based Paint (LBP);
> 0.3 mg/cm² and less than (<) 1.0 mg/cm² = Lead-Containing Paint (LCP); and
>0.0 mg/cm² and \leq 0.3 mg/cm² = Possible lead containing coating - paint chip sample recommended.

- 3.2.3 When confirmation paint chip sampling was deemed appropriate, it was performed utilizing accepted professional methodologies and was analyzed using inductively coupled argon plasma, atomic emission spectroscopy (ICAP, AES) in accordance with EPA method 6010 or Flame Atomic Absorption (FAA)

spectrometry, in accordance with EPA method 3050B/7000B. Laboratory results indicating a concentration of 0.5 weight percent (WT%) lead is considered LBP. Confirmation paint chip samples were collected and analyzed for this survey.

- 3.2.4 It should be noted that the XRF analyzer is a direct-read instrument that is *not* capable of providing results for the purposes of waste characterization. Therefore, a waste profile should always be conducted prior to disposing of lead components. This is to comply with all local, State and Federal laws in regards to proper waste disposal.
- 3.2.5 It should be noted that for this XRF Survey, the sides of the building were identified clockwise starting from the address side; A, B, C, and D. Multiple components on the same wall side are differentiated with numbers (1, 2, 3, etc.), left to right when facing the components. Though a risk assessment was not performed, the inspector attempted to identify the condition of the tested painted surface(s) on the side tested. Intact condition is identified when entirely intact; Fair condition is when less than or equal (≤ 2) to square feet (interior) or ≤ 10 square feet (exterior) of normal wear and tear or direct damage to paint; and Poor condition is severely worn, weathered, no longer adhering (peeling, cracking, flaking, chalking) paint.

3.3 Laboratory

After sample collection, all samples were transported via chain-of-custody procedures to SGS Forensic Laboratories, in Carson, CA, laboratory for analysis. SGS Forensic Laboratories is part of a larger, nation-wide laboratory organization known as SGS. These laboratories maintain accreditations by the American Industrial Hygiene Association (AIHA), the National Voluntary Laboratory Accreditation Program (NVLAP), the California Department of Public Health Environmental Laboratory Accreditation Program (ELAP), and AIHA's Environmental Lead Laboratory Accreditation Program (ELLAP).

3.4 Exclusions/Limitations

- 3.4.1 This site and sampling investigation did not access hidden and unknown portions of the building or sample in areas where access was not granted by the Owner. The cement slab and the asphalt parking lot were not included in HSA's scope of work. Additionally, the glue/mastic used to attach the mirrors to the walls in the restrooms could not be tested without removing and potentially breaking the materials or were inaccessible on the day of the survey. These materials are assumed to be ACM until tested.
- 3.4.2 Additionally, the XRF found tile with lead concentrations greater than 9.9 mg/cm². In order to eliminate a potential lead hazard which could be produced by bulk sampling of the tile, waste sampling, including Total Threshold Limit

Concentration (TTLC), was not performed. Therefore, prior to any demolition, the contractor needs to perform this sampling, along with possible follow up sampling such as Toxicity Characteristic Leaching Procedure (TCLP) and Soluble Threshold Limit Concentration (STLC) to ensure proper disposal of waste.

- 3.4.3 HSA's scope of work did not include collection of samples for any other suspect hazardous materials (i.e. soil, ground water, etc.), which may or may not have been associated with the buildings, the site or normal facility operations.

4.0 STANDARDS AND GUIDELINES

4.1 Asbestos

- 4.1.1 Asbestos Containing Building Material (ACBM) - Any material containing more than one percent asbestos, as defined in AHERA, 40 CFR Part 763.
- 4.1.2 Asbestos Containing Material (ACM) - Any material containing more than one percent asbestos, as defined by the EPA.
- 4.1.3 Asbestos Containing Construction Material (ACCM) - Any manufactured construction material which contains more than one-tenth of one percent asbestos by weight, as defined by the State of California.
- 4.1.4 If the total amount of ACM or ACCM to be abated is equal to or greater than 100 s.f. the following regulations must be met.
 - 4.1.4.1 *South Coast Air Quality Management District (SCAQMD)*, Rule 1403, this rule requires District notification and removal of all ACM items (friable and non-friable) from a building prior to demolition. It requires the use of a state certified and a registered asbestos abatement contractor and a ten (10) day written notification. However, no notification is required if there is less than 100 square feet of ACM is to be disturbed, unless any amount of ACM is disturbed outside of a containment by renovation or demolition activities, then a notification and a Procedure 5 is required. SCAQMD does not regulate ACCM.
 - 4.1.4.2 *Labor Code 6501.5*, requires the use of a state certified and registered asbestos abatement contractor for all asbestos removal projects that are equal to or more than 100 square feet of ACCM or ACM.
- 4.1.5 *Federal Occupational Safety and Health Administration (OSHA) 29 CFR 1926.1101*, California Code of Regulation (CCR) Title 8 § 1529 and § 5208 require employers to monitor the exposure of their employees who may be exposed to asbestos. If employees are exposed above certain criteria, the

employer must take action to limit the employee's exposure to asbestos and to protect the employee's health. Per these regulations, the permissible exposure limit (PEL) for asbestos is 0.1 fibers per cubic centimeter of air (f/cc) expressed as an eight-hour time weighted average (TWA) and the Excursion Limit is 1.0 f/cc expressed over a 30 minute time period.

- 4.1.6 *Environmental Protection Agency (EPA) National Emission Standards for Hazardous Air Pollutants (NESHAP) 40 CFR Part 61, Subpart M* requires the inspection for ACMs prior to any planned renovation or demolition of a building. If ACM has been identified it specifies work practice standards designed to minimize the release of asbestos fibers, such as the use of wet methods during building demolition or renovation, sealing waste in leak tight containers, transportation and disposal of waste material as expediently as practicable. The regulation also requires the owner or the operator of the renovation or demolition operation to notify the appropriate delegated entity (often a state agency) before any demolition or before any renovations of buildings when the amount of Regulated Asbestos Containing Material (RACM) is greater than 260 linear feet, 160 square feet or 35 cubic feet.
- 4.1.7 *Environmental Protection Agency (EPA), Asbestos Hazard Emergency Response Act (AHERA) 40 CFR Part 763, Subpart E*, this rule requires all K-12, public and private non-profit elementary and secondary schools nationwide, to inspect their schools for asbestos-containing building materials (ACBM) and develop and maintain an up-to-date Asbestos Management Plan (AMP). The management of ACBM can be maintained on an "in-place" based principle and the removal of ACBM is not necessary unless it is severely damaged or may become disturbed during a planned demolition or renovation project. In the event ACBM is to be removed or the school building demolished, public and private school districts must comply with NESHAP. The AHERA rule also stipulates that any personnel working on asbestos activities in schools must be trained and accredited in accordance with the Asbestos Model Accreditation Plan.

4.2 Lead

- 4.2.1 On December 21, 2019, Federal EPA and HUD revised regulations related to lead contamination went into effect. This new standard defines "Lead Contaminated Dust" for floors as 10 micrograms per square foot ($\mu\text{g}/\text{ft}^2$) and window sills and troughs as 100 $\mu\text{g}/\text{ft}^2$. These two numbers are also used as a cleanliness standard for post lead response actions in residential housing. Since EPA and HUD do not have an outdoor horizontal surface regulation/guideline, as an interim guideline, we suggest using 400 $\mu\text{g}/\text{ft}^2$ which is the CDPH exterior horizontal surface level. These levels can be used as post clearance for response actions or cleanliness levels.

- 4.2.2 California Department of Public Health (CDPH), Title 17 defines:
- 4.2.2.1 “Lead Based Paint” (LBP) as paint or other surface coatings that contain an amount of lead equal to, or in excess of 1.0 mg/cm² or 0.5 percent weight (WT%);
 - 4.2.2.2 “Lead Contaminated Dust” is defined as dust that contains an amount of lead equal to, or in excess of, 10 µg/ft² for interior floor surfaces, 100 µg/ft² for interior horizontal surfaces, and 400 µg/ft² for exterior floor and horizontal surfaces.
 - 4.2.2.3 “Lead Contaminated Soil” is defined as bare soil that contains an amount of lead equal to, or in excess of, 400 parts per million (ppm) in children’s play areas and 1000 ppm in all other areas.
 - 4.2.2.4 “Lead Hazard” is defined as deteriorated LBP, lead contaminated dust, lead contaminated soil, disturbing LBP or presumed LBP without containment, or any other nuisance which may result in persistent and quantifiable lead exposure.
- 4.2.3 Consumer Product Safety Commission’s (CPSC) defines LCP as greater than 0.009 WT% or 90 ppm lead by weight, effective as of August 2009. In 1978 the CPSC banned lead in excess of 0.06 WT% or 600 ppm for paint used in residences or on toys.
- 4.2.4 Title 8 CCR 1532.1, the Cal/OSHA Lead in Construction Standard, establishes the requirements for worker protection. Elements covered by this standard include requirements associated with conducting trigger task activities (e.g. manual scraping, manual sanding), exposure monitoring, containments for lead-related tasks, training and certification, respiratory protection, medical surveillance, etc. Any trigger task performed on surfaces containing lead is covered by this regulation.
- 4.2.4.1 **Note:** In March 2023, Cal/OSHA proposed a revision to the Lead-in-Construction standard, which included various changes. The primary change was the reduction of the lead permissible exposure limit (PEL) from 50 micrograms per cubic meter (µg/m³) to 10 µg/m³ and the action level (AL) from 30 µg/m³ AL to 2 µg/m³. At the writing of this report., these reduced standards have not been approved. However, their likely approval is anticipated sometime during 2023.
- 4.2.5 Lead waste is regulated under *California Title 22, §66261.24*. The standard defines lead hazardous waste as greater than >1,000 milligrams per kilogram (mg/kg) of lead and/or lead compounds determined as a Total Threshold Limit

Concentration (TTLC) or 5.0 milligrams per liter (mg/l) determined as a Soluble Threshold Limit Concentration (STLC) or Waste Extraction Test (WET) method.

- 4.2.6 Federal EPA under the Resource Conservation and Recovery Act (RCRA) also mandates hazardous waste criteria for lead that is tested by the Toxicity Characteristic Leaching Procedure (TCLP). This method sets a limit for the quantity of lead that can be “soluble” or leach into the water. The EPA maximum toxicity characteristic for lead is equal to or greater than ≥ 5.0 mg/l.
- 4.2.7 SB 460 makes it illegal to create a lead hazard or to have a condition that is a lead hazard in residential and public buildings. Title 17 defines “lead hazard” as deteriorated LBP lead contaminated dust, lead contaminated soil, disturbing LBP or presumed LBP without containment, or any other nuisance which may result in persistent and quantifiable lead exposure.
- 4.2.8 SB 460 also provides the CDPH and local enforcement agencies (including local building, housing, health, and environmental health agencies) the authority to issue orders to abate or otherwise correct a lead hazard. Enforcement agencies can also issue orders to cease and desist any activities that create lead hazards (such as disturbing lead based paint without using containment and failing to follow other lead safe work practices). SB 460 applies to persons engaged in performing:
 - 4.2.8.1 Remodeling and renovation work,
 - 4.2.8.2 Abatement of lead hazards, and
 - 4.2.8.3 Inspections and assessments of lead hazards.
- 4.3 Los Angeles County Code, Title 11, Health and Safety Chapter 11.28 defines “Dangerous levels of lead-bearing substances” as any paint, varnish, lacquer, putty, plaster, or similar coating or structural material which contains lead or its compounds in excess of 0.7 mg/cm^2 , when measured by a lead-detecting instrument approved by the director; or any substance, when measured by any scientifically accepted method, in a quantity determined by the director to constitute a hazard to children; or that level as determined in the most recent standards as established by the U. S. Department of Health, Education and Welfare, Public Health Service, Center for Disease Control.
- 4.4 Other Regulations and Guidelines

California Title 8, CCR §5194, Hazard Communication Standard, requires employers to notify their employees of hazardous materials in their workplace.

5.0 RESULTS

5.1 The laboratory reports with chain-of-custody documentation are provided in Appendix A, figures are provided in Appendix B, a photo exhibit is in Appendix C, Licenses are located in Appendix D, and notifications are provided in Appendix E.

5.2 Bulk Asbestos Sample Results

5.2.1 The results, descriptions, estimated quantities and analytical results for asbestos bulk samples are presented in Table IA. HSA collected 167 suspect bulk asbestos samples totaling in 414 analyses, by layer. Of these, 40 samples were determined to be ACM and 48 samples were determined to be ACCM per the PLM method. 18 of the ACCM samples were further analyzed by the Point Count method and the majority of these items were confirmed to be ACCM.

5.2.2 Listed on Table IB are the materials that were determined to be ACM and/or ACCM per laboratory analysis, or assumed to be ACM/ACCM where bulk sampling was not possible. The samples identified as ACM are in bold and shaded. The samples identified as ACCM are in bold.

5.2.2.1 ***Note:** all suspect bulk asbestos samples collected are representative of the materials found in each location. Therefore, materials similar in color, texture and appearance as those identified as ACM located within the sampled areas are to be considered asbestos until tested

5.3 Lead Sample Results

5.3.1 Results for the lead XRF survey are presented in Table IIA. A total of 402 measurements were taken using a Niton XRF Analyzer including pre and post calibration measurements for quality control. Of these, 57 XRF measurements were identified as LBP in accordance with the requirements of HUD and the CDPH, and 10 XRF measurements were determined to be LCP. In addition, four paint chip samples were collected and confirmed to be LCP. The paint chip sample results are reported on Table III.

5.3.2 Listed on Table IIB are the XRF measurements determined to be LBP and/or LCP. XRF measurements determined to be LBP are in bold print and shaded. XRF measurements determined to be LCP are in bold print.

5.3.3 The lead survey was performed for the purpose of contractor notification for Cal/OSHA compliance, and may not fulfill all requirements under the Housing and Urban Development (HUD) guidelines and/or waste disposal regulations.

6.0 RECOMMENDATIONS

- 6.1 ACM/ACCM and LBP/LCP were identified the materials sampled at the Inglewood Library located at 101 Manchester Blvd., Inglewood, CA .
- 6.2 The assumed ACM/ACBMs, such as the mirror mastic, should either be sampled prior to any disturbance or treated as ACM/ACBM during the demolition activities and for waste purposes.
- 6.3 Finally, the high ceiling area in the northeast corner of the building was in-accessible for bulk asbestos sampling of the ceiling or XRF sampling of the mural due to the inability for a lift to access the area. For this area to be impacted, a scaffold will need to be erected. When this occurs, HSA recommends that prior to any impact of the high ceiling material (which appears to be fiberglass), bulk asbestos samples shall be collected to determine the asbestos content, if any, of this material. The mural should also be tested via XRF sampling to determine whether there is any lead in the mural paint.
- 6.4 While ACM/ACCM and LBP/LCP were identified in the materials sampled at the Inglewood Library located at 101 Manchester Blvd., Inglewood, CA, the results are considered to be normal for a building of this age. Additionally, the materials (ACMs/ACCMs and LBPs/LCPs) present in the building were observed to be in good condition at the time of HSA's survey.
- 6.5 It is HSA's understanding that the property will undergo maintenance/renovation and/or demolition work that may require asbestos and/or lead abatement or impact at some future date. All contractors performing asbestos and/or lead related work at this location must perform their work pursuant to appropriate Asbestos and/or Lead specifications. The project should be monitored under the direction of a Certified Industrial Hygienist (CIH), who is also a State of California Certified Asbestos Consultant (CAC) and Certified Lead Project Designer
- 6.6 In California, a contractor must be registered as an asbestos abatement contractor for removal or any impact work involving 100 s.f. or more of ACM/ACCM. Special training is also required for any other type of ACM/ACCM maintenance or impact work.
- 6.7 Materials to be disposed of that contain <1% but more than 0.1% asbestos is not considered hazardous waste and may be disposed of as asbestos containing construction debris. However, the landfill must be notified that the waste contains asbestos due to potential permitting issues.
- 6.8 Lead waste should be segregated and a waste profile should be conducted on porcelain sinks and toilets, ceramic tile, paint chips, and other wastes possibly contaminated with or containing lead to comply with all local, State and Federal laws.

- 6.9 Care should be taken when performing any activities (e.g. manually dry sanding or scraping surfaces) to prepare any of the component(s) either determined to be coated with or which are suspected of containing lead for repainting.
- 6.10 Due to the nature, age, and use of the structure, hidden or unknown suspect ACM/ACCM, lead or other hazardous materials may be uncovered during renovation/maintenance activities. Therefore, all contractors working on the project should be informed of policies with regard to notifying management if previously unidentified suspect hazardous materials are discovered during the project.
- 6.11 This report was prepared for use by Griffin Structures in evaluating the subject site. The information contained within this report is as factual as possible and the opinions related herein are based on HSA's experience in similar investigations. Therefore, no warranty is made to any persons other than Griffin Structures regarding the conclusions or recommendations included within this report. HSA will not release copies to a third party without prior written consent of Griffin Structures. Please contact HSA at hsa@healthscience.com for any questions or concerns about the contents of this report.



TABLE IA - BULK ASBESTOS SAMPLING RESULTS

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
Loading Dock						
L-230803-01A	Drywall/Mud/Tape	Loading Dock	West hallway across from Teen Center	White Drywall - ND White Joint Compound - ND Paint - ND White Joint Compound - ND Paint - ND White Joint Compound - ND Paint - ND	Good	10,000 sq. ft.
L-230803-01B		Janitor's Closet	Southeast corner	White Drywall - ND Off-White Joint Compound - Chrysotile 2 % Drywall Tape - ND Off-White Joint Compound - Chrysotile 2 % Paint - ND		
L-230803-01C		Old Break Room	West wall behind refrigerator	White Drywall - ND Off-White Joint Compound - Chrysotile 2 % Drywall Tape - ND Off-White Joint Compound - Chrysotile 2 % Paint - ND Brown Mastic - Anthophyllite Trace Tan Mastic - ND		
L-230803-02A	Carpet Mastic	Teen Center	Center of room, under pool table	Light Brown Mastic - Chrysotile 2%	Good	5,000 sq. ft.
L-230803-02B		Depository	Center of room	Light Brown Mastic - Chrysotile 2%		



TABLE IA - BULK SAMPLING RESULTS- Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
L-230803-02C		Technical Services	North end of area	Light Brown Mastic - Chrysotile 2%		
L-230803-02D	Carpet Mastic	Technical Services	West end between cabinets	Light Brown Mastic - Chrysotile 2%	Good	5,000 sq. ft.
L-230803-02E		Hallway	North end in front of lockers at restrooms	Light Brown Mastic - Chrysotile 2%		
L-230803-03A	12" x 12" Blue Vinyl Floor Tile/Mastic	Old Break Room	At southwest corner	Blue Tile - ND Tan Mastic - ND Brown Mastic - Chrysotile 2 %	Good	1000 sq. ft.
L-230803-03B			At west wall behind refrigerator	Blue Tile - ND Tan Mastic - ND Brown Mastic - Chrysotile 2 %		
L-230803-03C			At northeast corner	Blue Tile - ND Tan Mastic - ND Brown Mastic - Chrysotile 2 %		
L-230803-04A	4" Brown Vinyl Base Cove/Mastic	North Hallway	Across from Teen Center	Brown Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace Paint - ND Off-White Non-Fibrous Material - ND	Good	1000 LF
L-230803-04B			Across from Old Break Room	Brown Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace		



TABLE IA - BULK SAMPLING RESULTS- Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
L-230803-04C			North of Elevators	Brown Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace Paint - ND Off-White Non-Fibrous Material - Chrysotile 2%		
L-230803-05A	4" Black Vinyl Base Cove/Mastic	Depository	Northwest corner	Black Non-Fibrous Material - ND Brown Mastic - Anthophyllite Trace Grey Non-Fibrous Material - ND	Good	1000 LF
L-230803-05B			South wall at door to stairs	Black Non-Fibrous Material - ND Brown Mastic - Anthophyllite Trace Paint - ND Off-White Joint Compound - Chrysotile 2 %		
L-230803-05C			West wall	Black Non-Fibrous Material - ND Brown Mastic - Anthophyllite Trace		
L-230804-06A	24" x 24" Ceiling Tile	Old Break Room	Northeast corner	Beige Fibrous Material - ND Paint - ND	Good	1000 sq. ft.
L-230804-06B			Center of room	Beige Fibrous Material - ND Paint - ND		
L-230804-06C			Southwest corner	Beige Fibrous Material - ND Paint - ND		



TABLE IA - BULK SAMPLING RESULTS- Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
L-230803-07A	4" Grey Vinyl Base Cove/Mastic	Tech Center	Southwest wall at door	Grey Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace Paint - ND Off-White Joint Compound - Chrysotile 2 %	Good	1000 LF
L-230803-07B	4" Grey Vinyl Base Cove/Mastic	Tech Center	Northwest area at door	Grey Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace Paint - ND Off-White Joint Compound - Chrysotile 2 % Drywall Tape - ND Off-White Joint Compound - Chrysotile 2 %	Good	1000 LF
L-230803-07C			East wall near southeast area	Grey Non-Fibrous Material - ND Tan Mastic - ND Paint - ND Off-White Joint Compound - ND		
L-230803-08A	Concealed Spline Ceiling Tile	Teen Center	West wall	Beige Fibrous Material - ND Paint - ND	Good	1000 sq. ft.
L-230803-08B		Depository	Center of Building	Beige Fibrous Material - ND Paint - ND		



TABLE IA - BULK SAMPLING RESULTS- Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
L-230803-09A	4" Blue Vinyl Base Cove/Mastic	Old Break Room	Southwest corner	Dark Blue Non-Fibrous Mat'l - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace Paint - ND	Good	1000 sq. ft.
L-230803-09B			West wall behind refrigerator	Dark Blue Non-Fibrous Mat'l - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace Paint - ND		
L-230803-09C	4" Blue Vinyl Base Cove/Mastic	Old Break Room	Northeast corner	Dark Blue Non-Fibrous Mat'l - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace Paint - ND	Good	1000 sq. ft.
L-230803-10A	6" Black Vinyl Base Cove/Mastic	Teen Center	Northeast corner behind door	Black Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace Paint - ND	Good	1000 LF
L-230803-10B			West wall be hind couch	Black Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace Paint - ND		



TABLE IA - BULK SAMPLING RESULTS- Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
L-230803-10C			South wall behind Entertainment Center	Black Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace Paint - ND Grey Cementitious Material - ND		
L-230803-11A	Black Mortar	Depository	South wall near exit door	Grey Mortar - ND Paint - ND	Good	1000 sq. ft.
L-230803-11B		Old Break Room	Northwest wall in corner behind door	Grey Mortar - ND Paint - ND		
L-230803-11C		North Hallway	Near loading back door	Grey Mortar - ND Paint - ND		



TABLE IA - BULK SAMPLING RESULTS- Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
First Floor						
1-230802-01A	Drywall/Mud/Tape	Front of Young Adult Area	At west wall	White Drywall - ND Off-White Joint Compound - Chrysotile 2 % Paint - ND Brown Mastic - Anthophyllite Trace Tan Mastic - ND Grey Cementitious Material - ND Paint - ND	Good	10,000 sq. ft.
1-230802-01B		Main Library	West wall behind west stairs	White Drywall - ND Off-White Joint Compound - Chrysotile 2 % Off-White Non-Fibrous Material - ND Paint - ND Brown Mastic - Anthophyllite Trace Tan Mastic - ND		
1-230802-01C		Imagination Place (Kid's Area)	At door to staff Offices	White Drywall - ND Off-White Joint Compound - Chrysotile 2 % Paint - ND Brown Mastic - Anthophyllite Trace Tan Mastic - ND		
1-230802-02A	Carpet Mastic	Front of Young Adult Office	Southwest corner	Tan Mastic/Debris - Chrysotile 2 %	Good	50,000 sq. ft.
1-230802-02B		Main Library	Northeast corner	Tan Mastic/Debris - Chrysotile 2 %		
1-230802-02C			North end of floor	Tan Mastic/Debris - Chrysotile 2 %		



TABLE IA - BULK SAMPLING RESULTS- Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
1-230802-02D			Southeast corner	Tan Fibrous Material - ND Tan Mastic/Debris - Chrysotile Trace		
1-230802-02E	Carpet Mastic	Main Library	Center of south wall	Tan Mastic/Debris - Chrysotile Trace	Good	50,000 sq. ft.
1-230802-02F		Children's Area	Northwest corner	Tan Mastic/Debris - Chrysotile 2%		
1-230802-02G			Southeast corner	Tan Mastic/Debris - Chrysotile 2 %		
1-230802-03A	Tread Material	West Stairwell	Public	Brown Non-Fibrous Material - ND Clear Mastic - ND Black Non-Fibrous Material - ND	Good	1000 sq. ft.
1-230802-03B		East Stairwell	Public	Brown Non-Fibrous Material - ND Clear Mastic - ND Black Non-Fibrous Material - ND		
1-230802-04A	4" Brown Base Cove/Mastic	Lobby Office	Southwest corner	Brown Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace Paint - ND Off-White Joint Compound - Chrysotile 2 %	Good	1000 LF
1-230802-04B			Under reception counter on north side	Brown Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace		
1-230802-04C		Lobby	Southwest corner	Brown Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace		



TABLE IA - BULK SAMPLING RESULTS- Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
230802-05A	4" Black Base Cove/Mastic	Main Library	At west wall in front of Young Adult Area - office	Black Non-Fibrous Material/Paint - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace Off-White Joint Compound - Chrysotile 2 %	Good	1000 LF
1-230802-05B			Behind stairs on east wall	Black Non-Fibrous Material/Paint - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace Off-White Joint Compound - Chrysotile 2 %		
1-230802-05C			At north wall	Black Non-Fibrous Material/Paint - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace		
1-230802-06A	Black Rubber Flooring/Mastic	Lobby	At center under air purifier	Black Flooring - ND Tan Mastic - ND Paint - ND Off-White Non-Fibrous Material - ND	Good	1000 sq. ft.
1-230802-06B		Lobby Office	North side under reception counter	Black Flooring - ND Tan Mastic - ND		
1-230802-06C		Elevator Hallway	West wall - west of Lobby Office	Black Flooring - ND Tan Mastic - ND Brown Mastic/Debris - Chrysotile 2 %		
1-230802-07A	Light Grey Rubber Flooring/Mastic	Lobby	Northeast area under security desk	Brown Flooring - ND Tan Mastic - ND Grey Non-Fibrous Material - ND	Good	1000 sq. ft.



TABLE IA - BULK SAMPLING RESULTS- Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
1-230802-07B			Southeast corner	Brown Flooring - ND Tan Mastic - ND		
1-230802-07C	Light Grey Rubber Flooring/Mastic	Lobby Office	Southwest corner	Brown Flooring - ND Tan Mastic - ND	Good	1000 sq. ft.
1-230804-08A	Concealed Spline Ceiling Tile	Children's Area	West of Children's Theater	Beige Fibrous Material - ND Paint - ND	Good	5000 sq. ft.
1-230804-08B		Main Lobby	Southwest corner	Beige Fibrous Material - ND Paint - ND		
1-230802-09A	White Rubber Flooring/Mastic	Lobby Office	Under desk at south wall	Grey Flooring - ND Tan Mastic - ND Off-White Non-Fibrous Material - ND	Good	1000 sq. ft.
1-230802-09B			Below reception counter at north wall	Grey Flooring - ND Tan Mastic - ND		
1-230802-09C			At southeast area	Grey Flooring - ND Tan Mastic - ND Off-White Non-Fibrous Material - ND		
1-230802-10A	4" Blue Vinyl Base Cove/Mastic	Imagination Place (Kid's Area)	At door to staff office	Dark Blue Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace Paint - ND Off-White Joint Compound - Chrysotile 2 %	Good	1000 LF



TABLE IA - BULK SAMPLING RESULTS- Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
1-230802-10B		Children's Service Area	Northwest corner	Dark Blue Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace Paint - ND		
1-230802-10C	4" Blue Vinyl Base Cove/Mastic	Children's Service Area	Southeast corner	Dark Blue Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace	Good	1000 LF
1-230802-11A	6" Black Vinyl Base Cove/Mastic	Entry	Northwest side	Black Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace	Good	30 LF
1-230802-11B			Southwest side	Black Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace		
1-230802-12A	12" x 12" Black Vinyl Flooring/Mastic	Children's Area	In front of restrooms	Black Non-Fibrous Material - ND Clear Mastic - ND	Good	80 LF
1-230802-12B			In front of restrooms	Black Non-Fibrous Material - ND Clear Mastic - ND		
1-230802-12C			In front of restrooms	Black Non-Fibrous Material - ND Clear Mastic - ND		
1-230802-13A	Bakelite	Children's Theater (Electrical/Server Room)	Not Sampled	Assumed ACM	Good	7 total



TABLE IA - BULK SAMPLING RESULTS- Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
1-230804-14A	24" x 24" Ceiling Tile	Children’s Theater	Northeast corner	Beige Fibrous Material - ND Paint - ND	Good	1000 sq. ft.
1-230804-14B			Southeast corner	Beige Fibrous Material - ND Paint - ND		
1-230804-14C			Center	Beige Fibrous Material - ND Paint - ND		
Second Floor						
2-230803-01A	Drywall/Mud/Tape	Main Library	At east stairwell	White Drywall - ND White Joint Compound - Chrysotile 2 % Drywall Tape - ND White Joint Compound - Chrysotile 2 % Paint - ND	Good	10,000 sq. ft.
2-230803-01B		Corridor to Restrooms	Southeast corner	White Drywall - ND White Joint Compound - Chrysotile 2 % Drywall Tape - ND White Joint Compound - Chrysotile 2 % Off-White Woven Material - ND Brown Mastic - Anthophyllite Trace		



TABLE IA - BULK SAMPLING RESULTS- Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
2-230803-01C		Main Library	Outside of Room 4 at north of door	White Drywall - ND White Joint Compound - Chrysotile 2 % Drywall Tape - ND White Joint Compound - Chrysotile 2 % Off-White Woven Material - ND Brown Mastic - Anthophyllite Trace		
2-230803-02A	Carpet Mastic	Main Library	Northeast corner	Brown Mastic/Debris - Chrysotile Trace Point Count - 0.06% Chrysotile	Good	75,000 sq. ft.
2-230803-02B			Southeast corner	Brown Mastic/Debris - Chrysotile Trace Point Count - 0.20% Chrysotile		
2-230803-02C			At south end	Brown Mastic/Debris - Chrysotile Trace Point Count - 0.13% Chrysotile		
2-230803-02D	Carpet Mastic	Main Library	Southwest corner	Tan Mastic - ND Off-White Non-Fibrous Material - ND Brown Mastic/Debris - Chrysotile Trace Point Count - 0.13% Chrysotile	Good	75,000 sq. ft.
2-230803-02E			Central area	Brown Mastic/Debris - Chrysotile Trace Point Count - 0.15% Chrysotile		
2-230803-02F		Main Library Staff Offices	Northwest corner	Brown Mastic/Debris - Chrysotile Trace Point Count - 0.14% Chrysotile		



TABLE IA - BULK SAMPLING RESULTS- Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
2-230803-02G			At north end	Tan Mastic - ND Off-White Non-Fibrous Material - ND Brown Mastic/Debris - Chrysotile Trace Point Count - 0.16% Chrysotile		
2-230803-03A	Tread Material	Stairwells	West stairwell	Dark Brown Non-Fibrous Material - ND Tan Mastic/Debris - ND	Good	1000 sq. ft.
2-230803-03B			East stairwell	Dark Brown Non-Fibrous Material - ND		
2-230803-04A	Black Vinyl Base Cove/Mastic	Stairwells	At east stairwell	Black Non-Fibrous Material - ND Beige Mastic - ND Brown Mastic - Anthophyllite Trace Off-White Joint Compound - Chrysotile 2 %	Good	1000 LF
2-230803-04B		Corridor to Restrooms	Southeast corner	Black Non-Fibrous Material - ND Beige Mastic - ND Brown Mastic - Anthophyllite Trace		
2-230803-04C		Main Library	Outside Room 4 at north of door	Black Non-Fibrous Material - ND Beige Mastic - ND Brown Mastic - Anthophyllite Trace		
2-230803-05A	12" x 12" Black Vinyl Sheet Flooring/Mastic	Drinking Fountain	At front of fountain	Black Flooring - ND	Good	16 sq. ft.
2-230803-05B			At front of fountain	Black Flooring - ND		
2-230803-05C			At front of fountain	Black Flooring - ND Tan Mastic - ND Off-White Non-Fibrous Material - ND		



TABLE IA - BULK SAMPLING RESULTS- Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
2-230803-06A	Concealed Spline Ceiling Tile	Administration Area	Northeast corner	Grey Fibrous Material - ND Paint - ND	Good	3000 sq. ft.
2-230803-06B			At center of south wall	Grey Fibrous Material - ND Paint - ND		
Third Floor						
3-230802-01A	Drywall/Mud/Tape	Administration Office	At wall base near door near Conference Room 34 at Entrance	White Drywall - ND Off-White Joint Compound - Chrysotile 2 % Drywall Tape - ND Off-White Joint Compound - Chrysotile 2 % Paint - ND Brown Mastic - Anthophyllite Trace	Good	10,000 sq. ft.
3-230802-01B		Main Library Area	At west stairwell	White Drywall - ND Off-White Joint Compound - Chrysotile 2 % Paint - ND Brown Mastic - Anthophyllite Trace		
3-230802-01C			Behind east stairwell	White Drywall - ND Paint - ND Brown Mastic - Anthophyllite Trace		



TABLE IA - BULK SAMPLING RESULTS- Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
3-230802-02A	Carpet Glue	Main Library	Southwest area	Tan Mastics/Debris - Chrysotile Trace Point Count - 0.16% Chrysotile	Good	20,000 sq. ft.
3-230802-02B			South end	Tan Mastics/Debris - Chrysotile Trace Point Count - 0.05% Chrysotile		
3-230802-02C			Southeast corner	Tan Mastics/Debris - Chrysotile Trace Point Count - 0.26% Chrysotile		
3-230802-02D			Central area	Tan Mastics/Debris - Chrysotile Trace White Non-Fibrous Material - ND Point Count - 0.11% Chrysotile		
3-230802-02E			Northeast corner	Tan Mastics/Debris - Chrysotile Trace Point Count - 0.26% Chrysotile		
3-230802-02F		North Office Area	North end of floor	Tan Mastics/Debris - Chrysotile Trace White Non-Fibrous Material - ND Point Count - 0.24% Chrysotile		
3-230802-02G		Conference Room	Northeast corner	Tan Mastics/Debris - Chrysotile Trace Point Count - 0.15% Chrysotile		



TABLE IA - BULK SAMPLING RESULTS- Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
3-230802-03A	Stair Tread	Stairwells	East stairwell	Brown Non-Fibrous Material - ND Tan Non-Fibrous Material - ND Tan Mastic - Chrysotile Trace	Good	1000 sq. ft.
3-230802-03B			West stairwell	Black Non-Fibrous Material/Stones - ND Yellow Mastic - ND Brown Non-Fibrous Material - ND Beige Mastic - ND Tan Non-Fibrous Material - ND Tan Mastic - Chrysotile Trace Grey Non-Fibrous Material - ND		
3-230802-04A	Blue Vinyl Base Cove/Mastic	Main Library	At east stairs	Blue Non-Fibrous Material - ND Beige Mastic - ND Brown Mastic - Anthophyllite Trace Off-White Joint Compound - Chrysotile Trace	Good	1000 LF
3-230802-04B			Northeast corner	Blue Non-Fibrous Material - ND Beige Mastic - ND Brown Mastic - Anthophyllite Trace Off-White Joint Compound - Chrysotile Trace		
3-230802-04C			At north wall west of Conference Room 3A	Blue Non-Fibrous Material - ND Beige Mastic - ND Brown Mastic - Anthophyllite Trace Off-White Joint Compound - Chrysotile Trace		



TABLE IA - BULK SAMPLING RESULTS- Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
3-230802-05A	12" x 12" Black Vinyl Sheet Flooring/Mastic	Drinking Fountain	In front of fountain	Black Tile - ND Yellow Mastic - ND Tan Mastic - Chrysotile Trace	Good	32 sq. ft.
3-230802-05B			In front of fountain	Black Tile - ND Yellow Mastic - ND Tan Mastic - Chrysotile Trace		
3-230802-05C			In front of fountain	Black Tile - ND Yellow Mastic - ND Tan Mastic - Chrysotile Trace		
3-230802-05D			At elevator	Black Tile - ND Yellow Mastic/Debris - ND		
3-230804-06A	24" x 24" Ceiling Tile	Conference Room	Southeast corner	Beige Fibrous Material - ND Paint - ND	Good	1000 sq. ft.
3-230804-06B			At center of north side	Beige Fibrous Material - ND Paint - ND		
3-230804-06C			Southwest corner	Beige Fibrous Material - ND Paint - ND		
3-230804-07A	24" x 24" Ceiling Tile	Administration Area	Southwest corner	Beige Fibrous Material - ND Paint - ND	Good	1000 sq. ft.
3-230804-07B			At center of north side	Beige Fibrous Material - ND Paint - ND		



TABLE IA - BULK SAMPLING RESULTS- Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
3-230804-07C			West side	Beige Fibrous Material - ND Paint - ND		
3-230804-08A	Concealed Spline Ceiling	Main Library	At east side	Beige Fibrous Material - ND Paint - ND	Good	5000 sq. ft.
3-230804-08B			Southeast corner	Beige Fibrous Material - ND Paint - ND		
Penthouse						
P-230803-01A	Drywall/Tape/Mud	General Room/South Room	At northwest corner	Brown Drywall - ND Off-White Joint Compound - Chrysotile Trace Point Count - 0.59% Chrysotile	Good	1000 sq. ft.
P-230803-01B			At north side of east wall	Brown Drywall - ND Off-White Joint Compound - Chrysotile Trace Point Count - 0.91% Chrysotile		
P-230803-01C			At south side of east wall	Brown Drywall - ND Off-White Joint Compound - Chrysotile Trace Point Count - 0.50% Chrysotile		
P-230803-02A	Debris	Penthouse	Debris pile	Beige Cementitious Material - ND Brown Fibrous Mat'l/Debris - ND	Good	50 sq. ft.
P-230803-02B			Debris pile	Beige Cementitious Material - ND Brown Fibrous Mat'l/Debris - ND		



TABLE IA - BULK SAMPLING RESULTS- Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
P-230803-02C			Debris pile	Brown Drywall - ND Off-White Joint Compound - Chrysotile Trace Point Count - 0.54% Chrysotile Beige Cementitious Material - ND Brown Fibrous Mat'l/Debris ND		
P-230803-03A	Thermal Systems Insulation (TSI) Wrap	Penthouse	At center of room	Yellow Fibrous Material - ND White Woven Material/Foil - ND White Fibrous Material/Adhesive - ND Tan Fibrous Material - ND	Good	300 LF
P-230803-03B			At center of room	Yellow Fibrous Material - ND White Woven Material/Foil - ND White Fibrous Material/Adhesive - ND		
P-230803-03C			At center of room	White Woven Material/Foil - ND Tan Fibrous Material/Adhesive - ND White Non-Fibrous Material - ND		
P-230803-04A	TSI Hard Pack Coring	Penthouse	At center of room	Yellow Fibrous Material - ND White Woven Material/Foil - ND Tan Fibrous Material/Adhesive - ND White Non-Fibrous Material - ND	Good	30 LF
P-230803-04B			At center of room	Yellow Fibrous Material - ND White Woven Material/Foil - ND Tan Fibrous Material/Adhesive - ND White Non-Fibrous Material - ND		



TABLE IA - BULK SAMPLING RESULTS- Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
P-230803-04C			At center of room	Yellow Fibrous Material - ND White Woven Material/Foil - ND Tan Fibrous Material/Adhesive - ND White Non-Fibrous Material - ND		
P-230803-05A	Vibration Damping Cloth	Penthouse	At north area	White Woven Material - ND Black Non-Fibrous Material - ND	Good	3-4 total
P-230803-05B			At west area	White Woven Material - ND Black Non-Fibrous Material - ND		
P-230803-05C	Vibration Damping Cloth	Penthouse	At south area	White Woven Material - ND Black Non-Fibrous Material - ND	Good	3-4 total



TABLE IA - BULK SAMPLING RESULTS- Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
Building Exterior and Roof						
M-230803-01A	Brown Rubber Flooring/Mastic	Staff Elevator Car	Northeast corner	Brown Flooring - ND Off-White Woven Material - ND Clear/Tan Mastic - ND Grey Non-Fibrous Material - ND Brown Mastic - Chrysotile 2 %	Good	30 sq. ft.
M-230803-01B			Southeast corner	Brown Flooring - ND Off-White Woven Material - ND Clear/Tan Mastic - ND Grey Non-Fibrous Material - ND Brown Mastic - Chrysotile 2 %		
M-230803-01C			Southwest corner	Brown Flooring - ND Off-White Woven Material - ND Clear/Tan Mastic - ND Grey Non-Fibrous Material - ND Brown Mastic - Chrysotile 2 %		
M-230803-02A	Concrete Brick Mortar	Exterior	Southwest corner	Dark Grey Mortar - ND	Good	5000 sq. ft.
M-230803-02B			At south exit door	Grey Cementitious Material - ND Dark Grey Mortar - ND Paint - ND		
M-230803-02C			Southeast corner	Dark Grey Mortar - ND		
M-230803-02D			Northeast corner	Dark Grey Mortar - ND		



TABLE IA - BULK SAMPLING RESULTS- Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
M-230803-02E			At north double door exit	Dark Grey Mortar - ND		
M-230803-03A	Stucco	Loading Dock	Behind door in stairwell	Grey Cementitious Material - ND Light Grey Cementitious Material -ND	Good	3000 sq. ft.
M-230803-03B		1 st Floor Landing	East wall of north stairwell (staff)	Grey Cementitious Material - ND Light Grey Cementitious Material -ND		
M-230803-03C		3 rd Floor Landing	At base of east wall of north stairwell (staff)	Grey Cementitious Material - ND Light Grey Cementitious Material -ND		
M-230803-03D		2 nd Floor	At door to staff offices	Light Grey Cementitious Material -ND		
M-230803-03E		Exterior - Between 1 st and 2 nd Floor	At base of landing wall	Grey Cementitious Material - ND Light Grey Cementitious Material -ND		
M-230803-04A	Mastic	Restrooms	Behind mirrors throughout building - not sampled	Assumed ACM	Good	12 total
M-230803-05A	Walking Pads	Lower Roof	Northeast corner	Stones - ND Black Tar - ND Black Felt - ND	Good	1000 sq. ft.
M-230803-05B			Northwest corner	Stones - ND Black Tar - ND Black Felt - ND		
M-230803-05C			Southwest corner	Stones - ND Black Tar - ND Black Felt - ND		



TABLE IA - BULK SAMPLING RESULTS- Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
M-230803-06A	Roofing Core	Lower Roof	Southeast corner	Off-White Non-Fibrous Material - ND Tan Mastics - ND Off-White Woven Material - ND Black Tars - ND Black Felts - ND Beige Semi-Fibrous Material - ND	Good	5000 sq. ft.
M-230803-06B			Center at south wall	Off-White Non-Fibrous Material - ND Tan Mastics - ND Off-White Woven Material - ND Black Tars - ND Black Felts - ND Beige Semi-Fibrous Material - ND		
M-230803-06C			Southwest corner	Off-White Non-Fibrous Material - ND Tan Mastics - ND Off-White Woven Material - ND Black Tars - ND Black Felts - ND Beige Semi-Fibrous Material - ND		
M-230803-06D			Northwest corner	Off-White Non-Fibrous Material - ND Tan Mastics - ND Off-White Woven Material - ND Black Tars - ND Black Felts - ND Beige Semi-Fibrous Material - ND		



TABLE IA - BULK SAMPLING RESULTS- Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
M-230803-06E	Roofing Core	Lower Roof	Northeast corner	Off-White Non-Fibrous Material - ND Tan Mastics - ND Off-White Woven Material - ND Black Tars - ND Black Felts - ND Beige Semi-Fibrous Material - ND	Good	5000 sq. ft.
M-230803-06F			West side	Off-White Non-Fibrous Material - ND Tan Mastics - ND Off-White Woven Material - ND Black Tars - ND Black Felts - ND Beige Semi-Fibrous Material - ND		
M-230803-06G			East side	Off-White Non-Fibrous Material - ND Tan Mastics - ND Off-White Woven Material - ND Black Tars - ND Black Felts - ND Beige Semi-Fibrous Material - ND		
M-230803-07A	Penetration Mastic	Lower Roof	At eye hole in southwest corner	Off-White Non-Fibrous Material - ND	Good	1000 sq. ft.
M-230803-07B			At spout drain in north side	Off-White Non-Fibrous Material - ND Black Semi-Fibrous Tar - ND		
M-230803-07C			Northwest corner of Penthouse base	Off-White Non-Fibrous Material - ND		



TABLE IA - BULK SAMPLING RESULTS- Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
M-230803-08A	Carpet Mastic	Stairs at Loading Dock to 1 st Floor	Under red carpet	Red Carpet - ND Beige Fibrous Material - ND Brown Mastic - Chrysotile 2 %	Good	1000 sq. ft.
M-230803-08B			Under red carpet	Red Carpet - ND Beige Fibrous Material - ND Brown Mastic - Chrysotile 2 %		
M-230803-08C			Under red carpet	Red Carpet - ND Beige Fibrous Material - ND Tan Mastic - ND		
Standards/Guidelines:						
EPA - ACM						>1.0
State of California - ACCM						>0.1
Analytical Method: EPA 600/R-93/116 - Polarized Light Microscopy (PLM)						
Abbreviations: ND = none detected; < = less than; % - percent; EPA = Environmental Protection Agency; ACM = Asbestos Containing Material; ACCM = Asbestos Containing Construction Material; LF = linear feet; ft ² = square feet; bold/shade = ACM; bold print only = ACCM						
Disclaimer: HSA’s measurements and component identifications are approximations and must be confirmed by contractors bidding the project. In addition, hidden or unknown suspect asbestos containing materials (ACM)/asbestos containing construction materials (ACCM) or lead containing/coated materials may be uncovered during the project. Multiple layers of building materials exist, abatement includes all layers of both ACMs and non-ACMs including all residue. Similar materials in color, texture and appearance as those identified in HSA’s report should be considered asbestos until sampled. All contractors working on the project should notify the Owner regarding the discovery of unidentified hazardous materials. All work to be performed in accordance with all state, local and federal regulations.						



TABLE IB - ACM/ACCM ASBESTOS SAMPLING RESULTS

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
Loading Dock						
L-230803-01B		Janitor's Closet	Southeast corner	White Drywall - ND Off-White Joint Compound - Chrysotile 2 % Drywall Tape - ND Off-White Joint Compound - Chrysotile 2 % Paint - ND		
L-230803-01C		Old Break Room	West wall behind refrigerator	White Drywall - ND Off-White Joint Compound - Chrysotile 2 % Drywall Tape - ND Off-White Joint Compound - Chrysotile 2 % Paint - ND Brown Mastic - Anthophyllite Trace Tan Mastic - ND		
L-230803-02A	Carpet Mastic	Teen Center	Center of room, under pool table	Light Brown Mastic - Chrysotile 2%	Good	5,000 sq. ft.
L-230803-02B		Depository	Center of room	Light Brown Mastic - Chrysotile 2%		
L-230803-02C		Technical Services	North end of area	Light Brown Mastic - Chrysotile 2%		
L-230803-02D	Carpet Mastic	Technical Services	West end between cabinets	Light Brown Mastic - Chrysotile 2%	Good	5,000 sq. ft.
L-230803-02E		Hallway	North end in front of lockers at restrooms	Light Brown Mastic - Chrysotile 2%		



TABLE IB - ACM/ACCM ASBESTOS SAMPLING RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
L-230803-03A	12" x 12" Blue Vinyl Floor Tile/Mastic	Old Break Room	At southwest corner	Blue Tile - ND Tan Mastic - ND Brown Mastic - Chrysotile 2 %	Good	1000 sq. ft.
L-230803-03B			At west wall behind refrigerator	Blue Tile - ND Tan Mastic - ND Brown Mastic - Chrysotile 2 %		
L-230803-03C			At northeast corner	Blue Tile - ND Tan Mastic - ND Brown Mastic - Chrysotile 2 %		
L-230803-04A	4" Brown Vinyl Base Cove/Mastic	North Hallway	Across from Teen Center	Brown Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace Paint - ND Off-White Non-Fibrous Material - ND	Good	1000 LF
L-230803-04B			Across from Old Break Room	Brown Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace		
L-230803-04C			North of Elevators	Brown Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace Paint - ND Off-White Non-Fibrous Material - Chrysotile 2%		



TABLE IB - ACM/ACCM ASBESTOS SAMPLING RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
L-230803-05A	4" Black Vinyl Base Cove/Mastic	Depository	Northwest corner	Black Non-Fibrous Material - ND Brown Mastic - Anthophyllite Trace Grey Non-Fibrous Material - ND	Good	1000 LF
L-230803-05B			South wall at door to stairs	Black Non-Fibrous Material - ND Brown Mastic - Anthophyllite Trace Paint - ND Off-White Joint Compound - Chrysotile 2 %		
L-230803-05C			West wall	Black Non-Fibrous Material - ND Brown Mastic - Anthophyllite Trace		
L-230803-07A	4" Grey Vinyl Base Cove/Mastic	Teen Center	Southwest wall at door	Grey Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace Paint - ND Off-White Joint Compound - Chrysotile 2 %	Good	1000 LF
L-230803-07B			Northwest area at door	Grey Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace Paint - ND Off-White Joint Compound - Chrysotile 2 % Drywall Tape - ND Off-White Joint Compound - Chrysotile 2 %		



TABLE IB - ACM/ACCM ASBESTOS SAMPLING RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
L-230803-09A	4" Blue Vinyl Base Cove/Mastic	Old Break Room	Southwest corner	Dark Blue Non-Fibrous Mat'l - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace Paint - ND	Good	1000 sq. ft.
L-230803-09B			West wall behind refrigerator	Dark Blue Non-Fibrous Mat'l - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace Paint - ND		
L-230803-09C			Northeast corner	Dark Blue Non-Fibrous Mat'l - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace Paint - ND		
L-230803-10A	6" Black Vinyl Base Cove/Mastic	Teen Center	Northeast corner behind door	Black Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace Paint - ND	Good	1000 LF
L-230803-10B			West wall be hind couch	Black Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace Paint - ND		



TABLE IB - ACM/ACCM ASBESTOS SAMPLING RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
L-230803-10C			South wall behind Entertainment Center	Black Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace Paint - ND Grey Cementitious Material - ND		
First Floor						
1-230802-01A	Drywall/Mud/Tape	Front of Young Adult Area	At west wall	White Drywall - ND Off-White Joint Compound - Chrysotile 2 % Paint - ND Brown Mastic - Anthophyllite Trace Tan Mastic - ND Grey Cementitious Material - ND Paint - ND	Good	10,000 sq. ft.
1-230802-01B		Main Library	West wall behind west stairs	White Drywall - ND Off-White Joint Compound - Chrysotile 2 % Off-White Non-Fibrous Material - ND Paint - ND Brown Mastic - Anthophyllite Trace Tan Mastic - ND		
1-230802-01C		Imagination Place (Kid's Area)	At door to staff Offices	White Drywall - ND Off-White Joint Compound - Chrysotile 2 % Paint - ND Brown Mastic - Anthophyllite Trace Tan Mastic - ND		



TABLE IB - ACM/ACCM ASBESTOS SAMPLING RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
1-230802-02A	Carpet Mastic	Front of Young Adult Office	Southwest corner	Tan Mastic/Debris - Chrysotile 2 %	Good	50,000 sq. ft.
1-230802-02B		Main Library	Northeast corner	Tan Mastic/Debris - Chrysotile 2 %		
1-230802-02C			North end of floor	Tan Mastic/Debris - Chrysotile 2 %		
1-230802-02D			Southeast corner	Tan Fibrous Material - ND Tan Mastic/Debris - Chrysotile Trace		
1-230802-02E	Carpet Mastic	Main Library	Center of south wall	Tan Mastic/Debris - Chrysotile Trace	Good	50,000 sq. ft.
1-230802-02F		Children's Area	Northwest corner	Tan Mastic/Debris - Chrysotile 2%		
1-230802-02G			Southeast corner	Tan Mastic/Debris - Chrysotile 2 %		
1-230802-04A	4" Brown Base Cove/Mastic	Lobby Office	Southwest corner	Brown Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace Paint - ND Off-White Joint Compound - Chrysotile 2 %	Good	1000 LF
1-230802-04B			Under reception counter on north side	Brown Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace		
1-230802-04C		Lobby	Southwest corner	Brown Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace		



TABLE IB - ACM/ACCM ASBESTOS SAMPLING RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023 **Ind. Hyg.:** D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
1-230802-05A	4" Black Base Cove/Mastic	Main Library	At west wall in front of Young Adult Area - office	Black Non-Fibrous Material/Paint - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace Off-White Joint Compound - Chrysotile 2 %	Good	1000 LF
1-230802-05B			Behind stairs on east wall	Black Non-Fibrous Material/Paint - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace Off-White Joint Compound - Chrysotile 2 %		
1-230802-05C			At north wall	Black Non-Fibrous Material/Paint - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace		
1-230802-06C	4" Black Base Cove/Mastic	Elevator Hallway	West wall - west of Lobby Office	Black Flooring - ND Tan Mastic - ND Brown Mastic/Debris - Chrysotile 2 %	Good	1000 LF
1-230802-10A	4" Blue Vinyl Base Cove/Mastic	Imagination Place (Kid's Area)	At door to staff office	Dark Blue Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace Paint - ND Off-White Joint Compound - Chrysotile 2 %	Good	1000 LF
1-230802-10B		Children's Service Area	Northwest corner	Dark Blue Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace Paint - ND		



TABLE IB - ACM/ACCM ASBESTOS SAMPLING RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
1-230802-10C			Southeast corner	Dark Blue Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace		
1-230802-11A	6" Black Vinyl Base Cove/Mastic	Entry	Northwest side	Black Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace	Good	30 LF
1-230802-11B			Southwest side	Black Non-Fibrous Material - ND Tan Mastic - ND Brown Mastic - Anthophyllite Trace		
1-230802-13A	Bakelite	Children's Theater (Electrical/Server Room)	Not Sampled	Assumed ACM	Good	7 total



TABLE IB - ACM/ACCM ASBESTOS SAMPLING RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023 **Ind. Hyg.:** D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
Second Floor						
2-230803-01A	Drywall/Mud/Tape	Main Library	At east stairwell	White Drywall - ND White Joint Compound - Chrysotile 2 % Drywall Tape - ND White Joint Compound - Chrysotile 2 % Paint - ND	Good	10,000 sq. ft.
2-230803-01B		Corridor to Restrooms	Southeast corner	White Drywall - ND White Joint Compound - Chrysotile 2 % Drywall Tape - ND White Joint Compound - Chrysotile 2 % Off-White Woven Material - ND Brown Mastic - Anthophyllite Trace		
2-230803-01C		Main Library	Outside of Room 4 at north of door	White Drywall - ND White Joint Compound - Chrysotile 2 % Drywall Tape - ND White Joint Compound - Chrysotile 2 % Off-White Woven Material - ND Brown Mastic - Anthophyllite Trace		
2-230803-02A	Carpet Mastic	Main Library	Northeast corner	Brown Mastic/Debris - Chrysotile Trace Point Count - 0.06% Chrysotile	Good	75,000 sq. ft.
2-230803-02B			Southeast corner	Brown Mastic/Debris - Chrysotile Trace Point Count - 0.20% Chrysotile		



TABLE IB - ACM/ACCM ASBESTOS SAMPLING RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
2-230803-02C			At south end	Brown Mastic/Debris - Chrysotile Trace Point Count - 0.13% Chrysotile		
2-230803-02D	Carpet Mastic	Main Library	Southwest corner	Tan Mastic - ND Off-White Non-Fibrous Material - ND Brown Mastic/Debris - Chrysotile Trace Point Count - 0.13% Chrysotile	Good	75,000 sq. ft.
2-230803-02E			Central area	Brown Mastic/Debris - Chrysotile Trace Point Count - 0.15% Chrysotile		
2-230803-02F		Main Library Staff Offices	Northwest corner	Brown Mastic/Debris - Chrysotile Trace Point Count - 0.14% Chrysotile		
2-230803-02G			At north end	Tan Mastic - ND Off-White Non-Fibrous Material - ND Brown Mastic/Debris - Chrysotile Trace Point Count - 0.16% Chrysotile		
2-230803-04A		Stairwells	At east stairwell	Black Non-Fibrous Material - ND Beige Mastic - ND Brown Mastic - Anthophyllite Trace Off-White Joint Compound - Chrysotile 2 %	Good	1000 LF
2-230803-04B	Black Vinyl Base Cove/Mastic	Corridor to Restrooms	Southeast corner	Black Non-Fibrous Material - ND Beige Mastic - ND Brown Mastic - Anthophyllite Trace		



TABLE IB - ACM/ACCM ASBESTOS SAMPLING RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023 **Ind. Hyg.:** D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
2-230803-04C		Main Library	Outside Room 4 at north of door	Black Non-Fibrous Material - ND Beige Mastic - ND Brown Mastic - Anthophyllite Trace		
Third Floor						
3-230802-01A	Drywall/Mud/Tape	Administration Office	At wall base near door near Conference Room 34 at Entrance	White Drywall - ND Off-White Joint Compound - Chrysotile 2 % Drywall Tape - ND Off-White Joint Compound - Chrysotile 2 % Paint - ND Brown Mastic - Anthophyllite Trace	Good	10,000 sq. ft.
3-230802-01B		Main Library Area	At west stairwell	White Drywall - ND Off-White Joint Compound - Chrysotile 2 % Paint - ND Brown Mastic - Anthophyllite Trace		
3-230802-01C			Behind east stairwell	White Drywall - ND Paint - ND Brown Mastic - Anthophyllite Trace		
3-230802-02A	Carpet Glue	Main Library	Southwest area	Tan Mastics/Debris - Chrysotile Trace Point Count - 0.16% Chrysotile	Good	20,000 sq. ft.
3-230802-02B			South end	Tan Mastics/Debris - Chrysotile Trace Point Count - 0.05% Chrysotile		
3-230802-02C			Southeast corner	Tan Mastics/Debris - Chrysotile Trace Point Count - 0.26% Chrysotile		



TABLE IB - ACM/ACCM ASBESTOS SAMPLING RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023 **Ind. Hyg.:** D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
3-230802-02D			Central area	Tan Mastics/Debris - Chrysotile Trace White Non-Fibrous Material - ND Point Count - 0.11% Chrysotile		
3-230802-02E			Northeast corner	Tan Mastics/Debris - Chrysotile Trace Point Count - 0.26% Chrysotile		
3-230802-02F	Carpet Glue	North Office Area	North end of floor	Tan Mastics/Debris - Chrysotile Trace White Non-Fibrous Material - ND Point Count - 0.24% Chrysotile	Good	20,000 sq. ft.
3-230802-02G		Conference Room	Northeast corner	Tan Mastics/Debris - Chrysotile Trace Point Count - 0.15% Chrysotile		
3-230802-03A	Stair Tread	Stairwells	East stairwell	Brown Non-Fibrous Material - ND Tan Non-Fibrous Material - ND Tan Mastic - Chrysotile Trace	Good	1000 sq. ft.
3-230802-03B			West stairwell	Black Non-Fibrous Material/Stones - ND Yellow Mastic - ND Brown Non-Fibrous Material - ND Beige Mastic - ND Tan Non-Fibrous Material - ND Tan Mastic - Chrysotile Trace Grey Non-Fibrous Material - ND		



TABLE IB - ACM/ACCM ASBESTOS SAMPLING RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023

Ind. Hyg.: D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
3-230802-04A	Blue Vinyl Base Cove/Mastic	Main Library	At east stairs	Blue Non-Fibrous Material - ND Beige Mastic - ND Brown Mastic - Anthophyllite Trace Off-White Joint Compound - Chrysotile Trace	Good	1000 LF
3-230802-04B			Northeast corner	Blue Non-Fibrous Material - ND Beige Mastic - ND Brown Mastic - Anthophyllite Trace Off-White Joint Compound - Chrysotile Trace		
3-230802-04C	Blue Vinyl Base Cove/Mastic	Main Library	At north wall west of Conference Room 3A	Blue Non-Fibrous Material - ND Beige Mastic - ND Brown Mastic - Anthophyllite Trace Off-White Joint Compound - Chrysotile Trace	Good	1000 LF
3-230802-05A	12" x 12" Black Vinyl Sheet Flooring/Mastic	Drinking Fountain	In front of fountain	Black Tile - ND Yellow Mastic - ND Tan Mastic - Chrysotile Trace	Good	32 sq. ft.
3-230802-05B			In front of fountain	Black Tile - ND Yellow Mastic - ND Tan Mastic - Chrysotile Trace		
3-230802-05C			In front of fountain	Black Tile - ND Yellow Mastic - ND Tan Mastic - Chrysotile Trace		
Penthouse						



TABLE IB - ACM/ACCM ASBESTOS SAMPLING RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023 **Ind. Hyg.:** D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
P-230803-01A	Drywall/Tape/Mud	General Room/South Room	At northwest corner	Brown Drywall - ND Off-White Joint Compound - Chrysotile Trace Point Count - 0.59% Chrysotile	Good	1000 sq. ft.
P-230803-01B			At north side of east wall	Brown Drywall - ND Off-White Joint Compound - Chrysotile Trace Point Count - 0.91% Chrysotile		
P-230803-01C			At south side of east wall	Brown Drywall - ND Off-White Joint Compound - Chrysotile Trace Point Count - 0.50% Chrysotile		
P-230803-02C			Debris pile	Brown Drywall - ND Off-White Joint Compound - Chrysotile Trace Point Count - 0.54% Chrysotile Beige Cementitious Material - ND Brown Fibrous Mat'l/Debris ND		
Building Exterior and Roof						
M-230803-01A	Brown Rubber Flooring/Mastic	Staff Elevator Car	Northeast corner	Brown Flooring - ND Off-White Woven Material - ND Clear/Tan Mastic - ND Grey Non-Fibrous Material - ND Brown Mastic - Chrysotile 2 %	Good	30 sq. ft.



TABLE IB - ACM/ACCM ASBESTOS SAMPLING RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023 **Ind. Hyg.:** D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
M-230803-01B			Southeast corner	Brown Flooring - ND Off-White Woven Material - ND Clear/Tan Mastic - ND Grey Non-Fibrous Material - ND Brown Mastic - Chrysotile 2 %		
M-230803-01C			Southwest corner	Brown Flooring - ND Off-White Woven Material - ND Clear/Tan Mastic - ND Grey Non-Fibrous Material - ND Brown Mastic - Chrysotile 2 %		
M-230803-04A	Mastic	Restrooms	Behind mirrors throughout building - not sampled	Assumed ACM	Good	12 total



TABLE IB - ACM/ACCM ASBESTOS SAMPLING RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2, 3, and 4 2023 **Ind. Hyg.:** D. Berman, CAC (15-5418)/R. Dullabaun, MS, CAC (11-4716)/R. Medina, CDPH LST, IHT

Sample No.	Material	Location	Description	Asbestos Results Type and Percent (%)	Condition	Approximate Square/Linear footage
M-230803-08A	Carpet Mastic	Stairs at Loading Dock to 1 st Floor	Under red carpet	Red Carpet - ND Beige Fibrous Material - ND Brown Mastic - Chrysotile 2 %	Good	1000 sq. ft.
M-230803-08B			Under red carpet	Red Carpet - ND Beige Fibrous Material - ND Brown Mastic - Chrysotile 2 %		

Standards/Guidelines:

EPA - ACM >1.0

State of California - ACCM >0.1

Analytical Method: EPA 600/R-93/116 - Polarized Light Microscopy (PLM)

Abbreviations: ND = none detected; < = less than; % - percent; EPA = Environmental Protection Agency; ACM = Asbestos Containing Material; ACCM = Asbestos Containing Construction Material; LF = linear feet; ft² = square feet; bold/shade = ACM; bold print only = ACCM

Disclaimer: HSA's measurements and component identifications are approximations and **must be confirmed** by contractors bidding the project. In addition, hidden or unknown suspect asbestos containing materials (ACM)/asbestos containing construction materials (ACCM) or lead containing/coated materials may be uncovered during the project. Multiple layers of building materials exist, abatement includes all layers of both ACMs and non-ACMs including all residue. Similar materials in color, texture and appearance as those identified in HSA's report should be considered asbestos until sampled. All contractors working on the project should notify the Owner regarding the discovery of unidentified hazardous materials. All work to be performed in accordance with all state, local and federal regulations.



TABLE IIA - LEAD BASED PAINT XRF RESULTS

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2 and 3, 2023

Ind. Hyg.: D. Berman, CDPH I/A, (LRC 00002357)/ R. Dullabaun, MS, CDPH I/A (LRC 00009201)/
R. Medina, CDPH LST (LRC 00002314)/A. Rizo, IHIT

TESTED WITH RADIATION MONITORING DEVICE (RMD) MODEL LPA-1B XRF TYPE ANALYZER (Serial Number1680L)							
Test No.	Location	Side	Color	Substrate	Component	Paint Cond'n	Result mg/cm ²
Loading Dock and Parking							
--	Pre - Calibration	--	--	--	--	--	0.9
--	Pre - Calibration	--	--	--	--	--	0.8
--	Pre - Calibration	--	--	--	--	--	0.8
1	Double Door Entrance	A	White	Drywall	Wall	Intact	-0.1
2	Double Door Entrance	A	White	Wood	Cabinet Doors	Fair	-0.2
3	Double Door Entrance	B	White	Drywall	Wall	Intact	1.8
4	Double Door Entrance	B	Grey	Wood	Door	Fair	-0.3
5	Double Door Entrance	B	Grey	Metal	Door Frame	Intact	-0.4
6	Double Door Entrance	G	Grey	Metal	Window Sill	Fair	-0.1
7	Double Door Entrance	B	White	Wood	Cabinet Door	Fair	-0.1
8	Double Door Entrance	C	White	Brick	Wall	Intact	-0.1
9	Double Door Entrance	C	Grey	Metal	Door	Intact	-0.3
10	Double Door Entrance	D	White	Concrete	Wall	Intact	-0.3
11	Double Door Entrance	D	Grey	Metal	Window Frame	Intact	-0.3
12	Double Door Entrance	D	Grey	Wood	Door	Fair	-0.5
13	Double Door Entrance	D	White	Drywall	Wall	Intact	-0.2
14	Corridor D - 009	B	White	Drywall	Wall	Intact	2.1



TABLE IIA - LEAD BASED PAINT XRF RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2 and 3, 2023

Ind. Hyg.: D. Berman, CDPH I/A, (LRC 00002357)/ R. Dullabaun, MS, CDPH I/A (LRC 00009201)/
R. Medina, CDPH LST (LRC 00002314)/A. Rizo, IHIT

TESTED WITH RADIATION MONITORING DEVICE (RMD) MODEL LPA-1B XRF TYPE ANALYZER (Serial Number1680L)							
Test No.	Location	Side	Color	Substrate	Component	Paint Cond'n	Result mg/cm ²
15	Corridor D - 009	D	White	Drywall	Wall	Intact	-0.0
16	Corridor D - 009	D	Grey	Wood	Door 1	Intact	-0.2
17	Corridor D - 009	D	Grey	Metal	Door Frame 2	Fair	-0.2
18	Corridor D - 009	D	Grey	Metal	Elevator Door	Intact	-0.0
19	Teen Center	A	White	Drywall	Wall	Intact	-0.0
20	Teen Center	A	Grey	Wood	Door	Intact	-0.0
21	Teen Center	A	Grey	Metal	Door Frame	Fair	-0.2
22	Teen Center	A	Green	Drywall	Wall	Intact	-0.1
23	Teen Center	A	Brown	Drywall	Wall	Intact	-0.1
24	Teen Center	A	Blue	Drywall	Wall	Intact	-0.0
25	Teen Center	B	White	Brick	Wall	Intact	-0.3
26	Teen Center	B	White	Metal	Drain Pipe	Intact	-0.1
27	Teen Center	B	Yellow	Brick	Wall	Intact	-0.1
28	Teen Center	B	Orange	Brick	Wall	Intact	-0.2
29	Teen Center	B	Blue	Brick	Wall	Intact	-0.2
30	Teen Center	C	White	Drywall	Wall	Intact	-0.5
31	Teen Center	C	White	Metal	Window Frame	Intact	-0.1
32	Teen Center	C	Grey	Wood	Door	Fair	-0.5



TABLE IIA - LEAD BASED PAINT XRF RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2 and 3, 2023

Ind. Hyg.: D. Berman, CDPH I/A, (LRC 00002357)/ R. Dullabaun, MS, CDPH I/A (LRC 00009201)/
R. Medina, CDPH LST (LRC 00002314)/A. Rizo, IHIT

TESTED WITH RADIATION MONITORING DEVICE (RMD) MODEL LPA-1B XRF TYPE ANALYZER (Serial Number1680L)							
Test No.	Location	Side	Color	Substrate	Component	Paint Cond'n	Result mg/cm ²
33	Teen Center	D	White	Drywall	Wall	Intact	-0.3
34	Teen Center	D	Grey	Wood	Door 1	Intact	-0.1
35	Teen Center	D	Grey	Metal	Door 2 Frame	Intact	-0.0
36	Teen Center - Office	A	White	Drywall	Wall	Intact	-0.1
37	Teen Center - Office	A	White	Metal	Window Frame	Intact	-0.1
38	Teen Center - Office	A	Grey	Wood	Door	Intact	-0.2
39	Teen Center - Office	B	White	Drywall	Wall	Intact	-0.2
40	Teen Center - Office	B	White	Metal	Window Frame	Intact	-0.2
41	Teen Center - Office	C	White	Concrete	Wall	Intact	-0.1
42	Teen Center - Office	C	White	Brick	Wall	Intact	-0.1
43	Teen Center - Office	D	White	Drywall	Wall	Intact	-0.4
44	Teen Center - Office	D	White	Metal	Window frame	Intact	-0.3
45	Teen Center	--	White	Concrete	Center Column	Intact	-0.3
46	Staff Lounge	A	White	Drywall	Wall	Intact	-0.0
47	Staff Lounge	B	White	Drywall	Wall	Intact	-0.2
48	Staff Lounge	B	White	Wood	Cabinet	Fair	-0.0
49	Staff Lounge	B	Grey	Wood	Door	Intact	-0.2
50	Staff Lounge	B	Grey	Metal	Door Jamb	Fair	-0.1



TABLE IIA - LEAD BASED PAINT XRF RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2 and 3, 2023

Ind. Hyg.: D. Berman, CDPH I/A, (LRC 00002357)/ R. Dullabaun, MS, CDPH I/A (LRC 00009201)/
R. Medina, CDPH LST (LRC 00002314)/A. Rizo, IHIT

TESTED WITH RADIATION MONITORING DEVICE (RMD) MODEL LPA-1B XRF TYPE ANALYZER (Serial Number1680L)							
Test No.	Location	Side	Color	Substrate	Component	Paint Cond'n	Result mg/cm ²
51	Staff Lounge	C	White	Concrete	Wall	Fair	-0.4
52	Staff Lounge	C	White	Brick	Wall	Fair	-0.2
53	Staff Lounge	D	White	Brick	Wall	Fair	-0.4
54	Depository	A	White	Brick	Wall	Intact	-0.1
55	Depository	B	Orange	Drywall	Wall	Intact	-0.2
56	Depository	B	Orange	Metal	Door	Intact	-0.1
57	Depository	B	Orange	Metal	Door Frame	Fair	-0.2
58	Depository	C	Orange	Drywall	Wall	Fair	-0.4
59	Depository	C	Grey	Wood	Door 1	Intact	-0.4
60	Depository	C	Grey	Metal	Door 2 Jamb	Fair	-0.3
61	Depository	D	White	Drywall	Wall	Poor	-0.3
62	Lower Lobby	B	Black	Wood	Door	Intact	-0.5
63	Lower Lobby	B	Black	Metal	Door Frame	Poor	-0.0
64	Men's Restroom	A	White	Ceramic	Wall Tile	Intact	>9.9
65	Men's Restroom	A	White	Porcelain	Toilet	Intact	1.0
66	Men's Restroom	A	Green	Metal	Stall Door	Fair	0.5
67	Men's Restroom	A	White	Porcelain	Urinal	Intact	-0.2
68	Men's Restroom	A	Green	Metal	Wall Divider	Poor	0.4



TABLE IIA - LEAD BASED PAINT XRF RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2 and 3, 2023

Ind. Hyg.: D. Berman, CDPH I/A, (LRC 00002357)/ R. Dullabaun, MS, CDPH I/A (LRC 00009201)/
R. Medina, CDPH LST (LRC 00002314)/A. Rizo, IHIT

TESTED WITH RADIATION MONITORING DEVICE (RMD) MODEL LPA-1B XRF TYPE ANALYZER (Serial Number1680L)							
Test No.	Location	Side	Color	Substrate	Component	Paint Cond'n	Result mg/cm ²
69	Men's Restroom	A	White	Porcelain	Sink	Intact	-0.7
70	Men's Restroom	B	Green	Ceramic	Wall Tile	Intact	6.7
71	Men's Restroom	C	Green	Ceramic	Wall Tile	Intact	>9.9
72	Men's Restroom	C	White	Drywall	Wall	Fair	-0.2
73	Men's Restroom	C	Orange	Wood	Door	Intact	-0.2
74	Men's Restroom	C	White	Ceramic	Baseboard Tile	Intact	>9.9
75	Men's Restroom	D	White	Drywall	Wall	Intact	-0.2
76	Men's Restroom	--	White	Drywall	Ceiling	Intact	-0.0
77	Men's Restroom	--	Brown	Ceramic	Floor Tile	Intact	-0.0
78	Woman's Restroom	A	White	Ceramic	Wall Tile	Intact	>9.9
79	Woman's Restroom	A	White	Porcelain	Sink	Intact	-0.3
80	Woman's Restroom	A	White	Porcelain	Toilet 1	Intact	3.4
81	Woman's Restroom	A	Orange	Metal	Stall Door 1	Fair	0.4
82	Woman's Restroom	A	White	Porcelain	Toilet 2	Intact	-0.5
83	Woman's Restroom	A	Orange	Metal	Stall Door 2	Intact	1.0
84	Woman's Restroom	B	White	Drywall	Wall	Intact	0.0
85	Woman's Restroom	B	White	Ceramic	Baseboard Tile	Intact	>9.9
86	Woman's Restroom	C	Orange	Wood	Door	Intact	-0.4



TABLE IIA - LEAD BASED PAINT XRF RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2 and 3, 2023

Ind. Hyg.: D. Berman, CDPH I/A, (LRC 00002357)/ R. Dullabaun, MS, CDPH I/A (LRC 00009201)/
R. Medina, CDPH LST (LRC 00002314)/A. Rizo, IHIT

TESTED WITH RADIATION MONITORING DEVICE (RMD) MODEL LPA-1B XRF TYPE ANALYZER (Serial Number1680L)							
Test No.	Location	Side	Color	Substrate	Component	Paint Cond'n	Result mg/cm ²
87	Woman's Restroom	C	White	Metal	Door Frame	Fair	-0.2
88	Woman's Restroom	D	Orange	Ceramic	Wall Tile	Intact	6.5
89	Woman's Restroom	--	White	Drywall	Ceiling	Intact	-0.1
90	Woman's Restroom	--	Brown	Ceramic	Floor Tile	Intact	-0.4
91	Janitor's Closet	A	White	Wood	Door	Fair	-0.2
92	Janitor's Closet	A		Metal	Door Jamb	Fair	-0.2
93	Janitor's Closet	A		Drywall	Wall	Fair	-0.4
94	Janitor's Closet	B		Drywall	Wall	Fair	-0.3
95	Janitor's Closet	B		Metal	Fire Sprinkler Pipe	Poor	0.2 XRF
PC 1							0.15 WT%
96	Janitor's Closet	C		Drywall	Wall	Intact	-0.4
97	Janitor's Closet	C		Porcelain	Sink		>9.9
98	Janitor's Closet	D		Drywall	Wall	Poor	-0.1
99	Post - Calibration	--	--	--	--	--	0.9
99	Post - Calibration	--	--	--	--	--	0.9
99	Post - Calibration	--	--	--	--	--	0.8
100	Pre - Calibration	--	--	--	--	--	0.9
101	Pre - Calibration	--	--	--	--	--	0.9



TABLE IIA - LEAD BASED PAINT XRF RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2 and 3, 2023

Ind. Hyg.: D. Berman, CDPH I/A, (LRC 00002357)/ R. Dullabaun, MS, CDPH I/A (LRC 00009201)/
R. Medina, CDPH LST (LRC 00002314)/A. Rizo, IHIT

TESTED WITH RADIATION MONITORING DEVICE (RMD) MODEL LPA-1B XRF TYPE ANALYZER (Serial Number1680L)							
Test No.	Location	Side	Color	Substrate	Component	Paint Cond'n	Result mg/cm ²
102	Pre - Calibration	--	--	--	--	--	0.8
103	Initial Processing D-021	A	White	Concrete	Wall	Intact	-0.2
104	Initial Processing D-021	A	White	Drywall	Wall	Intact	-0.1
105	Initial Processing D-021	B	White	Drywall	Wall	Intact	-0.0
106	Initial Processing D-021	B	Grey	Wood	Door	Intact	-0.3
107	Initial Processing D-021	B	Grey	Metal	Door Jamb	Fair	-0.3
108	Initial Processing D-021	B	White	Porcelain	Sink	Intact	>9.9
109	Initial Processing D-021	B	White	Metal	Window Frame	Intact	-0.1
110	Initial Processing D-021	C	White	Drywall	Wall	Intact	-0.4
111	Initial Processing D-021	C	White	Brick	Wall	Intact	-0.1
112	Initial Processing D-021	D	White	Brick	Wall	Intact	-0.4
113	Initial Processing D-021	B	White	Concrete	Column	Intact	-0.2
114	North Stairwell	A	White	Metal	Sprinkler Pipe	Fair	-0.1
115	North Stairwell	B	Blue	Metal	Door Frame	Intact	-0.1
116	North Stairwell	B	Blue	Metal	Door	Intact	-0.1
117	Post - Calibration	--	--	--	--	--	0.9
118	Post - Calibration	--	--	--	--	--	0.9
119	Post - Calibration	--	--	--	--	--	0.9



TABLE IIA - LEAD BASED PAINT XRF RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2 and 3, 2023

Ind. Hyg.: D. Berman, CDPH I/A, (LRC 00002357)/ R. Dullabaun, MS, CDPH I/A (LRC 00009201)/
R. Medina, CDPH LST (LRC 00002314)/A. Rizo, IHIT

TESTED WITH RADIATION MONITORING DEVICE (RMD) MODEL LPA-1B XRF TYPE ANALYZER (Serial Number1680L)							
Test No.	Location	Side	Color	Substrate	Component	Paint Cond'n	Result mg/cm ²
120	Pre - Calibration	--	--	--	--	--	1.0
121	Pre - Calibration	--	--	--	--	--	0.8
122	Pre - Calibration	--	--	--	--	--	0.9
123	Server Room	A	White	Drywall	Wall	Intact	-0.1
124	Server Room	C	White	Metal	Door Jamb	Intact	-0.2
125	Server Room	D	White	Metal	Door	Intact	-0.1
126	Post - Calibration	--	--	--	--	--	1.1
127	Post - Calibration	--	--	--	--	--	1.0
128	Post - Calibration	--	--	--	--	--	0.9
First Floor							
--	Pre - Calibration	--	--	--	--	--	0.9
--	Pre - Calibration	--	--	--	--	--	0.8
--	Pre - Calibration	--	--	--	--	--	0.8
1	Entrance Lobby	B	White	Drywall	Wall	Intact	-0.4
2	Entrance Lobby	B	White	Concrete	Wall	Intact	-0.1
3	Entrance Lobby	B	Grey	Wood	Door 1	Intact	-0.2
4	Entrance Lobby	B	Grey	Metal	Door Frame 1	Intact	-0.2
5	Entrance Lobby	B	Grey	Metal	Door Jamb 2	Intact	-0.2



TABLE IIA - LEAD BASED PAINT XRF RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2 and 3, 2023

Ind. Hyg.: D. Berman, CDPH I/A, (LRC 00002357)/ R. Dullabaun, MS, CDPH I/A (LRC 00009201)/
R. Medina, CDPH LST (LRC 00002314)/A. Rizo, IHIT

TESTED WITH RADIATION MONITORING DEVICE (RMD) MODEL LPA-1B XRF TYPE ANALYZER (Serial Number1680L)							
Test No.	Location	Side	Color	Substrate	Component	Paint Cond'n	Result mg/cm ²
6	Entrance Lobby	B	Blue	Drywall	Wall	Intact	-0.0
7	Entrance Lobby	B	Yellow	Drywall	Wall	Intact	-0.1
8	Entrance Lobby	B	Red	Drywall	Wall	Intact	-0.2
9	Entrance Lobby	--	Brown	Ceramic	Floor Tile	Intact	>9.9
10	Entrance Lobby - Women's Restroom	A	Orange	Ceramic	Wall Tile	Intact	6.2
11	Entrance Lobby - Women's Restroom	B	White	Ceramic	Wall Tile	Intact	>9.9
12	Entrance Lobby - Women's Restroom	C	White	Drywall	Wall	Intact	-0.4
13	Entrance Lobby - Women's Restroom	C	White	Porcelain	Toilet 1	Intact	-0.2
14	Entrance Lobby - Women's Restroom	C	Black	Metal	Stall Door 2	Intact	-0.5
15	Entrance Lobby - Women's Restroom	C	White	Porcelain	Sink 1	Intact	0.4
16	Entrance Lobby - Women's Restroom	C	Grey	Ceramic	Tile Sink Counter Top	Intact	-0.5
17	Entrance Lobby - Women's Restroom	C	White	Ceramic	Baseboard Tile	Intact	>9.9
18	Entrance Lobby - Women's Restroom	D	Grey	Wood	Door	Intact	-0.2
19	Entrance Lobby - Women's Restroom	--	White	Drywall	Ceiling	Intact	-0.1
20	Entrance Lobby - Women's Restroom	--	Brown	Ceramic	Floor Tile	Intact	-0.6
21	Entrance Lobby - Men's Restroom	A	White	Ceramic	Wall Tile	Intact	>9.9
22	Entrance Lobby - Men's Restroom	A	White	Porcelain	Sink	Intact	0.5
23	Entrance Lobby - Men's Restroom	A	Grey	Ceramic	Tile Counter Top	Intact	-0.4



TABLE IIA - LEAD BASED PAINT XRF RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2 and 3, 2023

Ind. Hyg.: D. Berman, CDPH I/A, (LRC 00002357)/ R. Dullabaun, MS, CDPH I/A (LRC 00009201)/
R. Medina, CDPH LST (LRC 00002314)/A. Rizo, IHIT

TESTED WITH RADIATION MONITORING DEVICE (RMD) MODEL LPA-1B XRF TYPE ANALYZER (Serial Number1680L)							
<i>Test No.</i>	<i>Location</i>	<i>Side</i>	<i>Color</i>	<i>Substrate</i>	<i>Component</i>	<i>Paint Cond'n</i>	<i>Result mg/cm²</i>
24	Entrance Lobby - Men's Restroom	A	Grey	Metal	Door	Fair	-0.2
25	Entrance Lobby - Men's Restroom	A	Grey	Metal	Door Frame	Fair	-0.2
26	Entrance Lobby - Men's Restroom	A	White	Porcelain	Urinal	Intact	-0.4
27	Entrance Lobby - Men's Restroom	A	White	Porcelain	Toilet	Intact	-0.4
28	Entrance Lobby - Men's Restroom	B	black	Metal	Stall Door	Intact	-0.2
29	Entrance Lobby - Men's Restroom	C	Green	Ceramic	Wall Tile	Intact	6.6
30	Entrance Lobby - Men's Restroom	--	White	Drywall	Ceiling	Intact	-0.4
31	Entrance Lobby - Men's Restroom	--	Brown	Ceramic	Floor Tile	Intact	-0.4
32	Entrance Lobby - Men's Restroom - Janitor's Closet	A	White	Drywall	Wall	Fair	-0.1
33	Entrance Lobby - Men's Restroom - Janitor's Closet	A	White	Metal	Sink	Fair	>9.9



TABLE IIA - LEAD BASED PAINT XRF RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2 and 3, 2023

Ind. Hyg.: D. Berman, CDPH I/A, (LRC 00002357)/ R. Dullabaun, MS, CDPH I/A (LRC 00009201)/
R. Medina, CDPH LST (LRC 00002314)/A. Rizo, IHIT

TESTED WITH RADIATION MONITORING DEVICE (RMD) MODEL LPA-1B XRF TYPE ANALYZER (Serial Number1680L)							
Test No.	Location	Side	Color	Substrate	Component	Paint Cond'n	Result mg/cm ²
34	Entrance Lobby - Men's Restroom - Janitor's Closet	A	White	Metal	Drain Pipe	Poor	0.3 XRF
PC 3							0.18 WT%
35	Entrance Lobby - Men's Restroom - Janitor's Closet	C	Grey	Metal	Door Frame	Intact	-0.1
36	Entrance Lobby - Men's Restroom - Janitor's Closet	D	White	Drywall	Wall	Intact	-0.2
37	Main Library	A	White	Drywall	Southwest Stair Wall	Intact	-0.3
38	Main Library	A	White	Concrete	Southwest Column	Intact	-0.2
39	Main Library	A	Grey	Wood	Door	Intact	-0.0
40	Main Library	B	White	Drywall	Wall	Intact	-0.2
41	Main Library	C	White	Drywall	Wall	Fair	-0.0
42	Main Library	C	Brown	Metal	Elevator Door Frame	Fair	-0.2
43	Main Library	C	Grey	Wood	Door	Fair	-0.4
44	Main Library	C	Grey	Metal	Door Jamb	Fair	-0.1
45	Main Library	D	White	Drywall	Southeast Stair Wall	Intact	-0.3
46	Registration Area	A	White	Drywall	Wall	Intact	-0.5
47	Registration Area	B	White	Wood	Lower Wall	Intact	-0.3
48	Registration Area	C	White	Wood	Door	Intact	-0.3
49	Children's Library	A	Blue	Concrete	Wall	Intact	-0.0
50	Children's Library	C	Blue	Drywall	Wall	Intact	-0.4



TABLE IIA - LEAD BASED PAINT XRF RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2 and 3, 2023

Ind. Hyg.: D. Berman, CDPH I/A, (LRC 00002357)/ R. Dullabaun, MS, CDPH I/A (LRC 00009201)/
R. Medina, CDPH LST (LRC 00002314)/A. Rizo, IHIT

TESTED WITH RADIATION MONITORING DEVICE (RMD) MODEL LPA-1B XRF TYPE ANALYZER (Serial Number1680L)							
Test No.	Location	Side	Color	Substrate	Component	Paint Cond'n	Result mg/cm ²
51	Children's Library	C	Blue	Wood	Door	Intact	-0.1
52	Children's Library	D	Blue	Wood	Door 1	Fair	0.1 XRF
PC 4							0.08 WT%
53	Children's Library	D	Blue	Metal	Boy's Restroom Door Frame	Intact	-0.1
54	Children's Library	D	Blue	Wood	Girl's Restroom Door Frame	Fair	-0.1
55	Children's Library	D	Purple	Ceramic	Wall	Intact	-0.5
56	Children's Library	--	Black	Ceramic	Floor Tile	Intact	-0.1
57	Children's Library - Story Room	A	Blue	Drywall	Wall	Intact	-0.1
58	Children's Library - Story Room	A	Blue	Wood	Door	Intact	-0.2
59	Children's Library - Story Room	A	Blue	Metal	Door Frame	Intact	-0.2
60	Children's Library - Story Room	B	Blue	Drywall	Wall	Intact	-0.0
61	Children's Library - Story Room	C	Blue	Drywall	Wall	Intact	-0.1
62	Children's Library - Story Room	D	Blue	Drywall	Wall	Intact	-0.2
63	Children's Library - Story Room	D	Light Blue	Drywall	Wall	Intact	-0.0
64	Children's Library - Boy's Restroom	A	Green	Ceramic	Wall Tile	Intact	6.3
65	Children's Library - Boy's Restroom	B	White	Ceramic	Wall Tile	Intact	>9.9
66	Children's Library - Boy's Restroom	B	Blue	Wood	Door	Intact	-0.2



TABLE IIA - LEAD BASED PAINT XRF RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2 and 3, 2023

Ind. Hyg.: D. Berman, CDPH I/A, (LRC 00002357)/ R. Dullabaun, MS, CDPH I/A (LRC 00009201)/
R. Medina, CDPH LST (LRC 00002314)/A. Rizo, IHIT

TESTED WITH RADIATION MONITORING DEVICE (RMD) MODEL LPA-1B XRF TYPE ANALYZER (Serial Number1680L)							
Test No.	Location	Side	Color	Substrate	Component	Paint Cond'n	Result mg/cm ²
67	Children's Library - Boy's Restroom	C	White	Ceramic	Wall Tile	Intact	-0.6
68	Children's Library - Boy's Restroom	C	Grey	Ceramic	Wall Tile	Intact	-0.6
69	Children's Library - Boy's Restroom	D	White	Porcelain	Toilet	Intact	-0.5
70	Children's Library - Boy's Restroom	D	White	Porcelain	Sink	Intact	-0.4
71	Children's Library - Boy's Restroom	--	White	Drywall	Ceiling	Intact	-0.6
72	Children's Library - Boy's Restroom	--	Brown	Ceramic	Floor Tile	Intact	-0.3
73	Children's Library - Girls Restroom	A	White	Ceramic	Wall Tile	Intact	>9.9
74	Children's Library - Girls Restroom	B	blue	Wood	Door	Intact	-0.3
75	Children's Library - Girls Restroom	B	Blue	Metal	Door Frame	Intact	-0.1
76	Children's Library - Girls Restroom	C	Orange	Ceramic	Wall Tile	Intact	6.5
77	Children's Library - Girls Restroom	D	White	Porcelain	Sink	Intact	-0.5
78	Children's Library - Girls Restroom	D	White	Porcelain	Toilet	Intact	-0.2
79	Children's Library - Girls Restroom	--	White	Drywall	Ceiling	Intact	-0.2
80	Children's Library - Girls Restroom	--	Brown	Ceramic	Floor Tile	Intact	-0.5
81	Story Room - Server Room	A	White	Drywall	Wall	Intact	-0.3
82	Story Room - Server Room	C	White	Wood	Door	Intact	-0.1
83	Book Trucks/Office Area	A	White	Drywall	Wall	Intact	-0.1
84	Book Trucks/Office Area	A	Grey	Wood	Door	Intact	-0.1



TABLE IIA - LEAD BASED PAINT XRF RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2 and 3, 2023

Ind. Hyg.: D. Berman, CDPH I/A, (LRC 00002357)/ R. Dullabaun, MS, CDPH I/A (LRC 00009201)/
R. Medina, CDPH LST (LRC 00002314)/A. Rizo, IHIT

TESTED WITH RADIATION MONITORING DEVICE (RMD) MODEL LPA-1B XRF TYPE ANALYZER (Serial Number1680L)							
Test No.	Location	Side	Color	Substrate	Component	Paint Cond'n	Result mg/cm ²
85	Book Trucks/Office Area	B	Purple	Wood	Door	Intact	-0.1
86	Book Trucks/Office Area	B	White	Metal	Door Frame 2	Intact	-0.3
87	Book Trucks/Office Area	B	White	Concrete	Column	Intact	-0.2
88	Book Trucks/Office Area	B	Blue	Wood	Door 3	Intact	-0.5
89	Book Trucks/Office Area	C	White	Wood	Cabinet Wall	Intact	-0.1
90	Book Trucks/Office Area	D	White	Metal	Sink	Intact	>9.9
91	Book Trucks/Office Area	D	White	Drywall	Wall	Intact	-0.2
92	Book Trucks/Office Area	D	Grey	Metal	Elevator Door	Intact	-0.1
93	Book Trucks/Office Area	D	blue	Metal	Door Frame	Intact	-0.0
94	Book Trucks/Office Area	D	White	Metal	Door	Intact	-0.1
95	Book Trucks/Office Area	A	White	Metal	Pipe at Stairwell/North Side	Poor	-0.3
96	Book Trucks/Office Area	D	Brown	Metal	North Stair Railing	Intact	-0.5
97	Book Trucks/Office Area - Men's Restroom	A	White	Ceramic	Wall Tile	Intact	>9.9
98	Book Trucks/Office Area - Men's Restroom	B	Green	Wood	Door	Intact	-0.3
99	Book Trucks/Office Area - Men's Restroom	C	Green	Ceramic	Wall Tile	Intact	5.6
100	Book Trucks/Office Area - Men's Restroom	D	White	Porcelain	Sink	Intact	-0.8
101	Book Trucks/Office Area - Men's Restroom	D	White	Porcelain	Toilet	Intact	-0.3
102	Book Trucks/Office Area - Men's Restroom	D	Green	Metal	Stall Door	Intact	1.0



TABLE IIA - LEAD BASED PAINT XRF RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2 and 3, 2023

Ind. Hyg.: D. Berman, CDPH I/A, (LRC 00002357)/ R. Dullabaun, MS, CDPH I/A (LRC 00009201)/
R. Medina, CDPH LST (LRC 00002314)/A. Rizo, IHIT

TESTED WITH RADIATION MONITORING DEVICE (RMD) MODEL LPA-1B XRF TYPE ANALYZER (Serial Number1680L)							
Test No.	Location	Side	Color	Substrate	Component	Paint Cond'n	Result mg/cm ²
103	Book Trucks/Office Area - Men's Restroom	--	White	Drywall	Ceiling	Intact	-0.2
104	Book Trucks/Office Area - Men's Restroom	--	Brown	Ceramic	Floor Tile	Intact	-0.4
105	Book Trucks/Office Area - Women's Restroom	A	White	Ceramic	Wall Tile	Intact	>9.9
106	Book Trucks/Office Area - Women's Restroom	B	White	Porcelain	Toilet	Intact	-1.1
107	Book Trucks/Office Area - Women's Restroom	B	White	Porcelain	Sink	Intact	-0.5
108	Book Trucks/Office Area - Women's Restroom	C	Orange	Ceramic	Wall Tile	Intact	6.3
109	Book Trucks/Office Area - Women's Restroom	D	Orange	Wood	Door	Intact	-0.1
110	Book Trucks/Office Area - Women's Restroom	--	White	Drywall	Ceiling	Intact	-0.2
111	Book Trucks/Office Area - Women's Restroom	--	Brown	Ceramic	Floor Tile	Intact	-0.3
112	Post - Calibration	--	--	--	--	--	0.8
113	Post - Calibration	--	--	--	--	--	0.8
114	Post - Calibration	--	--	--	--	--	0.9
Second Floor							
--	Pre - Calibration	--	--	--	--	--	0.9
--	Pre - Calibration	--	--	--	--	--	0.8
--	Pre - Calibration	--	--	--	--	--	0.8
1	Corridor 220	A	White	Drywall	Wall	Intact	-0.2
2	Corridor 220	A	Grey	Wood	door	Intact	-0.4



TABLE IIA - LEAD BASED PAINT XRF RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2 and 3, 2023

Ind. Hyg.: D. Berman, CDPH I/A, (LRC 00002357)/ R. Dullabaun, MS, CDPH I/A (LRC 00009201)/
R. Medina, CDPH LST (LRC 00002314)/A. Rizo, IHIT

TESTED WITH RADIATION MONITORING DEVICE (RMD) MODEL LPA-1B XRF TYPE ANALYZER (Serial Number1680L)							
Test No.	Location	Side	Color	Substrate	Component	Paint Cond'n	Result mg/cm ²
3	Corridor 220	A	Grey	Metal	Door Frame	Intact	-0.4
4	Corridor 220	B	White	Metal	Door Jamb	Intact	-0.2
5	Corridor 220	B	White	Wood	Door	Intact	0.0
6	Corridor 220	D	Orange	Wood	Door	Intact	-0.1
7	Corridor 220	D	Grey	Metal	Elevator Door	Intact	-0.1
8	Women's Restroom	A	White	Metal	Door	Intact	-0.1
9	Women's Restroom	A	White	Ceramic	Wall Tile	Intact	>9.9
10	Women's Restroom	A	White	Porcelain	Toilet 1	Intact	-0.1
11	Women's Restroom	A	Green	Metal	Stall Door 2	Intact	1.0
12	Women's Restroom	A	White	Porcelain	Sink	Intact	-0.2
13	Women's Restroom	A	White	Drywall	Wall Tile	Intact	-0.2
14	Women's Restroom	B	Orange	Wood	Door	Intact	-0.3
16	Post - Calibration (8/2/23)	--	--	--	--	--	1.0
17	Post - Calibration (8/2/23)	--	--	--	--	--	0.9
18	Post - Calibration (8/2/23)	--	--	--	--	--	1.0
19	Pre - Calibration (8/3/23)	--	--	--	--	--	0.9
20	Pre - Calibration (8/3/23)	--	--	--	--	--	1.0
21	Pre - Calibration (8/3/23)	--	--	--	--	--	0.8



TABLE IIA - LEAD BASED PAINT XRF RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2 and 3, 2023

Ind. Hyg.: D. Berman, CDPH I/A, (LRC 00002357)/ R. Dullabaun, MS, CDPH I/A (LRC 00009201)/
R. Medina, CDPH LST (LRC 00002314)/A. Rizo, IHIT

TESTED WITH RADIATION MONITORING DEVICE (RMD) MODEL LPA-1B XRF TYPE ANALYZER (Serial Number1680L)							
Test No.	Location	Side	Color	Substrate	Component	Paint Cond'n	Result mg/cm ²
22	Women's Restroom	B	White	Ceramic	Baseboard Tile	Intact	>9.9
23	Women's Restroom	B	White	Metal	Door Frame	Fair	0.0
24	Women's Restroom	C	Green	Ceramic	Wall Tile	Intact	4.2
25	Women's Restroom	D	White	Ceramic	Wall Tile	Intact	>9.9
26	Women's Restroom	--	White	Drywall	Ceiling	Intact	-0.0
27	Women's Restroom	--	Brown	Ceramic	Floor Tile	Intact	-0.2
28	Women's Restroom - Janitor's Closet	A	White	Drywall	Wall	Intact	-0.2
29	Women's Restroom - Janitor's Closet	A	White	Metal	Drain Pipe	Intact	-0.2
30	Women's Restroom - Janitor's Closet	B	White	Drywall	Wall	Fair	-0.1
31	Women's Restroom - Janitor's Closet	B	White	Metal	Drain Pipe	Intact	-0.2
32	Women's Restroom - Janitor's Closet	C	white	Drywall	Wall	Intact	0.0
33	Women's Restroom - Janitor's Closet	C	Red	Metal	Sprinkler Pipe Valve	Fair	-0.1
34	Women's Restroom - Janitor's Closet	C	White	Metal	Drain Pipe	Poor	-0.4
35	Women's Restroom - Janitor's Closet	C	White	Porcelain	Sink	Intact	>9.9
36	Women's Restroom - Janitor's Closet	C	White	Metal	Door	Intact	-0.4
37	Women's Restroom - Janitor's Closet	C	White	Metal	Door Jamb	Intact	-0.2
38	Women's Restroom - Janitor's Closet	D	White	Drywall	Wall	Fair	-0.4
39	Women's Restroom - Janitor's Closet	--	White	Drywall	Ceiling	Intact	-0.0



TABLE IIA - LEAD BASED PAINT XRF RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2 and 3, 2023

Ind. Hyg.: D. Berman, CDPH I/A, (LRC 00002357)/ R. Dullabaun, MS, CDPH I/A (LRC 00009201)/
R. Medina, CDPH LST (LRC 00002314)/A. Rizo, IHIT

TESTED WITH RADIATION MONITORING DEVICE (RMD) MODEL LPA-1B XRF TYPE ANALYZER (Serial Number1680L)							
Test No.	Location	Side	Color	Substrate	Component	Paint Cond'n	Result mg/cm ²
40	Office Workspace	A	Yellow	Wood	Door 1	Intact	-0.4
41	Office Workspace	A	White	Metal	Door Frame	Intact	-0.1
42	Office Workspace	A	White	Drywall	Wall	Intact	-0.1
43	Office Workspace	A	Red	Wood	Door 2	Intact	-0.1
44	Office Workspace	A	Purple	Wood	Door 3	Fair	-0.4
45	Office Workspace	A	White	Metal	Door Jamb 3	Intact	-0.2
46	Office Workspace	D	Blue	Drywall	Wall	Intact	-0.4
47	Office Workspace	D	White	Wood	Door	Intact	-0.3
48	Office Workspace	D	Blue	Metal	Door Frame	Intact	-0.0
49	Men's Restroom	A	Orange	Ceramic	Wall Tile	Intact	5.0
50	Men's Restroom	B	White	Drywall	Wall	Intact	-0.2
51	Men's Restroom	B	White	Ceramic	Baseboard Tile	Intact	>9.9
52	Men's Restroom	B	Grey	Metal	Door Frame	Fair	-0.2
53	Men's Restroom	B	Grey	Wood	Door	Intact	-0.3
54	Men's Restroom	C	White	Drywall	Wall	Intact	0.0
55	Men's Restroom	C	White	Ceramic	Wall Tile	Intact	>9.9
56	Men's Restroom	C	White	Porcelain	Sink 1	Intact	-0.6
57	Men's Restroom	C	Orange	Metal	Stall Door 1	Intact	0.4



TABLE IIA - LEAD BASED PAINT XRF RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2 and 3, 2023

Ind. Hyg.: D. Berman, CDPH I/A, (LRC 00002357)/ R. Dullabaun, MS, CDPH I/A (LRC 00009201)/
R. Medina, CDPH LST (LRC 00002314)/A. Rizo, IHIT

TESTED WITH RADIATION MONITORING DEVICE (RMD) MODEL LPA-1B XRF TYPE ANALYZER (Serial Number1680L)							
Test No.	Location	Side	Color	Substrate	Component	Paint Cond'n	Result mg/cm ²
58	Men's Restroom	C	White	Porcelain	Toilet 2	Intact	-0.3
59	Men's Restroom	C	Orange	Metal	Stall Door 3 Frame	Intact	0.0
60	Men's Restroom	D	White	Ceramic	Wall Tile	Intact	>9.9
61	Men's Restroom	--	White	Drywall	Ceiling	Intact	-0.5
62	Men's Restroom	--	Brown	Ceramic	Floor Tile	Intact	-0.4
63	Main Library	B	Purple	Wood	Door 1	Fair	-0.4
64	Main Library	B	Yellow	Wood	Door 2	Intact	-0.5
65	Main Library	B	Red	Wood	Door 3	Intact	-0.3
66	Main Library	C	White	Drywall	Wall	Fair	-0.2
67	Main Library	C	White	Concrete	Column 1	Intact	-0.1
68	Main Library	C	White	Metal	Door Frame	Intact	-0.3
69	Main Library	C	Purple	Wood	Door 1	Intact	-0.3
70	Main Library	C	Red	Wood	Door 2	Intact	-0.4
71	Main Library	C	Yellow	Wood	Door 3	Intact	-0.1
72	Main Library	C	Grey	Wood	Door 4	Fair	-0.1
73	Main Library	D	White	Drywall	Wall	Intact	-0.1
74	Main Library	--	Brown	Metal	Southeast Stair Railing	Fair	-0.8
75	Main Library	A	White	Drywall	Southwest Stairwell Wall	Intact	-0.2



TABLE IIA - LEAD BASED PAINT XRF RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2 and 3, 2023

Ind. Hyg.: D. Berman, CDPH I/A, (LRC 00002357)/ R. Dullabaun, MS, CDPH I/A (LRC 00009201)/
R. Medina, CDPH LST (LRC 00002314)/A. Rizo, IHIT

TESTED WITH RADIATION MONITORING DEVICE (RMD) MODEL LPA-1B XRF TYPE ANALYZER (Serial Number1680L)							
Test No.	Location	Side	Color	Substrate	Component	Paint Cond'n	Result mg/cm ²
76	Main Library	C	Brown	Metal	Elevator Door	Intact	0.0
77	Post - Calibration (8/3/23)	--	--	--	--	--	0.8
78	Post - Calibration (8/3/23)	--	--	--	--	--	0.8
79	Post - Calibration (8/3/23)	--	--	--	--	--	0.9
80	Pre - Calibration	--	--	--	--	--	1.0
81	Pre - Calibration	--	--	--	--	--	0.8
82	Pre - Calibration	--	--	--	--	--	0.9
83	Server Room	A	White	Drywall	Wall	Intact	-0.1
84	Server Room	C	White	Wood	Door	Intact	-0.1
85	Server Room	C	White	Metal	Door Frame	Intact	-0.3
86	Post - Calibration	--	--	--	--	--	1.1
87	Post - Calibration	--	--	--	--	--	1.0
88	Post - Calibration	--	--	--	--	--	0.9
Third Floor							
1	Main Library	A	Grey	Metal	Door	Fair	-0.0
2	Main Library	A	Grey	Metal	Window Frame	Intact	-0.5
3	Main Library	B	White	Drywall	Stairwell Wall	Intact	-0.0
4	Main Library	C	Brown	Metal	Elevator Door	Fair	-0.2



TABLE IIA - LEAD BASED PAINT XRF RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2 and 3, 2023

Ind. Hyg.: D. Berman, CDPH I/A, (LRC 00002357)/ R. Dullabaun, MS, CDPH I/A (LRC 00009201)/
R. Medina, CDPH LST (LRC 00002314)/A. Rizo, IHIT

TESTED WITH RADIATION MONITORING DEVICE (RMD) MODEL LPA-1B XRF TYPE ANALYZER (Serial Number1680L)							
Test No.	Location	Side	Color	Substrate	Component	Paint Cond'n	Result mg/cm ²
5	Main Library	C	White	Drywall	Wall	Intact	-0.0
6	Main Library	C	White	Concrete	Column	Intact	-0.1
7	Main Library	C	blue	Wood	Door 1	Intact	-0.2
8	Main Library	C	Orange	Wood	Door 2	Intact	-0.1
9	Main Library	C	blue	Wood	Door 3	Poor	-0.1
10	Main Library	D	Red	Wood	Door 2	Intact	-0.2
11	Main Library	D	White	Drywall	Wall	Intact	-0.0
12	Main Library	D	White	Wood	Cabinet Door	Intact	-0.4
13	Exhibit Space 314	A	White	Drywall	Wall	Intact	-0.2
14	Office 317	A	White	Drywall	Wall	Intact	-0.3
15	Film Developing 316	A	Black	Drywall	Wall	Intact	-0.3
16	Administrative Office	A	White	Concrete	Wall	Intact	-0.1
17	Administrative Office	A	White	Drywall	Wall	Intact	-0.1
18	Administrative Office	A	Grey	Wood	Door	Intact	-0.1
19	Administrative Office	D	White	Drywall	Wall	Intact	-0.5
20	Administrative Office	D	Grey	Metal	Door Jamb	Intact	-0.1
21	Women's Restroom	A	Orange	Ceramic	Wall Tile	Intact	6.4
22	Women's Restroom	B	White	Drywall	Wall	Intact	0.0



TABLE IIA - LEAD BASED PAINT XRF RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2 and 3, 2023

Ind. Hyg.: D. Berman, CDPH I/A, (LRC 00002357)/ R. Dullabaun, MS, CDPH I/A (LRC 00009201)/
R. Medina, CDPH LST (LRC 00002314)/A. Rizo, IHIT

TESTED WITH RADIATION MONITORING DEVICE (RMD) MODEL LPA-1B XRF TYPE ANALYZER (Serial Number1680L)							
Test No.	Location	Side	Color	Substrate	Component	Paint Cond'n	Result mg/cm ²
23	Women's Restroom	B	White	Ceramic	Baseboard Tile	Intact	>9.9
24	Women's Restroom	B	Orange	Wood	Door	Intact	-0.5
25	Women's Restroom	C	White	Ceramic	Wall Tile	Intact	>9.9
26	Women's Restroom	C	White	Porcelain	Sink 1	Intact	-0.4
27	Women's Restroom	C	White	Porcelain	Urinal	Intact	-0.4
28	Women's Restroom	C	Orange	Metal	Divider	Intact	1.0
29	Women's Restroom	C	White	Porcelain	Toilet 1	Intact	-0.4
30	Women's Restroom	C	Orange	Metal	Stall Door 2	Intact	1.0
31	Women's Restroom	--	White	Drywall	Ceiling	Intact	-0.1
32	Men's Restroom	A	White	Ceramic	Wall Tile	Intact	>9.9
33	Men's Restroom	A	White	Porcelain	Toilet	Intact	-0.2
34	Men's Restroom	A	Green	Metal	Stall Door	Fair	0.0
35	Men's Restroom	A	White	Porcelain	Urinal	Intact	-0.6
36	Men's Restroom	A	White	Porcelain	Sink	Intact	-0.3
37	Men's Restroom	A	White	Drywall	Wall	Intact	0.0
38	Men's Restroom	B	Green	Wood	Door	Intact	-0.7
39	Men's Restroom	B	White	Metal	Door Jamb	Intact	-0.2
40	Men's Restroom	C	Green	Ceramic	Wall Tile	Intact	5.9



TABLE IIA - LEAD BASED PAINT XRF RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2 and 3, 2023

Ind. Hyg.: D. Berman, CDPH I/A, (LRC 00002357)/ R. Dullabaun, MS, CDPH I/A (LRC 00009201)/
R. Medina, CDPH LST (LRC 00002314)/A. Rizo, IHIT

TESTED WITH RADIATION MONITORING DEVICE (RMD) MODEL LPA-1B XRF TYPE ANALYZER (Serial Number1680L)							
Test No.	Location	Side	Color	Substrate	Component	Paint Cond'n	Result mg/cm ²
41	Men's Restroom	D	White	Metal	Door Jamb	Intact	-0.4
42	Men's Restroom	D	White	Metal	Door	Intact	-0.1
43	Men's Restroom - Janitor's Closet	A	White	Drywall	Wall	Intact	-0.3
44	Men's Restroom - Janitor's Closet	A	White	Metal	Pipe	Intact	-0.0
45	Men's Restroom - Janitor's Closet	B	White	Drywall	Wall	Intact	-0.3
46	Men's Restroom - Janitor's Closet	B	White	Metal	Pipe	Intact	-0.4
47	Men's Restroom - Janitor's Closet	C	White	Metal	Sink	Intact	>9.9
48	Men's Restroom - Janitor's Closet	C	White	Metal	Drain Valve	Fair	0.1 XRF
PC 2							0.10 WT%
49	Post - Calibration (8/2/23)	--	--	--	--	--	1.0
50	Post - Calibration (8/2/23)	--	--	--	--	--	0.9
51	Post - Calibration (8/2/23)	--	--	--	--	--	1.0
Penthouse							
--	Pre - Calibration	--	--	--	--	--	0.9
--	Pre - Calibration	--	--	--	--	--	0.8
--	Pre - Calibration	--	--	--	--	--	0.8
1	Mechanical Room	B	Yellow	Metal	Railing	Intact	-0.1
2	Mechanical Room	B	Yellow	Metal	Toe Guard	Intact	-0.1



TABLE IIA - LEAD BASED PAINT XRF RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2 and 3, 2023

Ind. Hyg.: D. Berman, CDPH I/A, (LRC 00002357)/ R. Dullabaun, MS, CDPH I/A (LRC 00009201)/
R. Medina, CDPH LST (LRC 00002314)/A. Rizo, IHIT

TESTED WITH RADIATION MONITORING DEVICE (RMD) MODEL LPA-1B XRF TYPE ANALYZER (Serial Number1680L)							
Test No.	Location	Side	Color	Substrate	Component	Paint Cond'n	Result mg/cm ²
3	Mechanical Room	C	Yellow	Metal	HVAC Unit	Intact	-0.2
4	General Area	B	Red	Metal	Drain Pipe	Intact	-0.1
5	General Area	B	Red	Metal	Ladder	Fair	4.8
6	General Area	B	Red	Metal	I - Beam	Intact	-0.1
7	General Area	D	White	Metal	Door	Poor	-0.2
8	General Area	D	White	Metal	Door Frame	Fair	-0.1
9	General Area	D	White	Metal	Wall	Fair	-0.4
10	General Area	B	White	Metal	Roll-up Door Frame	Poor	3.2
11	General Area	B	Blue	Metal	Roll-up Door Frame	Fair	5.6
12	General Area	C	White	Metal	Roll-up door Frame	Poor	-0.1
13	Exterior	A	White	Concrete	Wall	Intact	1.0
14	Exterior	A	White	Metal	Drain Pipe	Intact	0.6
15	Exterior	B	White	Concrete	Outer Wall		1.0
16	Tower	A	Blue	Metal	Door	Fair	-0.1
17	Tower	A	White	Metal	Handrail	Fair	3.1
18	Tower	B	Grey	Concrete	Wall	Intact	-0.4
19	Tower	C	Grey	Metal	Door Frame	Intact	1.0
20	Tower	D	Blue	Metal	Door Jamb	Intact	0.4



TABLE IIA - LEAD BASED PAINT XRF RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2 and 3, 2023

Ind. Hyg.: D. Berman, CDPH I/A, (LRC 00002357)/ R. Dullabaun, MS, CDPH I/A (LRC 00009201)/
R. Medina, CDPH LST (LRC 00002314)/A. Rizo, IHIT

TESTED WITH RADIATION MONITORING DEVICE (RMD) MODEL LPA-1B XRF TYPE ANALYZER (Serial Number1680L)							
Test No.	Location	Side	Color	Substrate	Component	Paint Cond'n	Result mg/cm ²
21	Tower	--	White	Metal	Stairs	Poor	2.5
22	Tower	D	White	Metal	Stair String Board	Intact	4.4
23	Post - Calibration	--	--	--	--	--	1.1
24	Post - Calibration	--	--	--	--	--	1.0
25	Post - Calibration	--	--	--	--	--	0.9
Standards/Guidelines:							
Federal: Guidelines for the Evaluation and Control of Lead-Based Paint Hazards in Housing; Chapter 7, 1997 Revision						LBP	≥ 1.0
State (California): Title 17, California Code of Regulations, Division 1, Chapter 8						LBP	≥ 1.0
Los Angeles County Code: Title 11, Chapter 11.28, Section 11.28.010 C					Dangerous Level of Lead-Bearing Substances		> 0.7
Abbreviations: Side = A, B, C, D - clockwise starting from street front; > = greater than; ≥ = greater than or equal to; ≤ = less than or equal to; - = minus; LBP = Lead Based Paint (bold and shaded); LCP = Lead Containing Paint (bold only); 0.0 = negative (by XRF); Intact = paint that is entirely intact; Fair = ≤ 2 sq. ft (interior) or ≤ 10 sq ft (exterior) of normal wear and tear or direct damage to paint; Poor = severely worn, weathered, no longer adhering (peeling, cracking, flaking, chalking) paint							
NOTE: XRF technology should not be considered reliable for lower concentrations of lead that could still be of concern. Paint chip samples would have to be obtained in order to determine if the paint was lead containing for Cal/OSHA compliance purposes.							
The XRF technology should not be considered reliable for proper classification of waste.							
For multiple components on the same wall side, they are differentiated by being numbered (1, 2, 3, etc.) left to right when facing the components.							



TABLE IIB - LBP and LCP XRF RESULTS

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2 and 3, 2023

Ind. Hyg.: D. Berman, CDPH I/A, (LRC 00002357)/ R. Dullabaun, MS, CDPH I/A (LRC 00009201)/
R. Medina, CDPH LST (LRC 00002314)/A. Rizo, IHIT

TESTED WITH RADIATION MONITORING DEVICE (RMD) MODEL LPA-1B XRF TYPE ANALYZER (Serial Number1680L)							
Test No.	Location	Side	Color	Substrate	Component	Paint Cond'n	Result mg/cm ²
Loading Dock							
3	Double Door Entrance	B	White	Drywall	Wall	Intact	1.8
14	Corridor D - 009	B	White	Drywall	Wall	Intact	2.1
64	Men's Restroom	A	White	Ceramic	Wall Tile	Intact	>9.9
65	Men's Restroom	A	White	Porcelain	Toilet	Intact	1.0
66	Men's Restroom	A	Green	Metal	Stall Door	Fair	0.5
68	Men's Restroom	A	Green	Metal	Wall Divider	Poor	0.4
70	Men's Restroom	B	Green	Ceramic	Wall Tile	Intact	6.7
71	Men's Restroom	C	Green	Ceramic	Wall Tile	Intact	>9.9
74	Men's Restroom	C	White	Ceramic	Baseboard Tile	Intact	>9.9
78	Woman's Restroom	A	White	Ceramic	Wall Tile	Intact	>9.9
80	Woman's Restroom	A	White	Porcelain	Toilet 1	Intact	3.4
81	Woman's Restroom	A	Orange	Metal	Stall Door 1	Fair	0.4
83	Woman's Restroom	A	Orange	Metal	Stall Door 2	Intact	1.0
85	Woman's Restroom	B	White	Ceramic	Baseboard Tile	Intact	>9.9
88	Woman's Restroom	D	Orange	Ceramic	Wall Tile	Intact	6.5
95	Janitor's Closet	B		Metal	Fire Sprinkler Pipe	Poor	0.2 XRF



TABLE IIB - LBP and LCP XRF RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2 and 3, 2023

Ind. Hyg.: D. Berman, CDPH I/A, (LRC 00002357)/ R. Dullabaun, MS, CDPH I/A (LRC 00009201)/
R. Medina, CDPH LST (LRC 00002314)/A. Rizo, IHIT

TESTED WITH RADIATION MONITORING DEVICE (RMD) MODEL LPA-1B XRF TYPE ANALYZER (Serial Number1680L)							
Test No.	Location	Side	Color	Substrate	Component	Paint Cond'n	Result mg/cm ²
PC 1							0.15 WT%
97	Janitor's Closet	C		Porcelain	Sink		>9.9
108	Initial Processing D-021	B	White	Porcelain	Sink	Intact	>9.9
First Floor							
9	Entrance Lobby	--	Brown	Ceramic	Floor Tile	Intact	>9.9
10	Entrance Lobby - Women's Restroom	A	Orange	Ceramic	Wall Tile	Intact	6.2
11	Entrance Lobby - Women's Restroom	B	White	Ceramic	Wall Tile	Intact	>9.9
15	Entrance Lobby - Women's Restroom	C	White	Porcelain	Sink 1	Intact	0.4
17	Entrance Lobby - Women's Restroom	C	White	Ceramic	Baseboard Tile	Intact	>9.9
21	Entrance Lobby - Men's Restroom	A	White	Ceramic	Wall Tile	Intact	>9.9
22	Entrance Lobby - Men's Restroom	A	White	Porcelain	Sink	Intact	0.5
29	Entrance Lobby - Men's Restroom	C	Green	Ceramic	Wall Tile	Intact	6.6
33	Entrance Lobby - Men's Restroom - Janitor's Closet	A	White	Metal	Sink	Fair	>9.9
34	Entrance Lobby - Men's Restroom - Janitor's Closet	A	White	Metal	Drain Pipe	Poor	0.3 XRF
PC 3							0.18 WT%
52	Children's Library	D	Blue	Wood	Door 1	Fair	0.1 XRF
PC 4							0.08 WT%
64	Children's Library - Boy's Restroom	A	Green	Ceramic	Wall Tile	Intact	6.3



TABLE IIB - LBP and LCP XRF RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2 and 3, 2023

Ind. Hyg.: D. Berman, CDPH I/A, (LRC 00002357)/ R. Dullabaun, MS, CDPH I/A (LRC 00009201)/
R. Medina, CDPH LST (LRC 00002314)/A. Rizo, IHIT

TESTED WITH RADIATION MONITORING DEVICE (RMD) MODEL LPA-1B XRF TYPE ANALYZER (Serial Number1680L)							
Test No.	Location	Side	Color	Substrate	Component	Paint Cond'n	Result mg/cm ²
65	Children's Library - Boy's Restroom	B	White	Ceramic	Wall Tile	Intact	>9.9
73	Children's Library - Girls Restroom	A	White	Ceramic	Wall Tile	Intact	>9.9
76	Children's Library - Girls Restroom	C	Orange	Ceramic	Wall Tile	Intact	6.5
90	Book Trucks/Office Area	D	White	Metal	Sink	Intact	>9.9
97	Book Trucks/Office Area - Men's Restroom	A	White	Ceramic	Wall Tile	Intact	>9.9
99	Book Trucks/Office Area - Men's Restroom	C	Green	Ceramic	Wall Tile	Intact	5.6
102	Book Trucks/Office Area - Men's Restroom	D	Green	Metal	Stall Door	Intact	1.0
105	Book Trucks/Office Area - Women's Restroom	A	White	Ceramic	Wall Tile	Intact	>9.9
108	Book Trucks/Office Area - Women's Restroom	C	Orange	Ceramic	Wall Tile	Intact	6.3
Second Floor							
9	Women's Restroom	A	White	Ceramic	Wall Tile	Intact	>9.9
11	Women's Restroom	A	Green	Metal	Stall Door 2	Intact	1.0
22	Women's Restroom	B	White	Ceramic	Baseboard Tile	Intact	>9.9
24	Women's Restroom	C	Green	Ceramic	Wall Tile	Intact	4.2
25	Women's Restroom	D	White	Ceramic	Wall Tile	Intact	>9.9
49	Men's Restroom	A	Orange	Ceramic	Wall Tile	Intact	5.0
51	Men's Restroom	B	White	Ceramic	Baseboard Tile	Intact	>9.9
55	Men's Restroom	C	White	Ceramic	Wall Tile	Intact	>9.9



TABLE IIB - LBP and LCP XRF RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2 and 3, 2023

Ind. Hyg.: D. Berman, CDPH I/A, (LRC 00002357)/ R. Dullabaun, MS, CDPH I/A (LRC 00009201)/
R. Medina, CDPH LST (LRC 00002314)/A. Rizo, IHIT

TESTED WITH RADIATION MONITORING DEVICE (RMD) MODEL LPA-1B XRF TYPE ANALYZER (Serial Number1680L)							
Test No.	Location	Side	Color	Substrate	Component	Paint Cond'n	Result mg/cm²
57	Men's Restroom	C	Orange	Metal	Stall Door 1	Intact	0.4
60	Men's Restroom	D	White	Ceramic	Wall Tile	Intact	>9.9
Third Floor							
21	Women's Restroom	A	Orange	Ceramic	Wall Tile	Intact	6.4
23	Women's Restroom	B	White	Ceramic	Baseboard Tile	Intact	>9.9
25	Women's Restroom	C	White	Ceramic	Wall Tile	Intact	>9.9
28	Women's Restroom	C	Orange	Metal	Divider	Intact	1.0
30	Women's Restroom	C	Orange	Metal	Stall Door 2	Intact	1.0
32	Men's Restroom	A	White	Ceramic	Wall Tile	Intact	>9.9
40	Men's Restroom	C	Green	Ceramic	Wall Tile	Intact	5.9
47	Men's Restroom - Janitor's Closet	C	White	Metal	Sink	Intact	>9.9
48	Men's Restroom - Janitor's Closet	C	White	Metal	Drain Valve	Fair	0.1 XRF
PC 2							0.10 WT%
Penthouse							
5	General Area	B	Red	Metal	Ladder	Fair	4.8
10	General Area	B	White	Metal	Roll-up Door Frame	Poor	3.2
11	General Area	B	Blue	Metal	Roll-up Door Frame	Fair	5.6
13	Exterior	A	White	Concrete	Wall	Intact	1.0



TABLE IIB - LBP and LCP XRF RESULTS - Continued

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2 and 3, 2023

Ind. Hyg.: D. Berman, CDPH I/A, (LRC 00002357)/ R. Dullabaun, MS, CDPH I/A (LRC 00009201)/
R. Medina, CDPH LST (LRC 00002314)/A. Rizo, IHIT

TESTED WITH RADIATION MONITORING DEVICE (RMD) MODEL LPA-1B XRF TYPE ANALYZER (Serial Number1680L)							
Test No.	Location	Side	Color	Substrate	Component	Paint Cond'n	Result mg/cm ²
14	Exterior	A	White	Metal	Drain Pipe	Intact	0.6
15	Exterior	B	White	Concrete	Outer Wall		1.0
17	Tower	A	White	Metal	Handrail	Fair	3.1
19	Tower	C	Grey	Metal	Door Frame	Intact	1.0
20	Tower	D	Blue	Metal	Door Jamb	Intact	0.4
21	Tower	--	White	Metal	Stairs	Poor	2.5
22	Tower	D	White	Metal	Stair String Board	Intact	4.4
Standards/Guidelines:							
Federal: Guidelines for the Evaluation and Control of Lead-Based Paint Hazards in Housing; Chapter 7, 1997 Revision						LBP	≥ 1.0
State (California): Title 17, California Code of Regulations, Division 1, Chapter 8						LBP	≥ 1.0
Los Angeles County Code: Title 11, Chapter 11.28, Section 11.28.010 C					Dangerous Level of Lead-Bearing Substances		> 0.7
Abbreviations: Side = A, B, C, D - clockwise starting from street front; > = greater than; ≥ = greater than or equal to; ≤ = less than or equal to; - = minus; LBP = Lead Based Paint (bold and shaded); LCP = Lead Containing Paint (bold only); 0.0 = negative (by XRF); Intact = paint that is entirely intact; Fair = ≤ 2 sq. ft (interior) or ≤ 10 sq ft (exterior) of normal wear and tear or direct damage to paint; Poor = severely worn, weathered, no longer adhering (peeling, cracking, flaking, chalking) paint							



TESTED WITH RADIATION MONITORING DEVICE (RMD) MODEL LPA-1B XRF TYPE ANALYZER (Serial Number1680L)							
<i>Test No.</i>	<i>Location</i>	<i>Side</i>	<i>Color</i>	<i>Substrate</i>	<i>Component</i>	<i>Paint Cond'n</i>	<i>Result mg/cm²</i>
<p>NOTE: XRF technology should not be considered reliable for lower concentrations of lead that could still be of concern. Paint chip samples would have to be obtained in order to determine if the paint was lead containing for Cal/OSHA compliance purposes.</p> <p>The XRF technology should not be considered reliable for proper classification of waste.</p> <p>For multiple components on the same wall side, they are differentiated by being numbered (1, 2, 3, etc.) left to right when facing the components.</p>							



TABLE III - LEAD BASED PAINT RESULTS

HSA Project Number: 230201LA

Project: Griffith Structures, Inglewood Library, 101 W. Manchester Blvd., Inglewood, CA 90301

Date: August 2 and 3, 2023

Ind. Hyg.: D. Berman, CDPH I/A, (LRC 00002357)/
R. Dullabaun, MS, CDPH I/A (LRC 00009201)/
R. Medina, CDPH LST (LRC 00002314)/A. Rizo, IHIT

Sample Number	Locatio/XRF Measurement Sample Number	XRF Result mg/cm ²	Laboratory Results Lead WT% or ppm	
PC - 1	XRF Measurement 95 - Loading Doc	0.2	0.15 WT%	
PC - 2	XRF Measurement 48 - 3 rd Floor	0.1	0.10 WT%	
PC - 3	XRF Measurement 34 - 1 st Floor	0.3	0.18 WT%	
PC - 4	XRF Measurement 52 - 1 st Floor	0.1	0.08 WT%	
Standards/Guidelines				
Consumer Products Safety Commission, August 2009			0.009	90 ppm
CDPH/HUD Guidelines, June, 1995			0.5	≥ 5,000 ppm
Analytical Method: EPA method 6010/EPA method 3050B/7000B				
Abbreviations: WT% = weight by percent; ppm - parts per million; < = less than; ≥ = greater than or equal to; mg/cm ² = milligrams per centimeter squared; XRF = Xray Fluorescence; LBP = Lead Based Paint; LCP = Lead Containing Paint; bold/shade = LBP; bold = LCP				

Appendix A - Laboratory Reports



Bulk Asbestos Analysis

(EPA Method 40CFR, Part 763, Appendix E to Subpart E and EPA 600/R-93-116, Visual Area Estimation)

NVLAP Lab Code: 101459-1

Health Science Associates
Joel Berman
10771 Noel Street

Los Alamitos, CA 90720

Client ID: L1596
Report Number: B350499
Date Received: 08/04/23
Date Analyzed: 08/11/23
Date Printed: 08/11/23
First Reported: 08/11/23

Job ID/Site: 230201LA; Griffith Structures; 101 W Manchester Blvd, Inglewood, CA, 90301

SGSFL Job ID: L1596
Total Samples Submitted: 15
Total Samples Analyzed: 15

Date(s) Collected: 08/03/2023

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
P-230803-01A	51680912						
Layer: Brown Drywall			ND				
Layer: Off-White Joint Compound		Chrysotile	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (10 %)	Fibrous Glass (Trace)						
Comment: This comment applies to the Off-White Joint Compound only: Insufficient material for additional analyses.							
P-230803-01B	51680913						
Layer: Brown Drywall			ND				
Layer: Off-White Joint Compound		Chrysotile	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (10 %)	Fibrous Glass (Trace)						
P-230803-01C	51680914						
Layer: Brown Drywall			ND				
Layer: Off-White Joint Compound		Chrysotile	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (10 %)	Fibrous Glass (Trace)						
Comment: This comment applies to the Off-White Joint Compound only: Insufficient material for additional analyses.							
P-230803-02A	51680915						
Layer: Beige Cementitious Material			ND				
Layer: Brown Fibrous Mat'l with Debris			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)	Fibrous Glass (45 %)						
P-230803-02B	51680916						
Layer: Beige Cementitious Material			ND				
Layer: Brown Fibrous Mat'l with Debris			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)	Fibrous Glass (45 %)						

Client Name: Health Science Associates

Report Number: B350499

Date Printed: 08/11/23

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
P-230803-02C		51680917					
Layer: Brown Drywall						ND	
Layer: Off-White Joint Compound		Chrysotile		Trace			
Layer: Beige Cementitious Material				ND			
Layer: Brown Fibrous Mat'l with Debris				ND			
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)	Fibrous Glass (45 %)						
Comment: This comment applies to the Off-White Joint Compound only: Insufficient material for additional analyses.							
P-230803-03A		51680918					
Layer: Yellow Fibrous Material						ND	
Layer: White Woven Material w/ Foil						ND	
Layer: White Fibrous Material w/ Adhesive						ND	
Layer: Tan Fibrous Material						ND	
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (35 %)	Fibrous Glass (15 %)						
P-230803-03B		51680919					
Layer: Yellow Fibrous Material						ND	
Layer: White Woven Material w/ Foil						ND	
Layer: White Fibrous Material w/ Adhesive						ND	
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (50 %)	Fibrous Glass (15 %)						
P-230803-03C		51680920					
Layer: White Woven Material w/ Foil						ND	
Layer: Tan Fibrous Material w/ Adhesive						ND	
Layer: White Non-Fibrous Material						ND	
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (50 %)	Fibrous Glass (10 %)						
P-230803-04A		51680921					
Layer: Yellow Fibrous Material						ND	
Layer: White Woven Material w/ Foil						ND	
Layer: Tan Fibrous Material w/ Adhesive						ND	
Layer: White Non-Fibrous Material						ND	
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (50 %)	Fibrous Glass (10 %)						
P-230803-04B		51680922					
Layer: Yellow Fibrous Material						ND	
Layer: White Woven Material w/ Foil						ND	
Layer: Tan Fibrous Material w/ Adhesive						ND	
Layer: White Non-Fibrous Material						ND	
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (50 %)	Fibrous Glass (10 %)						

Client Name: Health Science Associates

Report Number: B350499

Date Printed: 08/11/23

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
P-230803-04C	51680923						
Layer: Yellow Fibrous Material			ND				
Layer: White Woven Material w/ Foil			ND				
Layer: Tan Fibrous Material w/ Adhesive			ND				
Layer: White Non-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (35 %) Fibrous Glass (10 %)							
P-230803-05A	51680924						
Layer: White Woven Material			ND				
Layer: Black Non-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace) Fibrous Glass (80 %)							
P-230803-05B	51680925						
Layer: White Woven Material			ND				
Layer: Black Non-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace) Fibrous Glass (95 %)							
P-230803-05C	51680926						
Layer: White Woven Material			ND				
Layer: Black Non-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace) Fibrous Glass (80 %)							



Tiffani Ludd, Laboratory Supervisor, Carson Laboratory

Note: Limit of Quantification ('LOQ') = 1%. 'Trace' denotes the presence of asbestos below the LOQ. 'ND' = 'None Detected'.

Analytical results and reports are generated by SGS Forensic Laboratories (SGSFL) at the request of and for the exclusive use of the person or entity (client) named on such report. Results, reports or copies of same will not be released by SGSFL to any third party without prior written request from client. This report applies only to the sample(s) tested. Supporting laboratory documentation is available upon request. This report must not be reproduced except in full, unless approved by SGSFL. The client is solely responsible for the use and interpretation of test results and reports requested from SGSFL. This report must not be used by the client to claim product endorsement by NVLAP or any other agency of the U.S. Government. SGSFL is not able to assess the degree of hazard resulting from materials analyzed. SGS Forensic Laboratories reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified. All samples were received in acceptable condition unless otherwise noted.



10771 Noel Street • Los Alamitos, CA 90720

Office: (714) 220-3922 • Fax: (714) 220-2081

Page 1 of 3E-mail results to: labresults@healthscience.comdsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET

FLOOR (circle one)

LD

1

2

3

PENTHOUSE

ROOF

Project #: 230201LA

Date: 8/3/2023

TAT

Project Manager: Joel Berman

Industrial Hygienist: Devin Berman

Rodica Dullabaun

Client: Griffith Structures

Rene Medina

Anahi Rizo-Zhang

Project Location: 101 W Manchester Blvd

Inglewood, CA 90301

Comments:

5 day

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
P-230803-01A	Drywall, mud & tape	Penthouse	Generic Room / South Room NW corner	F (M) TSI NF SC	D SD G	21000 ft ²	
01B			E wall, North	F (M) TSI NF SC	D SD G		
01C			E wall, South	F (M) TSI NF SC	D SD G		
02A	Debris pile	Debris Pile		F (M) TSI NF SC	D SD G	250 ft ²	
02B				F (M) TSI NF SC	D SD G		
02C				F (M) TSI NF SC	D SD G		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Vermin Controll 8/1/23 10:00am DC

Relinquished by: <i>Devin Berman</i>	Date: 8/1/23	Time: 10:15	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:



10771 Noel Street • Los Alamitos, CA 90720

Office: (714) 220-3922 • Fax: (714) 220-2081

Page 2 of 3E-mail results to: labresults@healthscience.comdsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET

FLOOR (circle one)

LD 1 2 3

PENTHOUSE

ROOF

Project #: 230201LA

Date: 8/3/2023

TAT

Project Manager: Joel Berman

Industrial Hygienist: Devin Berman

Rodica Dullabaun

Client: Griffith Structures

Rene Medina

Anahi Rizo-Zhang

Project Location: 101 W Manchester Blvd

Inglewood, CA 90301

Comments:

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
P-230803-03A	TSI wrap	Penthouse off piping	Center of Room	F TSI M SM SD	D	3002F	
03B				NF SC TSI M SM SD	G		
03C				F TSI M SM SD	D		
03D	TSI hard pack covering			NF SC TSI M SM SD	G	30LF	
04B				F TSI M SM SD	D		
04C				NF SC TSI M SM SD	G		

Type:

Condition:

Labeling:

Quantity:

F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Sergio Contreras 8-423 10:00 am DCU

Relinquished by: [Signature]
Relinquished by: [Signature]
Relinquished by: [Signature]Date: 8/4/23
Date:
Date:Time: 10:15
Time:
Time:Received by:
Received by:
Received by:Date:
Date:
Date:Time:
Time:
Time:

DS = ~~Deep~~ Deep Dust Vibration Cloth



10771 Noel Street • Los Alamitos, CA 90720

Office: (714) 220-3922 • Fax: (714) 220-2081

Page 3 of 3E-mail results to: labresults@healthscience.comdsberman@heejanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET				FLOOR (circle one)	LD	1	2	3	PENTHOUSE	ROOF	
TAT <i>5day</i>	Project Manager:	Joel Berman			Project #: 230201LA					Date: 8/3/2023	
	Client:	Griffith Structures			Industrial Hygienist: Devin Berman					Rodica Dullabaun	
	Project Location:	101 W Manchester Blvd Inglewood, CA 90301			Rene Medina					Anahi Rizo-Zhang	
				Comments:							

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
P-230803-05A	Vibration Dampening Cloth	Penthouse	N area	F TSI M SC	D SD G	3-4 Total	
05B			W area	F TSI M SC	D SD G		
05C			S area	F TSI M SC	D SD G		
				F TSI M SC	D SD G		
				F TSI M SC	D SD G		
				F TSI M SC	D SD G		
				F TSI M SC	D SD G		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Relinquished by: <i>Devin Berman</i>	Date: 8/4/23	Time: 1015	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:



Bulk Asbestos Analysis

(EPA Method 40CFR, Part 763, Appendix E to Subpart E and EPA 600/R-93-116, Visual Area Estimation)

NVLAP Lab Code: 101459-1

Health Science Associates
Joel Berman
10771 Noel Street

Los Alamitos, CA 90720

Client ID: L1596
Report Number: B350562
Date Received: 08/04/23
Date Analyzed: 08/11/23
Date Printed: 08/11/23
First Reported: 08/11/23

Job ID/Site: 230201LA; Griffith Structures, 101 W Manchester Blvd, Inglewood, CA 90301

SGSFL Job ID: L1596
Total Samples Submitted: 29
Total Samples Analyzed: 29

Date(s) Collected: 08/02/2023, 08/03/2023, 08/04/2023

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
M-230802-01A	51681536						
Layer: Brown Flooring			ND				
Layer: Off-White Woven Material			ND				
Layer: Clear/Tan Mastic			ND				
Layer: Grey Non-Fibrous Material			ND				
Layer: Brown Mastic		Chrysotile	2 %				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)		Synthetic (5 %)					
M-230802-01B	51681537						
Layer: Brown Flooring			ND				
Layer: Off-White Woven Material			ND				
Layer: Clear/Tan Mastic			ND				
Layer: Beige Non-Fibrous Material			ND				
Layer: Brown Mastic		Chrysotile	2 %				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)		Synthetic (5 %)					
M-230802-01C	51681538						
Layer: Brown Flooring			ND				
Layer: Off-White Woven Material			ND				
Layer: Clear/Tan Mastic			ND				
Layer: Beige Non-Fibrous Material			ND				
Layer: Brown Mastic		Chrysotile	2 %				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)		Synthetic (5 %)					
M-230803-02A	51681539						
Layer: Dark Grey Mortar			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
M-230803-02B	51681540						
Layer: Grey Cementitious Material			ND				
Layer: Dark Grey Mortar			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							

Client Name: Health Science Associates

Report Number: B350562

Date Printed: 08/11/23

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
M-230803-02C	51681541						
Layer: Dark Grey Mortar			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
M-230803-02D	51681542						
Layer: Dark Grey Mortar			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
M-230803-02E	51681543						
Layer: Dark Grey Mortar			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
M-230803-03A	51681544						
Layer: Light Grey Cementitious Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
M-230803-03B	51681545						
Layer: Grey Cementitious Material			ND				
Layer: Light Grey Cementitious Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
M-230803-03C	51681546						
Layer: Grey Cementitious Material			ND				
Layer: Light Grey Cementitious Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
M-230803-03D	51681547						
Layer: Light Grey Cementitious Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
M-230803-03E	51681548						
Layer: Grey Cementitious Material			ND				
Layer: Light Grey Cementitious Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
M-230804-05A	51681549						
Layer: Stones			ND				
Layer: Black Tar			ND				
Layer: Black Felt			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)	Fibrous Glass (10 %)						

Client Name: Health Science Associates

Report Number: B350562

Date Printed: 08/11/23

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
M-230804-05B	51681550						
Layer: Stones			ND				
Layer: Black Tar			ND				
Layer: Black Felt			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)	Fibrous Glass (10 %)						
M-230804-05C	51681551						
Layer: Stones			ND				
Layer: Black Tar			ND				
Layer: Black Felt			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)	Fibrous Glass (10 %)						
M-230804-06A	51681552						
Layer: Off-White Non-Fibrous Material			ND				
Layer: Tan Mastics			ND				
Layer: Off-White Woven Material			ND				
Layer: Black Tars			ND				
Layer: Black Felts			ND				
Layer: Beige Semi-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %)	Fibrous Glass (5 %)	Synthetic (5 %)					
M-230804-06B	51681553						
Layer: Off-White Non-Fibrous Material			ND				
Layer: Tan Mastics			ND				
Layer: Off-White Woven Material			ND				
Layer: Black Tars			ND				
Layer: Black Felts			ND				
Layer: Beige Semi-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %)	Fibrous Glass (5 %)	Synthetic (5 %)					
M-230804-06C	51681554						
Layer: Off-White Non-Fibrous Material			ND				
Layer: Tan Mastics			ND				
Layer: Off-White Woven Material			ND				
Layer: Black Tars			ND				
Layer: Black Felts			ND				
Layer: Beige Semi-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %)	Fibrous Glass (5 %)	Synthetic (5 %)					

Client Name: Health Science Associates

Report Number: B350562

Date Printed: 08/11/23

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
M-230804-06D	51681555						
Layer: Off-White Non-Fibrous Material			ND				
Layer: Tan Mastics			ND				
Layer: Off-White Woven Material			ND				
Layer: Black Tars			ND				
Layer: Black Felts			ND				
Layer: Beige Semi-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %)	Fibrous Glass (5 %)	Synthetic (5 %)					
M-230804-06E	51681556						
Layer: Off-White Non-Fibrous Material			ND				
Layer: Tan Mastics			ND				
Layer: Off-White Woven Material			ND				
Layer: Black Tars			ND				
Layer: Black Felts			ND				
Layer: Beige Semi-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %)	Fibrous Glass (5 %)	Synthetic (5 %)					
M-230804-06F	51681557						
Layer: Off-White Non-Fibrous Material			ND				
Layer: Tan Mastics			ND				
Layer: Off-White Woven Material			ND				
Layer: Black Tars			ND				
Layer: Black Felts			ND				
Layer: Beige Semi-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %)	Fibrous Glass (5 %)	Synthetic (5 %)					
M-230804-06G	51681558						
Layer: Off-White Non-Fibrous Material			ND				
Layer: Tan Mastics			ND				
Layer: Off-White Woven Material			ND				
Layer: Black Tars			ND				
Layer: Black Felts			ND				
Layer: Beige Semi-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %)	Fibrous Glass (5 %)	Synthetic (5 %)					
M-230804-07A	51681559						
Layer: Off-White Non-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
M-230804-07B	51681560						
Layer: Off-White Non-Fibrous Material			ND				
Layer: Black Semi-Fibrous Tar			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (2 %)							

Client Name: Health Science Associates

Report Number: B350562

Date Printed: 08/11/23

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
M-230804-07C	51681561						
Layer: Off-White Non-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
M-230802-08A	51681562						
Layer: Red Carpet			ND				
Layer: Beige Fibrous Material			ND				
Layer: Brown Mastic		Chrysotile	2 %				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)	Synthetic (90 %)						
M-230802-08B	51681563						
Layer: Red Carpet			ND				
Layer: Beige Fibrous Material			ND				
Layer: Brown Mastic		Chrysotile	2 %				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)	Synthetic (90 %)						
M-230802-08C	51681564						
Layer: Red Carpet			ND				
Layer: Beige Fibrous Material			ND				
Layer: Tan Mastic			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)	Synthetic (90 %)						



Tiffani Ludd, Laboratory Supervisor, Carson Laboratory

Note: Limit of Quantification ('LOQ') = 1%. 'Trace' denotes the presence of asbestos below the LOQ. 'ND' = 'None Detected'.

Analytical results and reports are generated by SGS Forensic Laboratories (SGSFL) at the request of and for the exclusive use of the person or entity (client) named on such report. Results, reports or copies of same will not be released by SGSFL to any third party without prior written request from client. This report applies only to the sample(s) tested. Supporting laboratory documentation is available upon request. This report must not be reproduced except in full, unless approved by SGSFL. The client is solely responsible for the use and interpretation of test results and reports requested from SGSFL. This report must not be used by the client to claim product endorsement by NVLAP or any other agency of the U.S. Government. SGSFL is not able to assess the degree of hazard resulting from materials analyzed. SGS Forensic Laboratories reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified. All samples were received in acceptable condition unless otherwise noted.

E-mail results to: labresults@healthscience.comdsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET		FLOOR (circle one)	LD	1	2	3	PENTHOUSE	ROOF
TAT <i>Today</i>	Project Manager:	Joel Berman		Project #:			230201LA	
	Client:	Griffith Structures		Industrial Hygienist:			Devin Berman	
	Project Location:	101 W Manchester Blvd Inglewood, CA 90301		Rene Medina			Anahi Rizo-Zhang	
				Date: 8/1/2023				
				Comments:				

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
M-230802-01A	Brown rubber flashing & mastic	Staff elevator cap	NE corner	F TSI M SC	D SD G	130 ft ²	
01B			SE corner	F TSI M SC	D SD G		
01C			SW corner	F TSI M SC	D SD G		
M-230803-02A	Concrete block mortar	Exterior	SW corner	F TSI M SC	D SD G	5,000 ft ²	
02B			At South Exit door	F TSI M SC	D SD G		
02C			SE corner	F TSI M SC	D SD G		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Relinquished by: <i>Devin Berman</i>	Date: 8/1/23	Time: 10:15	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

Valmire Contreras 8-1-23 10:00am

E-mail results to: labresults@healthscience.comdsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET		FLOOR (circle one)	LD	1	2	3	PENTHOUSE	ROOF
TAT 5 day	Project Manager:	Joel Berman		Project #:			230201LA	
	Client:	Griffith Structures		Industrial Hygienist:			Devin Berman	
	Project Location:	101 W Manchester Blvd Inglewood, CA 90301		Rene Medina			Anahi Rizo-Zhang	
			Comments:					
Date:		8/3/2023						

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
M-230803 02D	Concrete block mortar	Exterior	NE corner	F TSI M SC NF	D SD G	5,000ft ²	
02E			At North Exit double door	F TSI M SC NF	D SD G		
M-230803 03A	Stucco	Loading Dock	Stairwell, behind door	F TSI M SC NF	D SD G	3,000ft ²	
03B		1st Floor landing	N stairwell (stuff) E wall	F TSI M SC NF	D SD G		
03C		3rd Floor landing	N stairwell (stuff) E wall, at base	F TSI M SC NF	D SD G		
03D		2nd Floor at	At door to Staff Offices	F TSI M SC NF	D SD G		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Relinquished by: <i>Devin Berman</i>	Date: <i>8/14/23</i>	Time: <i>10:15</i>	Received by: <i>Veronica Contreras</i>	Date: <i>8-14-23</i>	Time: <i>10:00am</i>
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

E-mail results to: labresults@healthscience.comdsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET		FLOOR (circle one)	LD	1	2	3	PENTHOUSE	ROOF
TAT 5 day	Project Manager:	Joel Berman		Project #:			230201LA	
	Client:	Griffith Structures		Industrial Hygienist:			Devin Berman	
	Project Location:	101 W Manchester Blvd Inglewood, CA 90301		Rene Medina			Anahi Rizo-Zhang	
				Date: 8/3-4 /2023				
				Comments:				

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
M-230803 ↓ 03E	Stucco	Exterior - NO ACCESS INTERIOR - Between 1st and 2nd Floors	At landing, at base of the wall	F TSI M SC NF	D SD G	3000 ft ²	
↓ 04A	Mirror Mastic	In Restrooms	Throughout Assumed, not sampled	F TSI M SC NF	D SD G	12 total	
M-230804 - ↓ 05A	Walking Pads	Lower Roof	NE Corner	F TSI M SC NF	D SD G	<1000 ft ²	
↓ 05B			NW Corner	F TSI M SC NF	D SD G		
↓ 05C			SW Corner	F TSI M SC NF	D SD G		
↓ 06A	Roofing Wre	Lower Roof	SE Corner	F TSI M SC NF	D SD G	75,000 ft ²	

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

VATMINE CONCRETE 8-4-23 10:09 am DU

Relinquished by: <u>Devin Berman</u>	Date: <u>8/4/23</u>	Time: <u>1015</u>	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

E-mail results to: labresults@healthscience.comdsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET		FLOOR (circle one)	LD	1	2	3	PENTHOUSE	ROOF
TAT <i>5 day</i>	Project Manager:	Joel Berman		Project #:			230201LA	
	Client:	Griffith Structures		Industrial Hygienist:			Devin Berman	
	Project Location:	101 W Manchester Blvd Inglewood, CA 90301		Rene Medina			Anahi Rizo-Zhang	
				Date: 8/4/2023				
				Comments:				

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
M-230804-	Roofing Core	Lower Roof	S wall center	F TSI NF M	SM SD	5,000ft ²	
			SW corner	F TSI NF M	SM SD		
			NW corner	F TSI NF M	SM SD		
			NE corner	F TSI NF M	SM SD		
			W side	F TSI NF M	SM SD		
			E side	F TSI NF M	SM SD		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Relinquished by: <i>Devin Berman</i>	Date: <i>8/4/23</i>	Time: <i>10:15</i>	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

Valmire Contreras 8-4-23 10:00am

E-mail results to: labresults@healthscience.comdsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET		FLOOR (circle one)	LD	1	2	3	PENTHOUSE	ROOF
TAT <i>5 days</i>	Project Manager:	Joel Berman		Project #:			230201LA	
	Client:	Griffith Structures		Industrial Hygienist:			Devin Berman	
	Project Location:	101 W Manchester Blvd Inglewood, CA 90301		Rene Medina			Anahi Rizo-Zhang	
	Comments:							

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
M-230804- OTA	Roofing/Penetration Mastic	Lower SW corner Roof	at eyehook	F TSI M SC (NF)	D SD (G)	21000 ft ²	
OTB		N side	at spout/drain	F TSI M SC (NF)	D SD (G)		
OTC		NW corner	at penthouse base	F TSI M SC (NF)	D SD (G)		
M-230802- OSA	Carpet mastic under red carpet	stairs from LD to 1		F TSI M SC (NF)	D SD (G)	<1000 ft ²	
OSB				F TSI M SC (NF)	D SD (G)		
OSC				F TSI M SC (NF)	D SD (G)		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Relinquished by: <i>Devin Berman</i>	Date: <i>8/14/23</i>	Time: <i>10:15</i>	Received by: <i>Devin Berman</i>	Date: <i>8/14/23</i>	Time: <i>10:00 am</i>
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

Bulk Asbestos Analysis

(EPA Method 40CFR, Part 763, Appendix E to Subpart E and EPA 600/R-93-116, Visual Area Estimation)

NVLAP Lab Code: 101459-1

Health Science Associates
Joel Berman
10771 Noel Street

Los Alamitos, CA 90720

Client ID: L1596
Report Number: B350566
Date Received: 08/04/23
Date Analyzed: 08/11/23
Date Printed: 08/11/23
First Reported: 08/11/23

Job ID/Site: 230201LA; Griffith Structures, 101 W Manchester Blvd, Inglewood, CA 90301

SGSFL Job ID: L1596
Total Samples Submitted: 40
Total Samples Analyzed: 40

Date(s) Collected: 08/02/2023

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
1-230802-01A	51681572						
Layer: White Drywall			ND				
Layer: Off-White Joint Compound		Chrysotile	2 %				
Layer: Paint			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Layer: Tan Mastic			ND				
Layer: Grey Cementitious Material			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (5 %) Fibrous Glass (Trace)							
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							
1-230802-01B	51681573						
Layer: White Drywall			ND				
Layer: Off-White Joint Compound		Chrysotile	2 %				
Layer: Off-White Non-Fribrous Material			ND				
Layer: Paint			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Layer: Tan Mastic			ND				
Total Composite Values of Fibrous Components:		Asbestos (2%)					
Cellulose (Trace) Fibrous Glass (Trace)							
Comment: This commetn applies to the Brown Mastic only: Insufficient material for additional analyses.							
1-230802-01C	51681574						
Layer: White Drywall			ND				
Layer: Off-White Joint Compound		Chrysotile	2 %				
Layer: Paint			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Layer: Tan Mastic			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace) Fibrous Glass (Trace)							
Comment: This commetn applies to the Brown Mastic only: Insufficient material for additional analyses.							
1-230802-02A	51681575						
Layer: Tan Mastic with Debris		Chrysotile	2 %				
Total Composite Values of Fibrous Components:		Asbestos (2%)					
Cellulose (Trace)							

Client Name: Health Science Associates

Report Number: B350566

Date Printed: 08/11/23

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
1-230802-02B	51681576						
Layer: Tan Mastic with Debris		Chrysotile	2 %				
Total Composite Values of Fibrous Components:		Asbestos (2%)					
Cellulose (Trace)							
1-230802-02C	51681577						
Layer: Tan Mastic with Debris		Chrysotile	2 %				
Total Composite Values of Fibrous Components:		Asbestos (2%)					
Cellulose (Trace)							
1-230802-02D	51681578						
Layer: Tan Fibrous Material			ND				
Layer: Tan Mastic with Debris		Chrysotile	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)		Synthetic (7 %)					
Comment: This comment applies to the Tan Mastic with Debris only: Insufficient material for additional analyses.							
1-230802-02E	51681579						
Layer: Tan Mastic with Debris		Chrysotile	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)		Synthetic (7 %)					
Comment: This comment applies to the Tan Mastic with Debris only: Insufficient material for additional analyses.							
1-230802-02F	51681580						
Layer: Tan Mastic with Debris		Chrysotile	2 %				
Total Composite Values of Fibrous Components:		Asbestos (2%)					
Cellulose (Trace)							
1-230802-02G	51681581						
Layer: Tan Mastic with Debris		Chrysotile	2 %				
Total Composite Values of Fibrous Components:		Asbestos (2%)					
Cellulose (Trace)							
1-230802-03A	51681582						
Layer: Brown Non-Fibrous Material			ND				
Layer: Clear Mastic			ND				
Layer: Black Non-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
1-230802-03B	51681583						
Layer: Brown Non-Fibrous Material			ND				
Layer: Clear Mastic			ND				
Layer: Black Non-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							

Client Name: Health Science Associates

Report Number: B350566

Date Printed: 08/11/23

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
1-230802-04A	51681584						
Layer: Brown Non-Fibrous Material			ND				
Layer: Tan Mastic			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Layer: Paint			ND				
Layer: Off-White Joint Compound		Chrysotile	2 %				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							
1-230802-04B	51681585						
Layer: Brown Non-Fibrous Material			ND				
Layer: Tan Mastic			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							
1-230802-04C	51681586						
Layer: Brown Non-Fibrous Material			ND				
Layer: Tan Mastic			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							
1-230802-05A	51681587						
Layer: Black Non-Fibrous Material with Paint			ND				
Layer: Tan Mastic			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Layer: Off-White Joint Compound		Chrysotile	2 %				
Total Composite Values of Fibrous Components:		Asbestos (2%)					
Cellulose (Trace)							
1-230802-05B	51681588						
Layer: Black Non-Fibrous Material with Paint			ND				
Layer: Tan Mastic			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Layer: Off-White Joint Compound		Chrysotile	2 %				
Total Composite Values of Fibrous Components:		Asbestos (2%)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							
1-230802-05C	51681589						
Layer: Black Non-Fibrous Material			ND				
Layer: Tan Mastic			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							

Client Name: Health Science Associates

Report Number: B350566

Date Printed: 08/11/23

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
1-230802-06A	51681590						
Layer: Black Flooring			ND				
Layer: Tan Mastic			ND				
Layer: Paint			ND				
Layer: Off-White Non-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
1-230802-06B	51681591						
Layer: Black Flooring			ND				
Layer: Tan Mastic			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
1-230802-06C	51681592						
Layer: Black Flooring			ND				
Layer: Tan Mastic			ND				
Layer: Brown Mastic with Debris		Chrysotile	2 %				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
1-230802-07A	51681593						
Layer: Brown Flooring			ND				
Layer: Tan Mastic			ND				
Layer: Grey Non-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
1-230802-07B	51681594						
Layer: Brown Flooring			ND				
Layer: Tan Mastic			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
1-230802-07C	51681595						
Layer: Brown Flooring			ND				
Layer: Tan Mastic			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
1-230804-08A	51681596						
Layer: Beige Fibrous Material			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (35 %)	Fibrous Glass (45 %)						
1-230804-08B	51681597						
Layer: Beige Fibrous Material			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (35 %)	Fibrous Glass (45 %)						

Client Name: Health Science Associates

Report Number: B350566

Date Printed: 08/11/23

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
1-230802-09A	51681598						
Layer: Grey Flooring			ND				
Layer: Tan Mastic			ND				
Layer: Off-White Non-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
1-230802-09B	51681599						
Layer: Grey Flooring			ND				
Layer: Tan Mastic			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
1-230802-09C	51681600						
Layer: Grey Flooring			ND				
Layer: Tan Mastic			ND				
Layer: Grey Non-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
1-230802-10A	51681601						
Layer: Dark Blue Non-Fibrous Material			ND				
Layer: Tan Mastic			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Layer: Paint			ND				
Layer: Off-White Joint Compound		Chrysotile	2 %				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							
1-230802-10B	51681602						
Layer: Dark Blue Non-Fibrous Material			ND				
Layer: Tan Mastic			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							
1-230802-10C	51681603						
Layer: Dark Blue Non-Fibrous Material			ND				
Layer: Tan Mastic			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							

Client Name: Health Science Associates

Report Number: B350566

Date Printed: 08/11/23

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
1-230802-11A	51681604						
Layer: Black Non-Fibrous Material			ND				
Layer: Tan Mastic			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							
1-230802-11B	51681605						
Layer: Black Non-Fibrous Material			ND				
Layer: Tan Mastic			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							
1-230802-12A	51681606						
Layer: Black Non-Fibrous Material			ND				
Layer: Clear Mastic			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
1-230802-12B	51681607						
Layer: Black Non-Fibrous Material			ND				
Layer: Clear Mastic			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
1-230802-12C	51681608						
Layer: Black Non-Fibrous Material			ND				
Layer: Clear Mastic			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
1-230804-14A	51681609						
Layer: Beige Fibrous Material			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (35 %) Fibrous Glass (45 %)							
1-230804-14B	51681610						
Layer: Beige Fibrous Material			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (35 %) Fibrous Glass (45 %)							
1-230804-14C	51681611						
Layer: Beige Fibrous Material			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (35 %) Fibrous Glass (45 %)							

Client Name: Health Science Associates

Report Number: B350566

Date Printed: 08/11/23

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
-----------	------------	------------------	---------------------	------------------	---------------------	------------------	---------------------



Tiffani Ludd, Laboratory Supervisor, Carson Laboratory

Note: Limit of Quantification ('LOQ') = 1%. 'Trace' denotes the presence of asbestos below the LOQ. 'ND' = 'None Detected'.

Analytical results and reports are generated by SGS Forensic Laboratories (SGSFL) at the request of and for the exclusive use of the person or entity (client) named on such report. Results, reports or copies of same will not be released by SGSFL to any third party without prior written request from client. This report applies only to the sample(s) tested. Supporting laboratory documentation is available upon request. This report must not be reproduced except in full, unless approved by SGSFL. The client is solely responsible for the use and interpretation of test results and reports requested from SGSFL. This report must not be used by the client to claim product endorsement by NVLAP or any other agency of the U.S. Government. SGSFL is not able to assess the degree of hazard resulting from materials analyzed. SGS Forensic Laboratories reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified. All samples were received in acceptable condition unless otherwise noted.

E-mail results to: labresults@healthscience.comdsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET		FLOOR (circle one)	LD	1	2	3	PENTHOUSE	ROOF
TAT <i>5day</i>	Project Manager:	Joel Berman		Project #:			230201LA	
	Client:	Griffith Structures		Industrial Hygienist:			Devin Berman	
	Project Location:	101 W Manchester Blvd		Rene Medina			Rodica Dullabaun	
		Inglewood, CA 90301		Comments:			Anahi Rizo-Zhang	

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
1-230802-01A	Drywall, mud & tape	1st floor Front of Young Adult area	SW corner W wall	F TSI (M) SC (NF)	D SD (G)	10,000 ft ²	
01B		Main Library area	Behind W stairs W wall	F TSI (M) SC (NF)	D SD (G)		
01C		Imagination Place - kids area	at door to Staff offices	F TSI (M) SC (NF)	D SD (G)		
02A	Carpet mastic	Front of Young Adult office	SW corner	F TSI (M) SC (NF)	D SD (G)	75,000 ft ²	
02B		Main Library area	NE corner	F TSI (M) SC (NF)	D SD (G)		
02C			N end floor	F TSI (M) SC (NF)	D SD (G)		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Relinquished by: <i>Devi D-R</i>	Date: <i>8/4/23</i>	Time: <i>10:10</i>	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

Vermin Contingency 9-4-23 10:00am

E-mail results to: labresults@healthscience.comdsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET		FLOOR (circle one)	LD	1	2	3	PENTHOUSE	ROOF
TAT 5 day	Project Manager:	Joel Berman					Project #: 230201LA	
	Client:	Griffith Structures					Industrial Hygienist: Devin Berman	
	Project Location:	101 W Manchester Blvd Inglewood, CA 90301					Rene Medina	
						Anahi Rizo-Zhang		
Comments:								

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
1-230802-02D	Carpet mastic	1st floor main library	SE corner	F NF	TSI SC	SM SD	
02E			S wall, center	F NF	TSI SC	SM SD	
02F		Children's area	NW corner	F NF	TSI SC	SM SD	
02G			SE corner	F NF	TSI SC	SM SD	
03A	Tread material	West stairwell, public		F NF	TSI SC	SM SD	
03B		East		F NF	TSI SC	SM SD	

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Relinquished by: <u>Den S. B.</u>	Date: <u>8/14/23</u>	Time: <u>10:00</u>	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

Ummine Contreras 8-423 10:00 am DO

E-mail results to: labresults@healthscience.comdsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET		FLOOR (circle one)	LD	1	2	3	PENTHOUSE	ROOF
TAT	Project Manager: <u>Joel Berman</u>	Project #: <u>230201LA</u>					Date: <u>8/2/2023</u>	
5day	Client: <u>Griffith Structures</u>	Industrial Hygienist: <u>Devin Berman</u>					<u>Rodica Dullabaun</u>	
	Project Location: <u>101 W Manchester Blvd</u> <u>Inglewood, CA 90301</u>	<u>Rene Medina</u>					<u>Anahi Rizo-Zhang</u>	
Comments:								

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
1-230802 - 04A	4" Brown Basecore & mastic	1st floor	Lobby office, SW corner	F (M) TSI NF SC	SD (G)	<1000 LF	
04B		Lobby office	Under reception counter, N side	F (M) TSI NF SC	SD (G)		
04C		Lobby	SW corner	F (M) TSI NF SC	SD (G)		
05A	4" Black Basecore & mastic	Main library	In front of young adult office, W wall	F (M) TSI NF SC	SD (G)	1000 LF	
05B			Behind stairs, E wall	F (M) TSI NF SC	SD (G)		
05C		Public elevator lobby Children's Services P5B 8/2/23	Mark library area SE corner N wall P5B 8/2/23	F (M) TSI NF SC	SD (G)		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Volume collected 9.423 10:00am

Relinquished by: <u>Devin Berman</u>	Date: <u>8/14/23</u>	Time: <u>190</u>	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

E-mail results to: labresults@healthscience.comdsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET		FLOOR (circle one)	LD	1	2	3	PENTHOUSE	ROOF
TAT <i>Today</i>	Project Manager:	Joel Berman		Project #:			230201LA	
	Client:	Griffith Structures		Industrial Hygienist:			Devin Berman	
	Project Location:	101 W Manchester Blvd Inglewood, CA 90301		Rene Medina			Anahi Rizo-Zhang	
			Comments:					

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
1-230802- 06A	Black Rubber flooring material be mastic	1st floor Lobby	Center, under air purifier	F (NF) TSI (M) SM SD	D (G)	~1000ft ²	
06B		Lobby office	Under Reception counter, N side	F (NF) TSI (M) SM SD	D (G)		
06C		Elevator hallway W of Lobby office	W wall	F (NF) TSI (M) SM SD	D (G)		
07A	Light gray rubber flooring material + mastic	Lobby	NE area, under Security desk	F (NF) TSI (M) SM SD	D (G)	~1000ft ²	
07B			SE corner	F (NF) TSI (M) SM SD	D (G)		
07C			Lobby office, SW corner	F (NF) TSI (M) SM SD	D (G)		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Guillermo Contreras 9:473 10:00am 00

Relinquished by: <i>Dev SB</i>	Date: <i>8/4/23</i>	Time: <i>low</i>	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

E-mail results to: labresults@healthscience.comdsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET		FLOOR (circle one)	LD	1	2	3	PENTHOUSE	ROOF
TAT 5 day	Project Manager:	Joel Berman		Project #:			230201LA	
	Client:	Griffith Structures		Industrial Hygienist:			Devin Berman	
	Project Location:	101 W Manchester Blvd Inglewood, CA 90301		Rene Medina			Anahi Rizo-Zhang	
				Comments:				

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
1-230804- 08A	Concealed Spline Ceiling tile	1st floor Children's Area	W of Children's Theatre	(F) TSI (M) SM	D SD	5,000 ft ²	
08B		Main Library	SW corner	(F) TSI (M) SM	D SD		
1-230802- 09A	white rubber flooring material + mastic	Lobby office	S wall under desk	(F) TSI (M) SM	D SD	2,000 ft ²	
09B		Lobby office	N wall below reception counter	(F) TSI (M) SM	D SD		
09C			SE area	(F) TSI (M) SM	D SD		
10A	Blue vinyl base ure + mastic	Imagination Place Kids area	at door to staff offices	(F) TSI (M) SM	D SD	2,000 LK	

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Relinquished by: <u>Den S. Berman</u>	Date: <u>8/14/23</u>	Time: <u>1010</u>	Received by: <u>Valmire Contreras</u>	Date: <u>8-14-23</u>	Time: <u>10:00am</u>
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:



E-mail results to: labresults@healthscience.com

dsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET		FLOOR (circle one)	LD	1	2	3	PENTHOUSE	ROOF
TAT	Project Manager: Joel Berman	Project #: 230201LA					Date: 8/2/2023	
5 day	Client: Griffith Structures	Industrial Hygienist: Devin Berman					Rodica Dullabaun	
	Project Location: 101 W Manchester Blvd Inglewood, CA 90301	Rene Medina					Anahi Rizo-Zhang	
Comments:								

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
1-230802-10B	Blue 4" Vinyl basecoat + mastic	1st Floor children's service area	NW corner	F TSI M SC	D SD G	~1000 LF	
10C			SE corner	F TSI M SC	D SD G		
11A	6" Black Vinyl basecoat + mastic	Entry	NW side	F TSI M SC	D SD G	~30 LF	
11B			SW side	F TSI M SC	D SD G		
12A	12"x12" Black VSF	In children's area	In front of RR	F TSI M SC	D SD G	~85 ft ²	
12B				F TSI M SC	D SD G		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Carmine Contreras 8/4/23 10:00am

Relinquished by: Devin Berman	Date: 8/4/23	Time: 1010	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

E-mail results to: labresults@healthscience.comdsberman@heezjanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET				FLOOR (circle one)	LD	1	2	3	PENTHOUSE	ROOF
TAT <i>5 day</i>	Project Manager: <u>Joel Berman</u>		Project #: <u>230201LA</u>						Date: <u>8/2/2023</u>	
	Client: <u>Griffith Structures</u>		Industrial Hygienist: <u>Devin Berman</u>						<u>Rodica Dullabaun</u>	
	Project Location: <u>101 W Manchester Blvd</u> <u>Inglewood, CA 90301</u>		<u>Rene Medina</u>						<u>Anahi Rizo-Zhang</u>	
Comments:										

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
1-230802-12C	12" x 12" Black VSF	2 nd floor In children's area	In front of RRs	F (NF) M SC	TSI SM SD (G)	~85 ft ²	
13A	Bakelite	1 st floor, In children's theatre electrical/server room	Assumed, not sampled	F (NF) M SC	TSI SM SD (G)	7 total	
1-230804-14A	24" x 24" Ceiling tile	1 st floor Children's Theatre	NE corner	F (NF) M SC	TSI SM SD (G)	21000 ft ²	
14B			SE corner	F (NF) M SC	TSI SM SD (G)		
14C			Center	F (NF) M SC	TSI SM SD (G)		
				F (NF) M SC	TSI SM SD (G)		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Relinquished by: <i>[Signature]</i>	Date: <u>8/4/23</u>	Time: <u>1010</u>	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

Samina Contreras 8-4-23 10:00am PD

Bulk Asbestos Analysis

(EPA Method 40CFR, Part 763, Appendix E to Subpart E and EPA 600/R-93-116, Visual Area Estimation)

NVLAP Lab Code: 101459-1

Health Science Associates
Joel Berman
10771 Noel Street

Los Alamitos, CA 90720

Client ID: L1596
Report Number: B350579
Date Received: 08/04/23
Date Analyzed: 08/11/23
Date Printed: 08/11/23
First Reported: 08/11/23

Job ID/Site: 230201LA; Griffith Structures, 101 W Manchester Blvd, Inglewood, CA 90301

SGSFL Job ID: L1596
Total Samples Submitted: 34
Total Samples Analyzed: 34

Date(s) Collected: 08/03/2023, 08/04/2023

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
L-230803-01A	51681623						
Layer: White Drywall			ND				
Layer: White Joint Compound			ND				
Layer: Paint			ND				
Layer: White Joint Compound			ND				
Layer: Paint			ND				
Layer: White Joint Compound			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (3 %)	Fibrous Glass (Trace)						
L-230803-01B	51681624						
Layer: White Drywall			ND				
Layer: Off-White Joint Compound		Chrysotile	2 %				
Layer: Drywall Tape			ND				
Layer: Off-White Joint Compound		Chrysotile	2 %				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (15 %)	Fibrous Glass (Trace)						
L-230803-01C	51681625						
Layer: White Drywall			ND				
Layer: Off-White Joint Compound		Chrysotile	2 %				
Layer: Drywall Tape			ND				
Layer: Off-White Joint Compound		Chrysotile	2 %				
Layer: Paint			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Layer: Tan Mastic			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (15 %)	Fibrous Glass (Trace)						
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							
L-230803-02A	51681626						
Layer: Light Brown Mastic		Chrysotile	2 %				
Total Composite Values of Fibrous Components:		Asbestos (2%)					
Cellulose (Trace)							

Client Name: Health Science Associates

Report Number: B350579

Date Printed: 08/11/23

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
L-230803-02B	51681627						
Layer: Light Brown Mastic		Chrysotile	2 %				
Total Composite Values of Fibrous Components:		Asbestos (2%)					
Cellulose (Trace)							
L-230803-02C	51681628						
Layer: Light Brown Mastic		Chrysotile	2 %				
Total Composite Values of Fibrous Components:		Asbestos (2%)					
Cellulose (Trace)							
L-230803-02D	51681629						
Layer: Light Brown Mastic		Chrysotile	2 %				
Total Composite Values of Fibrous Components:		Asbestos (2%)					
Cellulose (Trace)							
L-230803-02E	51681630						
Layer: Light Brown Mastic		Chrysotile	2 %				
Total Composite Values of Fibrous Components:		Asbestos (2%)					
Cellulose (Trace)							
L-230803-03A	51681631						
Layer: Blue Tile			ND				
Layer: Tan Mastic			ND				
Layer: Brown Mastic		Chrysotile	2 %				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
L-230803-03B	51681632						
Layer: Blue Tile			ND				
Layer: Tan Mastic			ND				
Layer: Brown Mastic		Chrysotile	2 %				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
L-230803-03C	51681633						
Layer: Blue Tile			ND				
Layer: Tan Mastic			ND				
Layer: Brown Mastic		Chrysotile	2 %				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
L-230803-04A	51681634						
Layer: Brown Non-Fibrous Material			ND				
Layer: Tan Mastic			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Layer: Paint			ND				
Layer: Off-White Non-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							

Client Name: Health Science Associates

Report Number: B350579

Date Printed: 08/11/23

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
L-230803-04B	51681635						
Layer: Brown Non-Fibrous Material			ND				
Layer: Tan Mastic			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							
L-230803-04C	51681636						
Layer: Brown Non-Fibrous Material			ND				
Layer: Tan Mastic			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Layer: Paint			ND				
Layer: Off-White Joint Compound		Chrysotile	2 %				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							
L-230803-05A	51681637						
Layer: Black Non-Fibrous Material			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Layer: Grey Non-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							
L-230803-05B	51681638						
Layer: Black Non-Fibrous Material			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Layer: Paint			ND				
Layer: Off-White Joint Compound		Chrysotile	2 %				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							
L-230803-05C	51681639						
Layer: Black Non-Fibrous Material			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							
L-230804-06A	51681640						
Layer: Beige Fibrous Material			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (35 %)	Fibrous Glass (45 %)						

Client Name: Health Science Associates

Report Number: B350579

Date Printed: 08/11/23

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
L-230804-06B	51681641						
Layer: Beige Fibrous Material			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (35 %)	Fibrous Glass (45 %)						
L-230804-06C	51681642						
Layer: Beige Fibrous Material			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (35 %)	Fibrous Glass (45 %)						
L-230803-07A	51681643						
Layer: Grey Non-Fibrous Material			ND				
Layer: Tan Mastic			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Layer: Paint			ND				
Layer: Off-White Joint Compound		Chrysotile	2 %				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							
L-230803-07B	51681644						
Layer: Grey Non-Fibrous Material			ND				
Layer: Tan Mastic			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Layer: Paint			ND				
Layer: Off-White Joint Compound		Chrysotile	2 %				
Layer: Drywall Tape			ND				
Layer: Off-White Joint Compound		Chrysotile	2 %				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							
L-230803-07C	51681645						
Layer: Grey Non-Fibrous Material			ND				
Layer: Tan Mastic			ND				
Layer: Paint			ND				
Layer: Off-White Joint Compound			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
L-230803-08A	51681646						
Layer: Beige Fibrous Material			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (35 %)	Fibrous Glass (45 %)						

Client Name: Health Science Associates

Report Number: B350579

Date Printed: 08/11/23

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
L-230803-08B	51681647						
Layer: Beige Fibrous Material			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (35 %)	Fibrous Glass (45 %)						
L-230803-09A	51681648						
Layer: Dark Blue Non-Fibrous Mat'l			ND				
Layer: Tan Mastic			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							
L-230803-09B	51681649						
Layer: Dark Blue Non-Fibrous Mat'l			ND				
Layer: Tan Mastic			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							
L-230803-09C	51681650						
Layer: Dark Blue Non-Fibrous Mat'l			ND				
Layer: Tan Mastic			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							
L-230803-10A	51681651						
Layer: Black Non-Fibrous Material			ND				
Layer: Tan Mastic			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							
L-230803-10B	51681652						
Layer: Black Non-Fibrous Material			ND				
Layer: Tan Mastic			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							

Client Name: Health Science Associates

Report Number: B350579

Date Printed: 08/11/23

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
L-230803-10C	51681653						
Layer: Black Non-Fibrous Material			ND				
Layer: Tan Mastic			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Layer: Paint			ND				
Layer: Grey Cementitious Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							
L-230803-11A	51681654						
Layer: Grey Mortar			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
L-230803-11B	51681655						
Layer: Grey Mortar			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
L-230803-11C	51681656						
Layer: Grey Mortar			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							



Tiffani Ludd, Laboratory Supervisor, Carson Laboratory

Note: Limit of Quantification ('LOQ') = 1%. 'Trace' denotes the presence of asbestos below the LOQ. 'ND' = 'None Detected'.

Analytical results and reports are generated by SGS Forensic Laboratories (SGSFL) at the request of and for the exclusive use of the person or entity (client) named on such report. Results, reports or copies of same will not be released by SGSFL to any third party without prior written request from client. This report applies only to the sample(s) tested. Supporting laboratory documentation is available upon request. This report must not be reproduced except in full, unless approved by SGSFL. The client is solely responsible for the use and interpretation of test results and reports requested from SGSFL. This report must not be used by the client to claim product endorsement by NVLAP or any other agency of the U.S. Government. SGSFL is not able to assess the degree of hazard resulting from materials analyzed. SGS Forensic Laboratories reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified. All samples were received in acceptable condition unless otherwise noted.

E-mail results to: labresults@healthscience.comdsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET				FLOOR (circle one) <u>LD</u> 1 2 3				PENTHOUSE ROOF	
TAT <i>Today</i>	Project Manager: <u>Joel Berman</u>		Project #: <u>230201LA</u>				Date: <u>8/3/2023</u>		
	Client: <u>Griffith Structures</u>		Industrial Hygienist: <u>Devin Berman</u>				<u>Rodica Dullabaun</u>		
	Project Location: <u>101 W Manchester Blvd</u> <u>Inglewood, CA 90301</u>		<u>Rene Medina</u>				<u>Anahi Rizo-Zhang</u>		
Comments:									

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
L-230803- 01A	Drywall, mud & tape	Loading Dock	N hallway, across from teen center <i>DSR 8/2/23</i>	F (M) TSI NF SC	D G	10,000 ft ²	
01B		Janitor's Closet	SE corner	F (M) TSI NF SC	D G		
01C		Old Break Room	W wall behind fridge	F (M) TSI NF SC	D G		
02A	Carpet mastic	Teen Center	Center of room, under the pool table	F (M) TSI NF SC	D G	< 5,000 ft ²	
02B		Depository	Center of room	F (M) TSI NF SC	D G		
02C		Technical Services	N end area	F (M) TSI NF SC	D G		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Relinquished by: <u>Devin S Berman</u>	Date: <u>8/14/2023</u>	Time: <u>10:10</u>	Received by: <u>Valerie Gonzalez 9-473</u>	Date: <u>10/09/2023</u>	Time: <u>10:00am</u>
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

E-mail results to: labresults@healthscience.comdsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET				FLOOR (circle one) <u>LD</u> 1 2 3				PENTHOUSE ROOF	
TAT <i>5day</i>	Project Manager: <u>Joel Berman</u>		Project #: <u>Z30201LA</u>				Date: <u>8/3/2023</u>		
	Client: <u>Griffith Structures</u>		Industrial Hygienist: <u>Devin Berman</u>				<u>Rodica Dullabaun</u>		
	Project Location: <u>101 W Manchester Blvd</u> <u>Inglewood, CA 90301</u>		<u>Rene Medina</u>				<u>Anahi Rizo-Zhang</u>		
Comments:									

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
L-230803-02D	Carpet Mastic	Loading Dock Technical Serv.	W end, between cabinets	F (M) TSI (NF) SC	D (G) SD	25,000 ft ²	
02E		Hallway at Restrooms	N end, in front of lockers	F (M) TSI (NF) SC	D (G) SD		
03A	Blue 12"x12" vinyl floor tile + mastic	Old Break Room	SW corner	F (M) TSI (NF) SC	D (G) SD	1,000 ft ²	
03B			W wall behind fridge	F (M) TSI (NF) SC	D (G) SD		
03C			NE corner	F (M) TSI (NF) SC	D (G) SD		
04A	Brown 4" Vinyl basecoat + mastic	N hallway	Across from teen center	F (M) TSI (NF) SC	D (G) SD	1,000 ft ²	

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

*Valmire Conteros 9-4-23**11:00 am PD*

Relinquished by: <i>Devin Berman</i>	Date: <i>8/4/2023</i>	Time: <i>7:01</i>	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

E-mail results to: labresults@healthscience.comdsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET				FLOOR (circle one)	LD	1	2	3	PENTHOUSE	ROOF
TAT <i>5 day</i>	Project Manager: <u>Joel Berman</u>		Project #: <u>230201LA</u>						Date: <u>8/3-4/2023</u>	
	Client: <u>Griffith Structures</u>		Industrial Hygienist: <u>Devin Berman</u>						<u>Rodica Dullabaun</u>	
	Project Location: <u>101 W Manchester Blvd</u> <u>Inglewood, CA 90301</u>		<u>Rene Medina</u>						<u>Anahi Rizo-Zhang</u>	
Comments:										

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
L-230803 - 04B	Brown 4" Vinyl basecoat + maskic	Loading Dock g hallway	Across from old Break Room	F TSI NF M SC	SD D G	1100 LF	
04C	↓	N hallway	N of elevator	F TSI NF M SC	SD D G	↓	
05A	Black 4" Vinyl basecoat + maskic	Distribution Depository Area DSB 8/3/23	NW corner	F TSI NF M SC	SD D G	<1000 LF	
05B	↓	↓	S wall at door to stairs	F TSI NF M SC	SD D G	↓	
05C	↓	↓	W wall	F TSI NF M SC	SD D G	↓	
L-230804 - 06A	24" x 24" ceiling tile	Old Break Room Distribution Center DSB 8/3/2023	NE corner	F TSI NF M SC	SD D G	<1000 5,000 ft ²	DSB 8/4/2023

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Valentine Contreras 8-4-23 10:02 am

Relinquished by: <i>Devin Berman</i>	Date: <i>8/4/2023</i>	Time: <i>1010</i>	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:



E-mail results to: labresults@healthscience.com

dsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET				FLOOR (circle one)	LD	1	2	3	PENTHOUSE	ROOF
TAT 5day	Project Manager: Joel Berman		Project #: 230201LA						Date: 8/31/2023	
	Client: Griffith Structures		Industrial Hygienist: Devin Berman						Rodica Dullabaun	
	Project Location: 101 W Manchester Blvd Inglewood, CA 90301		Rene Medina						Anahi Rizo-Zhang	
Comments:										

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
L-2308004 OGB	24"x24" ceiling tile	Loading Dock Old Break Room	Center of room	(F) TSI (M) SC	D SD	21000 ft ²	
			SW corner	(F) TSI (M) SC	D SD		
L-2308003 O7A	24"x24" ceiling tile vinyl base	Tech Center	SW wall at dock	(F) TSI (M) SC	D SD	21000 LF	
		To	NW area at dock	(F) TSI (M) SC	D SD		
			E wall near SE area	(F) TSI (M) SC	D SD		
O8A O8B	Concealed spline Ceiling tile	Teen Center Depository	W wall Center of bldg	(F) TSI (M) SC	D SD	1000 ft ²	

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

DSB 8/13/2023

Jaimie Contreras 9-4-23 10:00am DO

Relinquished by: <i>Heaven S. m</i>	Date: 8/14/2023	Time: 1010	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

E-mail results to: labresults@healthscience.comdsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET		FLOOR (circle one)		LD	1	2	3	PENTHOUSE	ROOF
TAT <i>5 day</i>	Project Manager:	Joel Berman		Project #:				230201LA	
	Client:	Griffith Structures		Industrial Hygienist:				Devin Berman	
	Project Location:	101 W Manchester Blvd Inglewood, CA 90301		Rene Medina				Anahi Rizo-Zhang	
Date: 8/3/2023									
Comments:									

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
L-230803-09A	Blue 4" Vinyl basecoat	Loading Dock	SW corner	F TSI NF M SC	SM SD D G	1000 LF	
09B	+ mastic	Old Break Room	W wall behind fridge	F TSI NF M SC	SM SD D G		
09C			NE corner	F TSI NF M SC	SM SD D G		
10A	6" Black Vinyl basecoat + mastic	Teen Center	NE corner behind door	F TSI NF M SC	SM SD D G	1000 LF	
10B			W wall behind couch	F TSI NF M SC	SM SD D G		
10C			S wall behind Entertainment Center	F TSI NF M SC	SM SD D G		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Valerie Chirras 8-4-23 10:00am DD

Relinquished by: <i>Devin Berman</i>	Date: <i>8/4/2023</i>	Time: <i>1010</i>	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:



10771 Noel Street • Los Alamitos, CA 90720

Office: (714) 220-3922 • Fax: (714) 220-2081

Page 6 of 6E-mail results to: labresults@healthscience.comdsberman@heezjanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET				FLOOR (circle one) <u>LD</u> 1 2 3				PENTHOUSE ROOF	
TAT <i>5day</i>	Project Manager: <u>Joel Berman</u>		Project #: <u>230201LA</u>				Date: <u>8/3/2023</u>		
	Client: <u>Griffith Structures</u>		Industrial Hygienist: <u>Devin Berman</u>				<u>Rodica Dullabaun</u>		
	Project Location: <u>101 W Manchester Blvd</u> <u>Inglewood, CA 90301</u>		<u>Rene Medina</u>				<u>Anahi Rizo-Zhang</u>		
Comments:									

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
<i>L-230803-11A</i>	<i>Block mortar</i>	<i>Loading Dock</i>	<i>Depository, S wall near exit door</i>	F TSI M <u>SM</u> NF SC	D SD <u>G</u>	<i><1000ft²</i>	
<i>11B</i>		<i>Kitchen DSB 8/3/23 old Break Room</i>	<i>NW wall corner behind door</i>	F TSI M <u>SM</u> NF SC	D SD <u>G</u>		
<i>11C</i>		<i>N Hallway area</i>	<i>near loading back door</i>	F TSI M <u>SM</u> NF SC	D SD <u>G</u>		
				F TSI M SM NF SC	D SD G		
				F TSI M SM NF SC	D SD G		
				F TSI M SM NF SC	D SD G		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Valmire Contreras 8-4-23 10:00am 20

Relinquished by: <i>Devin Berman</i>	Date: <i>8/4/2023</i>	Time: <i>4:00</i>	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

Bulk Asbestos Analysis

(EPA Method 40CFR, Part 763, Appendix E to Subpart E and EPA 600/R-93-116, Visual Area Estimation)

NVLAP Lab Code: 101459-1

Health Science Associates
Joel Berman
10771 Noel Street

Los Alamitos, CA 90720

Client ID: L1596
Report Number: B350584
Date Received: 08/04/23
Date Analyzed: 08/11/23
Date Printed: 08/11/23
First Reported: 08/11/23

Job ID/Site: 230201LA; Griffith Structures, 101 W Manchester Blvd, Inglewood, CA 90301**SGSFL Job ID:** L1596**Date(s) Collected:** 08/02/2023, 08/04/2023**Total Samples Submitted:** 27**Total Samples Analyzed:** 27

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
3-230802-01A	51681736						
Layer: White Drywall			ND				
Layer: Off-White Joint Compound		Chrysotile	2 %				
Layer: Drywall Tape			ND				
Layer: Off-White Joint Compound		Chrysotile	2 %				
Layer: Paint			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (20 %)							
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							
3-230802-01B	51681737						
Layer: White Drywall			ND				
Layer: Off-White Joint Compound		Chrysotile	2 %				
Layer: Paint			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (20 %)							
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							
3-230802-01C	51681738						
Layer: White Drywall			ND				
Layer: Paint			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (20 %)							
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							
3-230802-02A	51681739						
Layer: Tan Mastics with Debris		Chrysotile	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
3-230802-02B	51681740						
Layer: Tan Mastics with Debris		Chrysotile	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							

Client Name: Health Science Associates

Report Number: B350584

Date Printed: 08/11/23

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
3-230802-02C	51681741						
Layer: Tan Mastics with Debris		Chrysotile	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
3-230802-02D	51681742						
Layer: Tan Mastics with Debris		Chrysotile	Trace				
Layer: White Non-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Tan Mastics with Debris only: Insufficient material for additional analyses.							
3-230802-02E	51681743						
Layer: Tan Mastics with Debris		Chrysotile	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
3-230802-02F	51681744						
Layer: Tan Mastics with Debris		Chrysotile	Trace				
Layer: White Non-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Tan Mastics with Debris only: Insufficient material for additional analyses.							
3-230802-02G	51681745						
Layer: Tan Mastics with Debris		Chrysotile	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
3-230802-03A	51681746						
Layer: Brown Non-Fibrous Material			ND				
Layer: Tan Non-Fibrous Material			ND				
Layer: Tan Mastic		Chrysotile	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Tan Mastic only: Insufficient material for additional analyses.							
3-230802-03B	51681747						
Layer: Black Non-Fibrous Material w/ Stones			ND				
Layer: Yellow Mastic			ND				
Layer: Brown Non-Fibrous Material			ND				
Layer: Beige Mastic			ND				
Layer: Tan Non-Fibrous Material			ND				
Layer: Tan Mastic		Chrysotile	Trace				
Layer: Grey Non-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Tan Mastic only: Insufficient material for additional analyses.Bulk complex sample.							

Client Name: Health Science Associates

Report Number: B350584

Date Printed: 08/11/23

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
3-230802-04A	51681748						
Layer: Blue Non-Fibrous Material			ND				
Layer: Beige Mastic			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Layer: Off-White Joint Compound		Chrysotile	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic and Off-White Joint Compound only: Insufficient material for additional analyses.							
3-230802-04B	51681749						
Layer: Blue Non-Fibrous Material			ND				
Layer: Beige Mastic			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Layer: Off-White Joint Compound		Chrysotile	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic and Off-White Joint Compound only: Insufficient material for additional analyses.							
3-230802-04C	51681750						
Layer: Blue Non-Fibrous Material			ND				
Layer: Beige Mastic			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Layer: Off-White Joint Compound		Chrysotile	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic and Off-White Joint Compound only: Insufficient material for additional analyses.							
3-230802-05A	51681751						
Layer: Black Tile			ND				
Layer: Yellow Mastic			ND				
Layer: Tan Mastic		Chrysotile	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Tan Mastic only: Insufficient material for additional analyses.							
3-230802-05B	51681752						
Layer: Black Tile			ND				
Layer: Yellow Mastic			ND				
Layer: Tan Mastic		Chrysotile	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Tan Mastic only: Insufficient material for additional analyses.							

Client Name: Health Science Associates

Report Number: B350584

Date Printed: 08/11/23

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
3-230802-05C	51681753						
Layer: Black Tile			ND				
Layer: Yellow Mastic			ND				
Layer: Tan Mastic		Chrysotile	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Tan Mastic only: Insufficient material for additional analyses.							
3-230802-05D	51681754						
Layer: Black Tile			ND				
Layer: Yellow Mastic with Debris			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
3-230804-06A	51681755						
Layer: Beige Fibrous Material			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (35 %)	Fibrous Glass (45 %)						
3-230804-06B	51681756						
Layer: Beige Fibrous Material			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (35 %)	Fibrous Glass (45 %)						
3-230804-06C	51681757						
Layer: Beige Fibrous Material			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (35 %)	Fibrous Glass (45 %)						
3-230804-07A	51681758						
Layer: Beige Fibrous Material			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (35 %)	Fibrous Glass (45 %)						
3-230804-07B	51681759						
Layer: Beige Fibrous Material			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (35 %)	Fibrous Glass (45 %)						
3-230804-07C	51681760						
Layer: Beige Fibrous Material			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (35 %)	Fibrous Glass (45 %)						

Client Name: Health Science Associates

Report Number: B350584

Date Printed: 08/11/23

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
3-230804-08A	51681761						
Layer: Beige Fibrous Material			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (35 %)	Fibrous Glass (45 %)						
3-230804-08B	51681762						
Layer: Beige Fibrous Material			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (35 %)	Fibrous Glass (45 %)						



Tiffani Ludd, Laboratory Supervisor, Carson Laboratory

Note: Limit of Quantification ('LOQ') = 1%. 'Trace' denotes the presence of asbestos below the LOQ. 'ND' = 'None Detected'.

Analytical results and reports are generated by SGS Forensic Laboratories (SGSFL) at the request of and for the exclusive use of the person or entity (client) named on such report. Results, reports or copies of same will not be released by SGSFL to any third party without prior written request from client. This report applies only to the sample(s) tested. Supporting laboratory documentation is available upon request. This report must not be reproduced except in full, unless approved by SGSFL. The client is solely responsible for the use and interpretation of test results and reports requested from SGSFL. This report must not be used by the client to claim product endorsement by NVLAP or any other agency of the U.S. Government. SGSFL is not able to assess the degree of hazard resulting from materials analyzed. SGS Forensic Laboratories reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified. All samples were received in acceptable condition unless otherwise noted.



ASBESTOS BULK SAMPLE DATA SHEET		FLOOR (circle one)	LD	1	2	(3)	PENTHOUSE	ROOF
TAT 5 day	Project Manager:	Joel Berman		Project #:			230201LA	
	Client:	Griffith Structures		Industrial Hygienist:			Devin Berman	
	Project Location:	101 W Manchester Blvd Inglewood, CA 90301		Rene Medina			Rodica Dullabaun Anahi Rizo-Zhang	
Comments:								

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
3-230802-01A	Daywall, mud & tape	3rd floor Entrance to Admin. Offices	near Conference Room 3A at wall base, near door	(F) TSI M (SM) NF SC	D SD (G)	10,000 ft ²	
01B		Main Library area	At West stairwell	(F) TSI M (SM) NF SC	D SD (G)		
01C		Main Library area	behind the East stairwell	(F) TSI M (SM) NF SC	D SD (G)		
02A	Carpet Glue	Main Library	SW area	(F) TSI M (SM) NF SC	D SD (G)	20,000 ft ²	
02B			S end	(F) TSI M (SM) NF SC	D SD (G)		
02C			SE corner	(F) TSI M (SM) NF SC	D SD (G)		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Relinquished by: Devin D. Berman	Date: 6/4/23	Time: 1020	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

WARNING CONTAINS 8-4-23 10:00am 20

E-mail results to: labresults@healthscience.comdsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET		FLOOR (circle one)	LD	1	2	3	PENTHOUSE	ROOF
TAT <i>5day</i>	Project Manager:	Joel Berman		Project #:				230201LA
	Client:	Griffith Structures		Industrial Hygienist:				Devin Berman
	Project Location:	101 W Manchester Blvd Inglewood, CA 90301		Rene Medina				Anahi Rizo-Zhang
			Comments:					
Date:	8/ /2023							

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
3-230802-02D	Carpet Glue	3rd floor Main Library	Central area	F TSI NF M SC (SM)	D SD (G)	20,000 ft ²	
02E			NE corner	F TSI NF M SC (SM)	D SD (G)		
02F		N Office area	N end floor	F TSI NF M SC (SM)	D SD (G)		
02G		Conference Room	NE corner	F TSI NF M SC (SM)	D SD (G)		
03A	Stair Tread	East Stairwell		F TSI NF M SC (SM)	D SD (G)	4000 ft ²	
03B		West Stairwell		F TSI NF M SC (SM)	D SD (G)		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Varmine Contreras 8-4-23 10:00am

Relinquished by: <i>Devin Berman</i>	Date: <i>8/4/23</i>	Time: <i>1020</i>	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

E-mail results to: labresults@healthscience.comdsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET		FLOOR (circle one)	LD	1	2	3	PENTHOUSE	ROOF
TAT 5 day	Project Manager:	Joel Berman		Project #:			230201LA	
	Client:	Griffith Structures		Industrial Hygienist:			Devin Berman	
	Project Location:	101 W Manchester Blvd Inglewood, CA 90301		Rene Medina			Anahi Rizo-Zhang	
				Comments:				

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
3-230802-04A	Blue Vinyl base core	3rd floor Main library Room	at E stairs	F TSI (M) SM SD (NF) SC (G)	D	21000 LF	
04B			NE corner	F TSI (M) SM SD (NF) SC (G)	D		
04C			N wall, w of conference 3A	F TSI (M) SM SD (NF) SC (G)	D		
05A	12" x 12" Black flooring "Rock-like" DBB	Staff stairwell In front of water fountain		F TSI (M) SM SD (NF) SC (G)	D	32 DSB 8/2/2023	
05B				F TSI (M) SM SD (NF) SC (G)	D		
05C				F TSI (M) SM SD (NF) SC (G)	D		
05D		On elevator		F TSI (M) SM SD (NF) SC (G)	D		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Veronica Contreras 8/4/23 11:00am DO

Relinquished by: Devin Berman	Date: 8/4/23	Time: 1020	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:



ASBESTOS BULK SAMPLE DATA SHEET		FLOOR (circle one)	LD	1	2	3	PENTHOUSE	ROOF
TAT	Project Manager: Joel Berman	Project #: 230201LA					Date: 8/4/2023	
5 day	Client: Griffith Structures	Industrial Hygienist: Devin Berman					Rodica Dullabaun	
	Project Location: 101 W Manchester Blvd Inglewood, CA 90301	Rene Medina					Anahi Rizo-Zhang	
Comments:								

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
3-230804-06A	24"x24" ceiling tile	3 rd floor Conference Room	SE corner	F TSI NF M SC	D SD G	<1000 ft ²	
06B			N side Center	F TSI NF M SC	D SD G		
06C			SW corner	F TSI NF M SC	D SD G		
07A	24"x24" ceiling tile	Admin Area	SW corner	F TSI NF M SC	D SD G	<1000 ft ²	
07B			N side, Center	F TSI NF M SC	D SD G		
07C			W side	F TSI NF M SC	D SD G		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Valmire Contreras 8-4-23 10:00 am

Relinquished by: Devin Berman	Date: 8/4/23	Time: 1020	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:



10771 Noel Street • Los Alamitos, CA 90720

Office: (714) 220-3922 • Fax: (714) 220-2081

Page 5 of 5E-mail results to: labresults@healthscience.comdsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET			FLOOR (circle one)	LD	1	2	3	PENTHOUSE	ROOF
TAT <i>5 day</i>	Project Manager:	Joel Berman		Project #:				230201LA	
	Client:	Griffith Structures		Industrial Hygienist:				Devin Berman	
	Project Location:	101 W Manchester Blvd Inglewood, CA 90301		Rene Medina				Anahi Rizo-Zhang	
Comments:									

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
3-230804-08A <i>08B 8/12/23</i>	Concealed Spline Ceiling system tiles	3 rd Main library floor	E side	F TSI M SC	D SD	5100 ft ²	
			SE corner	F TSI M SC	D SD		
				F TSI M SC	D SD		
				F TSI M SC	D SD		
				F TSI M SC	D SD		
				F TSI M SC	D SD		
				F TSI M SC	D SD		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Relinquished by: <i>Devin Berman</i>	Date: <i>8/14/23</i>	Time: <i>1020</i>	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

Devin Berman *8-14-23 10:04 am*

Bulk Asbestos Analysis

(EPA Method 40CFR, Part 763, Appendix E to Subpart E and EPA 600/R-93-116, Visual Area Estimation)

NVLAP Lab Code: 101459-1

Health Science Associates
Joel Berman
10771 Noel Street

Los Alamitos, CA 90720

Client ID: L1596
Report Number: B350586
Date Received: 08/04/23
Date Analyzed: 08/11/23
Date Printed: 08/11/23
First Reported: 08/11/23

Job ID/Site: 230201LA; Griffith Structures, 101 W Manchester Blvd, Inglewood, CA 90301

SGSFL Job ID: L1596
Total Samples Submitted: 20
Total Samples Analyzed: 20

Date(s) Collected: 08/03/2023

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
2-230803-01A	51681763						
Layer: White Drywall			ND				
Layer: White Joint Compound		Chrysotile	2 %				
Layer: Drywall Tape			ND				
Layer: White Joint Compound		Chrysotile	2 %				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (15 %)	Fibrous Glass (Trace)						
2-230803-01B	51681764						
Layer: White Drywall			ND				
Layer: White Joint Compound		Chrysotile	2 %				
Layer: Drywall Tape			ND				
Layer: White Joint Compound		Chrysotile	2 %				
Layer: Off-White Woven Material			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (20 %)	Fibrous Glass (Trace)						
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							
2-230803-01C	51681765						
Layer: White Drywall			ND				
Layer: White Joint Compound		Chrysotile	2 %				
Layer: Drywall Tape			ND				
Layer: White Joint Compound		Chrysotile	2 %				
Layer: Off-White Woven Material			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (20 %)	Fibrous Glass (Trace)						
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							
2-230803-02A	51681766						
Layer: Brown Mastic with Debris		Chrysotile	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							

Client Name: Health Science Associates

Report Number: B350586

Date Printed: 08/11/23

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
2-230803-02B	51681767						
Layer: Brown Mastic with Debris		Chrysotile	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
2-230803-02C	51681768						
Layer: Brown Mastic with Debris		Chrysotile	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
2-230803-02D	51681769						
Layer: Tan Mastic			ND				
Layer: Off-White Non-Fibrous Material			ND				
Layer: Brown Mastic with Debris		Chrysotile	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic with Debris only: Insufficient material for additional analyses.							
2-230803-02E	51681770						
Layer: Brown Mastic with Debris		Chrysotile	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
2-230803-02F	51681771						
Layer: Brown Mastic with Debris		Chrysotile	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
2-230803-02G	51681772						
Layer: Tan Mastic			ND				
Layer: Off-White Non-Fibrous Material			ND				
Layer: Brown Mastic with Debris		Chrysotile	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic with Debris only: Insufficient material for additional analyses.							
2-230803-03A	51681773						
Layer: Dark Brown Non-Fibrous Material			ND				
Layer: Tan Mastic with Debris			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
2-230803-03B	51681774						
Layer: Dark Brown Non-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							

Client Name: Health Science Associates

Report Number: B350586

Date Printed: 08/11/23

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
2-230803-04A	51681775						
Layer: Black Non-Fibrous Material			ND				
Layer: Beige Mastic			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Layer: Off-White Joint Compound		Chrysotile	2 %				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							
2-230803-04B	51681776						
Layer: Black Non-Fibrous Material			ND				
Layer: Beige Mastic			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							
2-230803-04C	51681777						
Layer: Black Non-Fibrous Material			ND				
Layer: Beige Mastic			ND				
Layer: Brown Mastic		Anthophyllite	Trace				
Total Composite Values of Fibrous Components:		Asbestos (Trace)					
Cellulose (Trace)							
Comment: This comment applies to the Brown Mastic only: Insufficient material for additional analyses.							
2-230803-05A	51681778						
Layer: Black Flooring			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
2-230803-05B	51681779						
Layer: Black Flooring			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
2-230803-05C	51681780						
Layer: Black Flooring			ND				
Layer: Tan Mastic			ND				
Layer: Off-White Non-Fibrous Material			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (Trace)							
2-230804-06A	51681781						
Layer: Grey Fibrous Material			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (35 %) Fibrous Glass (45 %)							

Client Name: Health Science Associates

Report Number: B350586

Date Printed: 08/11/23

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
2-230804-06B	51681782						
Layer: Grey Fibrous Material			ND				
Layer: Paint			ND				
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (35 %)	Fibrous Glass (45 %)						



Tiffani Ludd, Laboratory Supervisor, Carson Laboratory

Note: Limit of Quantification ('LOQ') = 1%. 'Trace' denotes the presence of asbestos below the LOQ. 'ND' = 'None Detected'.

Analytical results and reports are generated by SGS Forensic Laboratories (SGSFL) at the request of and for the exclusive use of the person or entity (client) named on such report. Results, reports or copies of same will not be released by SGSFL to any third party without prior written request from client. This report applies only to the sample(s) tested. Supporting laboratory documentation is available upon request. This report must not be reproduced except in full, unless approved by SGSFL. The client is solely responsible for the use and interpretation of test results and reports requested from SGSFL. This report must not be used by the client to claim product endorsement by NVLAP or any other agency of the U.S. Government. SGSFL is not able to assess the degree of hazard resulting from materials analyzed. SGS Forensic Laboratories reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified. All samples were received in acceptable condition unless otherwise noted.



10771 Noel Street • Los Alamitos, CA 90720

Office: (714) 220-3922 • Fax: (714) 220-2081

Page 1 of 4

E-mail results to: labresults@healthscience.com

dsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET		FLOOR (circle one)	LD	1	2	3	PENTHOUSE	ROOF
TAT 5 day	Project Manager:	Joel Berman					Project #: 230201LA	
	Client:	Griffith Structures					Industrial Hygienist: Devin Berman	
	Project Location:	101 W Manchester Blvd Inglewood, CA 90301					Date: 8/3/2023 Rodica Dullabaun Anahi Rizo-Zhang	
		Comments:						

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
2-230803-01A	Drywall, mud & tape	2nd Floor: Main Library	NE ^{RD 8/3/23} corner East Stairwell	F TSI M SC	D SD G	10,000 ft ²	
D1B		In corridor to Staff R.R.	SE ^{RD 8/3/23} corner SE corner	F TSI M SC	D SD G		
O1C		Main library	RD 8/3/23 S end Outside of room 4, N of door	F TSI M SC	D SD G		
O2A	Carpet mastic	Main Library	NE ^{RD 8/3/23} Sto corner	F TSI M SC	D SD G	75,000 ft ²	
O2B			SE corner	F TSI M SC	D SD G		
O2C			S end	F TSI M SC	D SD G		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Relinquished by: <i>Dev B</i>	Date: 8/4/23	Time: 1010	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

Volume (containing) 9-473 10:00am DC

E-mail results to: labresults@healthscience.comdsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET		FLOOR (circle one)	LD	1	2	3	PENTHOUSE	ROOF
TAT 5 clay	Project Manager: Joel Berman		Project #: 230201LA				Date: 8/3/2023	
	Client: Griffith Structures		Industrial Hygienist: Devin Berman				Rodica Dullabaun	
	Project Location: 101 W Manchester Blvd		Rene Medina				Anahi Rizo-Zhang	
	Inglewood, CA 90301		Comments:					

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
2-230803	Carpet	2nd Floor:	SW corner	F TSI	D	75,000	
02D	mask	Main Library	central area	M SC	SD	Pt2	
02G				NF	G		
02F		Main Library	NW corner	F TSI	D		
02G		Staff offices	N end	M SC	SD		
03A	Tread material	Stairwell	West stairwell	F TSI	D	4,000 ft ²	
03B			East stairwell	M SC	SD		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Relinquished by: <i>Devin Berman</i>	Date: 8/4/23	Time: 1010	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

vanessa Contreras 9-1-23 10:00am

E-mail results to: labresults@healthscience.comdsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET		FLOOR (circle one)	LD	1	(2)	3	PENTHOUSE	ROOF
TAT 5 day	Project Manager:	Joel Berman				Project #:		230201LA
	Client:	Griffith Structures				Industrial Hygienist:		Devin Berman
	Project Location:	101 W Manchester Blvd Inglewood, CA 90301				Rene Medina		Anahi Rizo-Zhang
Date: 8/3/2023								
Comments:								

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
2-230803 - 04A	Black Vinyl base coat + mastic	2nd floor	4+ East Stairwell	F TSI NF M SC	SD D G	1000 LF	
04B		In Corridor to Staff RR Room	SE corner	F TSI NF M SC	SD D G		
04C		Main library	Outside Room 4, N of door	F TSI NF M SC	SD D G		
DSB 8/13/2023 05A	Black 12"x12" VSF Black 12"x12" VSF	In front of drinking fountain		F TSI NF M SC	SD D G	160 ft ²	
DSB				F TSI NF M SC	SD D G		
05C				F TSI NF M SC	SD D G		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Relinquished by: <u>Devin Berman</u>	Date: <u>8/14/23</u>	Time: <u>10:10</u>	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

Upholding Integrity 8-4-23 10:00 AM DV



10771 Noel Street • Los Alamitos, CA 90720

Office: (714) 220-3922 • Fax: (714) 220-2081

Page 4 of 4E-mail results to: labresults@healthscience.comdsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET				FLOOR (circle one)	LD	1	2	3	PENTHOUSE	ROOF
TAT 5 day	Project Manager: Joel Berman		Project #: 230201LA					Date: 8/4/2023		
	Client: Griffith Structures		Industrial Hygienist: Devin Berman					Rodica Dullabaun		
	Project Location: 101 W Manchester Blvd Inglewood, CA 90301		Rene Medina					Anahi Rizo-Zhang		
Comments:										

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
2-230804-06A	Concealed spline ceiling tile	2nd floor Admin Area	NE corner	(F) TSI (M) SM	D SD	3100 ft ²	
06B		Main Library	Swall, center	(F) TSI (M) SM	D SD		
				(F) TSI (M) SM	D SD		
				(F) TSI (M) SM	D SD		
				(F) TSI (M) SM	D SD		
				(F) TSI (M) SM	D SD		
				(F) TSI (M) SM	D SD		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Relinquished by: <i>Dev Berman</i>	Date: 8/4/23	Time: 1010	Received by: <i>Marlene Contreras</i>	Date: 8/4/23	Time: 10:09 am
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

Metals Analysis of Paints

(AIHA-LAP, LLC Accreditation, Lab ID #101629)

Health Science Associates
Joel Berman
10771 Noel Street

Los Alamitos, CA 90720


Client ID: L1596
Report Number: M252758
Date Received: 08/03/23
Date Analyzed: 08/10/23
Date Printed: 08/10/23
First Reported: 08/10/23

Job ID / Site: 230201LA; Griffith Structures; 101 W Manchester Blvd, Inglewood, CA, 90301
Date(s) Collected: 08/02/2023

SGSFL Job ID: L1596
Total Samples Submitted: 4
Total Samples Analyzed: 4

Sample Number	Lab Number	Analyte	Result	Result Units	Reporting Limit*	Method Reference
PC#1	LM253356	Pb	0.15	wt%	0.006	EPA 3050B/7000B
PC#2	LM253357	Pb	0.10	wt%	0.006	EPA 3050B/7000B
PC#3	LM253358	Pb	0.18	wt%	0.02	EPA 3050B/7000B
PC#4	LM253359	Pb	0.08	wt%	0.02	EPA 3050B/7000B

* The Reporting Limit represents the lowest amount of analyte that the laboratory can confidently detect in the sample, and is not a regulatory level. The Units for the Reporting Limit are the same as the Units for the Final Results.



Beatriz Hinojosa, Laboratory Supervisor, Carson Laboratory

Analytical results and reports are generated by SGS Forensic Laboratories at the request of and for the exclusive use of the person or entity (client) named on such report. Results, reports or copies of same will not be released by SGS Forensic Laboratories to any third party without prior written request from client. This report applies only to the sample(s) tested. Supporting laboratory documentation is available upon request. This report must not be reproduced except in full, unless approved by SGS Forensic Laboratories. The client is solely responsible for the use and interpretation of test results and reports requested from SGS Forensic Laboratories. SGS Forensic Laboratories is not able to assess the degree of hazard resulting from materials analyzed. SGS Forensic Laboratories reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified. Any modifications that have been made to referenced test methods are documented in SGS Forensic Laboratories' Standard Operating Procedures Manual. Sample results have not been blank corrected. Quality control and sample receipt condition were acceptable unless otherwise noted.

Note* Sampling data used in this report was provided by the client as noted on the associated chain of custody form.



10771 Noel Street • Los Alamitos, CA 90720

Office: (714) 220-3922 • Fax: (714) 220-2081 -

Will this require a CDPH 8552 Form?

Page 1 of 1
Get CDPH 8552 Form

E-mail results to: labresults@healthscience.com dsberman@healthscience.com

janmariebailey@yahoo.com

LEAD BULK SAMPLE DATA SHEET		FLOOR (circle one)	LD	1	2	3	PENTHOUSE	ROOF
TAT 5 Day	Project Manager:	Joel Berman	Project #:	230201LA			Date: 8/2/2023	
	Client:	Griffith Structures	Industrial Hygienist:	Devin Berman			Rodica Dullabaun	
	Project Location:	101 W Manchester Blvd Inglewood, CA 90301		Rene Medina			Anahi Rizo-Zhang	
			Comments:					

Sample #	Area (dimensions)	Media	Location / Description / XRF #	Notes / Instructions
PC #1		Paint Chip	XRF #95 (LD)	Parking/Loading Dock Floor
PC #2		Paint Chip	XRF #48 (3)	3rd Floor
PC #3		Paint Chip	XRF #34 (1)	1st Floor
PC #4		Paint Chip	XRF #52 (1)	1st Floor

Laboratory Reporting Units:	Wipe in $\mu\text{g}/\text{ft}^2$	Soil in ppm	<input checked="" type="checkbox"/> Paint Chip in WT % (Lead)	Analytical Method
	Waste Water in ppm	Drinking Water in ppb	<input type="checkbox"/> Paint Chip in mg/cm^2	
	Lead Waste in TTLC, STLC, TCLP (circle all that apply)			
				<input checked="" type="checkbox"/> FAAS <input type="checkbox"/> ICP <input type="checkbox"/> GFAS

Special Instructions to Laboratory:

Relinquished by: Anahi Rizo-Zhang	Date: 8/3/23	Time: 2:41pm	Received by: Janmarie Conner	Date: 8-3-23	Time: 2:42pm
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

Bulk Asbestos Material Analysis

(EPA Method 600/R-93/116, Point Count Analysis)

Health Science Associates
Joel Berman
10771 Noel Street

Los Alamitos, CA 90720

Client ID: L1596
Report Number: N015671
Date Received: 08/18/23
Date Analyzed: 08/24/23
Date Printed: 08/24/23

Job ID/Site: 230201LA; Griffith Structures, 101 W Manchester Blvd, Inglewood, CA 90301

SGSFL Job ID: L1596

PLM Report Number: B350586

Total Samples Submitted: 7

Total Samples Analyzed: 7

Sample Preparation and Analysis:

Each sample was prepared using the gravimetric technique. A representative subsample was weighed, ashed for eight hours, and reweighed to determine the proportion of the organic component. The ashed residue was ground in concentrated hydrochloric acid, dried and reweighed to determine the acid-soluble component weight percentage. The residual material was analyzed for asbestos using polarized light microscopy. Asbestos quantitation was performed using the semi-quantitative Point Count method following the general guidelines in EPA Method 600/R-93/116. The analytical sensitivity for the method is calculated as the asbestos concentration that results from one point counted in the analysis adjusted using the residual weight of the sample. The limit of detection for this method has not been determined.

Sample ID	Lab Number	Sample Description		
2-230803-02A	51681766	Brown Mastic with Debris		
<i>Point Count Results:</i>				
Number of asbestos points counted:	3		Organic weight percentage:	77.10
Number of non-empty points:	1000		Acid-soluble weight percentage:	1.49
Percent asbestos in layer:	0.06		Residual weight percentage:	21.41
Analytical sensitivity (%):	0.02			
Asbestos type(s) detected:	Chrysotile			
Comment:				
2-230803-02B	51681767	Brown Mastic with Debris		
<i>Point Count Results:</i>				
Number of asbestos points counted:	5		Organic weight percentage:	59.11
Number of non-empty points:	1000		Acid-soluble weight percentage:	1.32
Percent asbestos in layer:	0.20		Residual weight percentage:	39.57
Analytical sensitivity (%):	0.04			
Asbestos type(s) detected:	Chrysotile			
Comment:				
2-230803-02C	51681768	Brown Mastic with Debris		
<i>Point Count Results:</i>				
Number of asbestos points counted:	4		Organic weight percentage:	67.33
Number of non-empty points:	1000		Acid-soluble weight percentage:	0.91
Percent asbestos in layer:	0.13		Residual weight percentage:	31.75
Analytical sensitivity (%):	0.03			
Asbestos type(s) detected:	Chrysotile			
Comment:				

Bulk Asbestos Material Analysis

(EPA Method 600/R-93/116, Point Count Analysis)

Health Science Associates
Joel Berman
10771 Noel Street

Los Alamitos, CA 90720

Client ID: L1596
Report Number: N015671
Date Received: 08/18/23
Date Analyzed: 08/24/23
Date Printed: 08/24/23

Job ID/Site: 230201LA; Griffith Structures, 101 W Manchester Blvd, Inglewood, CA 90301

SGSFL Job ID: L1596

PLM Report Number: B350586

Total Samples Submitted: 7

Total Samples Analyzed: 7

Sample Preparation and Analysis:

Each sample was prepared using the gravimetric technique. A representative subsample was weighed, ashed for eight hours, and reweighed to determine the proportion of the organic component. The ashed residue was ground in concentrated hydrochloric acid, dried and reweighed to determine the acid-soluble component weight percentage. The residual material was analyzed for asbestos using polarized light microscopy. Asbestos quantitation was performed using the semi-quantitative Point Count method following the general guidelines in EPA Method 600/R-93/116. The analytical sensitivity for the method is calculated as the asbestos concentration that results from one point counted in the analysis adjusted using the residual weight of the sample. The limit of detection for this method has not been determined.

Sample ID	Lab Number	Sample Description		
2-230803-02D	51681769	Brown Mastic with Debris		
<i>Point Count Results:</i>				
Number of asbestos points counted:	4	Organic weight percentage:	67.18	
Number of non-empty points:	1000	Acid-soluble weight percentage:	0.19	
Percent asbestos in layer:	0.13	Residual weight percentage:	32.64	
Analytical sensitivity (%):	0.03			
Asbestos type(s) detected:	Chrysotile			
Comment:				
2-230803-02E	51681770	Brown Mastic with Debris		
<i>Point Count Results:</i>				
Number of asbestos points counted:	6	Organic weight percentage:	74.40	
Number of non-empty points:	1000	Acid-soluble weight percentage:	0.50	
Percent asbestos in layer:	0.15	Residual weight percentage:	25.10	
Analytical sensitivity (%):	0.03			
Asbestos type(s) detected:	Chrysotile			
Comment:				
2-230803-02F	51681771	Brown Mastic with Debris		
<i>Point Count Results:</i>				
Number of asbestos points counted:	4	Organic weight percentage:	59.96	
Number of non-empty points:	1000	Acid-soluble weight percentage:	5.86	
Percent asbestos in layer:	0.14	Residual weight percentage:	34.18	
Analytical sensitivity (%):	0.03			
Asbestos type(s) detected:	Chrysotile			
Comment:				

Bulk Asbestos Material Analysis

(EPA Method 600/R-93/116, Point Count Analysis)

Health Science Associates
Joel Berman
10771 Noel Street

Los Alamitos, CA 90720

Client ID: L1596
Report Number: N015671
Date Received: 08/18/23
Date Analyzed: 08/24/23
Date Printed: 08/24/23

Job ID/Site: 230201LA; Griffith Structures, 101 W Manchester Blvd, Inglewood, CA 90301

SGSFL Job ID: L1596

PLM Report Number: B350586

Total Samples Submitted: 7

Total Samples Analyzed: 7

Sample Preparation and Analysis:

Each sample was prepared using the gravimetric technique. A representative subsample was weighed, ashed for eight hours, and reweighed to determine the proportion of the organic component. The ashed residue was ground in concentrated hydrochloric acid, dried and reweighed to determine the acid-soluble component weight percentage. The residual material was analyzed for asbestos using polarized light microscopy. Asbestos quantitation was performed using the semi-quantitative Point Count method following the general guidelines in EPA Method 600/R-93/116. The analytical sensitivity for the method is calculated as the asbestos concentration that results from one point counted in the analysis adjusted using the residual weight of the sample. The limit of detection for this method has not been determined.

Sample ID	Lab Number	Sample Description
2-230803-02G	51681772	Brown Mastic with Debris
<i>Point Count Results:</i>		
Number of asbestos points counted:	4	Organic weight percentage: 60.85
Number of non-empty points:	1000	Acid-soluble weight percentage: 0.38
Percent asbestos in layer:	0.16	Residual weight percentage: 38.77
Analytical sensitivity (%):	0.04	
Asbestos type(s) detected:	Chrysotile	

Comment:



Tiffani Ludd, Laboratory Supervisor, Carson Laboratory

Analytical results and reports are generated by SGS Forensic Laboratories (SGSFL) at the request of and for the exclusive use of the person or entity (client) named on such report. Results, reports or copies of same will not be released by SGSFL to any third party without prior written request from client. This report applies only to the sample(s) tested. Supporting laboratory documentation is available upon request. This report must not be reproduced except in full, unless approved by SGSFL. The client is solely responsible for the use and interpretation of test results and reports requested from SGSFL. This report must not be used by the client to claim product endorsement by NVLAP or any other agency of the U.S. Government. SGSFL is not able to assess the degree of hazard resulting from materials analyzed. SGS Forensic Laboratories reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified. All samples were received in acceptable condition unless otherwise noted.



E-mail results to: labresults@healthscience.com

dsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET		FLOOR (circle one)	LD	1	2	3	PENTHOUSE	ROOF
TAT 5 day	Project Manager:	Joel Berman					Project #: 230201LA	
	Client:	Griffith Structures					Industrial Hygienist: Devin Berman	
	Project Location:	101 W Manchester Blvd Inglewood, CA 90301					Date: 8/3/2023 Rodica Dullabaun Anahi Rizo-Zhang	
Comments:								

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
2-230803-01A	Drywall, mud & tape	2nd Floor: Main Library	NE ^{RD 8/3/23} corner East Stairwell	F M NF	TSI SM SD	10,000 ft ²	
D1B		In corridor to Staff R/R	SE ^{RD 8/3/23} corner SE corner	F M NF	TSI SM SD		
O1C		Main library	RD 8/3/23 SE end Outside of Room 4, N of door	F M NF	TSI SM SD		
O2A	Carpet mastic	Main Library	NE ^{RD 8/3/23} SE corner SE corner	F M NF	TSI SM SD	75,000 ft ²	
O2B			SE corner	F M NF	TSI SM SD		
O2C			S end	F M NF	TSI SM SD		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Relinquished by: <i>Devin Berman</i>	Date: 8/4/23	Time: 1010	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

Volume (containers) 9-473 10:00am DC

E-mail results to: labresults@healthscience.comdsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET		FLOOR (circle one)	LD	1	2	3	PENTHOUSE	ROOF
TAT 5 clay	Project Manager:	Joel Berman					Project #: 230201LA	
	Client:	Griffith Structures					Industrial Hygienist: Devin Berman	
	Project Location:	101 W Manchester Blvd Inglewood, CA 90301					Rene Medina	
						Comments:		
							Date: 8/3/2023	
							Rodica Dullabaun	
							Anahi Rizo-Zhang	

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
2-230803	Carpet	2nd Floor:	SW corner	F TSI	D	75,000	
02D	mask	Main Library	central area	M SC	SD	Pt2	
02G				NF	G		
02F		Main Library	NW corner	F TSI	D		
02G		Staff offices	N end	M SC	SD		
03A	Tread material	Stairwell	West stairwell	F TSI	D	4,000 ft ²	
03B			East stairwell	M SC	SD		
				NF	G		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Relinquished by: <i>Debi S R</i>	Date: 8/1/23	Time: 1010	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

vanne Contreras 9-1-23 10:09am

E-mail results to: labresults@healthscience.comdsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET		FLOOR (circle one)	LD	1	2	3	PENTHOUSE	ROOF
TAT 5 day	Project Manager:	Joel Berman				Project #:		230201LA
	Client:	Griffith Structures				Industrial Hygienist:		Devin Berman
	Project Location:	101 W Manchester Blvd Inglewood, CA 90301				Rene Medina		Anahi Rizo-Zhang
Date: 8/3/2023								
Comments:								

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
2-230803 - 04A	Black Vinyl base coat + mastic	2nd floor	4+ East Stairwell	F TSI NF M SC	SD D G	1000 LF	
04B		In Corridor to Staff RR Room	SE corner	F TSI NF M SC	SD D G		
04C		Main library	Outside Room 4, N of door	F TSI NF M SC	SD D G		
DSB 8/13/2023 05A	Black 12"x12" VSF Base coat + mastic	In front of drinking fountain		F TSI NF M SC	SD D G	16 ft ²	
DSB				F TSI NF M SC	SD D G		
05C				F TSI NF M SC	SD D G		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Relinquished by: <u>Devin Berman</u>	Date: <u>8/14/23</u>	Time: <u>10:10</u>	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

Urgent Concerns 8-4-23 10:00 AM DV



10771 Noel Street • Los Alamitos, CA 90720

Office: (714) 220-3922 • Fax: (714) 220-2081

Page 4 of 4E-mail results to: labresults@healthscience.comdsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET				FLOOR (circle one)	LD	1	2	3	PENTHOUSE	ROOF
TAT 5 day	Project Manager: Joel Berman		Project #: 230201LA					Date: 8/4/2023		
	Client: Griffith Structures		Industrial Hygienist: Devin Berman					Rodica Dullabaun		
	Project Location: 101 W Manchester Blvd Inglewood, CA 90301		Rene Medina					Anahi Rizo-Zhang		
Comments:										

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
2-230804-06A	Concealed spline ceiling tile	2nd floor Admin Area	NE corner	(F) TSI (M) SM	D SD	3100 ft ²	
06B		Main Library	Swall, center	(F) TSI (M) SM	D SD		
				(F) TSI (M) SM	D SD		
				(F) TSI (M) SM	D SD		
				(F) TSI (M) SM	D SD		
				(F) TSI (M) SM	D SD		
				(F) TSI (M) SM	D SD		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Relinquished by: <i>Dev Berman</i>	Date: 8/4/23	Time: 1010	Received by: <i>Marlene Contreras</i>	Date: 8/4/23	Time: 10:09 am
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

Bulk Asbestos Material Analysis

(EPA Method 600/R-93/116, Point Count Analysis)

Health Science Associates
Joel Berman
10771 Noel Street

Los Alamitos, CA 90720

Client ID: L1596
Report Number: N015672
Date Received: 08/18/23
Date Analyzed: 08/23/23
Date Printed: 08/24/23

Job ID/Site: 230201LA; Griffith Structures; 101 W Manchester Blvd, Inglewood, CA, 90301

SGSFL Job ID: L1596

PLM Report Number: B350499

Total Samples Submitted: 4
Total Samples Analyzed: 4

Sample Preparation and Analysis:

Each sample was prepared using the gravimetric technique. A representative subsample was weighed, ashed for eight hours, and reweighed to determine the proportion of the organic component. The ashed residue was ground in concentrated hydrochloric acid, dried and reweighed to determine the acid-soluble component weight percentage. The residual material was analyzed for asbestos using polarized light microscopy. Asbestos quantitation was performed using the semi-quantitative Point Count method following the general guidelines in EPA Method 600/R-93/116. The analytical sensitivity for the method is calculated as the asbestos concentration that results from one point counted in the analysis adjusted using the residual weight of the sample. The limit of detection for this method has not been determined.

Sample ID	Lab Number	Sample Description
P-230803-01A	51680912	Off-White Joint Compound
<i>Point Count Results:</i>		
Number of asbestos points counted:	9	Organic weight percentage: 7.82
Number of non-empty points:	1000	Acid-soluble weight percentage: 27.22
Percent asbestos in layer:	0.59	Residual weight percentage: 64.97
Analytical sensitivity (%):	0.06	
Asbestos type(s) detected:	Chrysotile	
Comment:		
P-230803-01B	51680913	Off-White Joint Compound
<i>Point Count Results:</i>		
Number of asbestos points counted:	13	Organic weight percentage: 7.21
Number of non-empty points:	1000	Acid-soluble weight percentage: 23.21
Percent asbestos in layer:	0.91	Residual weight percentage: 69.58
Analytical sensitivity (%):	0.07	
Asbestos type(s) detected:	Chrysotile	
Comment:		
P-230803-01C	51680914	Off-White Joint Compound
<i>Point Count Results:</i>		
Number of asbestos points counted:	10	Organic weight percentage: 7.49
Number of non-empty points:	1000	Acid-soluble weight percentage: 42.82
Percent asbestos in layer:	0.50	Residual weight percentage: 49.69
Analytical sensitivity (%):	0.05	
Asbestos type(s) detected:	Chrysotile	
Comment:		

Bulk Asbestos Material Analysis

(EPA Method 600/R-93/116, Point Count Analysis)

Health Science Associates
Joel Berman
10771 Noel Street

Los Alamitos, CA 90720

Client ID: L1596
Report Number: N015672
Date Received: 08/18/23
Date Analyzed: 08/23/23
Date Printed: 08/24/23

Job ID/Site: 230201LA; Griffith Structures; 101 W Manchester Blvd, Inglewood, CA, 90301

SGSFL Job ID: L1596

PLM Report Number: B350499

Total Samples Submitted: 4
Total Samples Analyzed: 4

Sample Preparation and Analysis:

Each sample was prepared using the gravimetric technique. A representative subsample was weighed, ashed for eight hours, and reweighed to determine the proportion of the organic component. The ashed residue was ground in concentrated hydrochloric acid, dried and reweighed to determine the acid-soluble component weight percentage. The residual material was analyzed for asbestos using polarized light microscopy. Asbestos quantitation was performed using the semi-quantitative Point Count method following the general guidelines in EPA Method 600/R-93/116. The analytical sensitivity for the method is calculated as the asbestos concentration that results from one point counted in the analysis adjusted using the residual weight of the sample. The limit of detection for this method has not been determined.

Sample ID	Lab Number	Sample Description
P-230803-02C	51680917	Off-White Joint Compound
<i>Point Count Results:</i>		
Number of asbestos points counted:	10	Organic weight percentage: 7.49
Number of non-empty points:	1000	Acid-soluble weight percentage: 38.76
Percent asbestos in layer:	0.54	Residual weight percentage: 53.75
Analytical sensitivity (%):	0.05	
Asbestos type(s) detected:	Chrysotile	

Comment:



Tiffani Ludd, Laboratory Supervisor, Carson Laboratory

Analytical results and reports are generated by SGS Forensic Laboratories (SGSFL) at the request of and for the exclusive use of the person or entity (client) named on such report. Results, reports or copies of same will not be released by SGSFL to any third party without prior written request from client. This report applies only to the sample(s) tested. Supporting laboratory documentation is available upon request. This report must not be reproduced except in full, unless approved by SGSFL. The client is solely responsible for the use and interpretation of test results and reports requested from SGSFL. This report must not be used by the client to claim product endorsement by NVLAP or any other agency of the U.S. Government. SGSFL is not able to assess the degree of hazard resulting from materials analyzed. SGS Forensic Laboratories reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified. All samples were received in acceptable condition unless otherwise noted.



10771 Noel Street • Los Alamitos, CA 90720

Office: (714) 220-3922 • Fax: (714) 220-2081

Page 1 of 3E-mail results to: labresults@healthscience.comdsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET

FLOOR (circle one)

LD

1

2

3

PENTHOUSE

ROOF

Project #: 230201LA

Date: 8/3/2023

TAT

Project Manager: Joel Berman

Industrial Hygienist: Devin Berman

Rodica Dullabaun

Client: Griffith Structures

Rene Medina

Anahi Rizo-Zhang

Project Location: 101 W Manchester Blvd

Inglewood, CA 90301

Comments:

5 day

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
P-230803-	Drywall, mud & tape	Penthouse	Generic Room / South Room NW corner	F TSI (M) NF SC	D SD G	21000 ft ²	
01A							
01B			E wall, North	F TSI (M) NF SC	D SD G		
01C			E wall, South	F TSI (M) NF SC	D SD G		
02A	Debris pile	Debris Pile		F TSI (M) NF SC	D SD G	250 ft ²	
02B				F TSI (M) NF SC	D SD G		
02C				F TSI (M) NF SC	D SD G		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Relinquished by: <i>Devin Berman</i>	Date: 8/14/23	Time: 10:15	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

Verdine Contreras 8/11/23 10:09am DC

Bulk Asbestos Material Analysis

(EPA Method 600/R-93/116, Point Count Analysis)

Health Science Associates
Joel Berman
10771 Noel Street

Los Alamitos, CA 90720

Client ID: L1596
Report Number: N015673
Date Received: 08/18/23
Date Analyzed: 08/24/23
Date Printed: 08/24/23

Job ID/Site: 230201LA; Griffith Structures, 101 W Manchester Blvd, Inglewood, CA 90301

SGSFL Job ID: L1596

PLM Report Number: B350584

Total Samples Submitted: 7

Total Samples Analyzed: 7

Sample Preparation and Analysis:

Each sample was prepared using the gravimetric technique. A representative subsample was weighed, ashed for eight hours, and reweighed to determine the proportion of the organic component. The ashed residue was ground in concentrated hydrochloric acid, dried and reweighed to determine the acid-soluble component weight percentage. The residual material was analyzed for asbestos using polarized light microscopy. Asbestos quantitation was performed using the semi-quantitative Point Count method following the general guidelines in EPA Method 600/R-93/116. The analytical sensitivity for the method is calculated as the asbestos concentration that results from one point counted in the analysis adjusted using the residual weight of the sample. The limit of detection for this method has not been determined.

Sample ID	Lab Number	Sample Description		
3-230802-02A	51681739	Tan Mastics with Debris		
<i>Point Count Results:</i>				
Number of asbestos points counted:	3	Organic weight percentage:	47.75	
Number of non-empty points:	1000	Acid-soluble weight percentage:	0.39	
Percent asbestos in layer:	0.16	Residual weight percentage:	51.85	
Analytical sensitivity (%):	0.05			
Asbestos type(s) detected:	Chrysotile			
Comment:				
3-230802-02B	51681740	Tan Mastics with Debris		
<i>Point Count Results:</i>				
Number of asbestos points counted:	1	Organic weight percentage:	52.86	
Number of non-empty points:	1000	Acid-soluble weight percentage:	2.25	
Percent asbestos in layer:	0.05	Residual weight percentage:	44.89	
Analytical sensitivity (%):	0.04			
Asbestos type(s) detected:	Chrysotile			
Comment:				
3-230802-02C	51681741	Tan Mastics with Debris		
<i>Point Count Results:</i>				
Number of asbestos points counted:	5	Organic weight percentage:	47.77	
Number of non-empty points:	1000	Acid-soluble weight percentage:	0.26	
Percent asbestos in layer:	0.26	Residual weight percentage:	51.97	
Analytical sensitivity (%):	0.05			
Asbestos type(s) detected:	Chrysotile			
Comment:				

Bulk Asbestos Material Analysis

(EPA Method 600/R-93/116, Point Count Analysis)

Health Science Associates
Joel Berman
10771 Noel Street

Los Alamitos, CA 90720

Client ID: L1596
Report Number: N015673
Date Received: 08/18/23
Date Analyzed: 08/24/23
Date Printed: 08/24/23

Job ID/Site: 230201LA; Griffith Structures, 101 W Manchester Blvd, Inglewood, CA 90301

SGSFL Job ID: L1596

PLM Report Number: B350584

Total Samples Submitted: 7

Total Samples Analyzed: 7

Sample Preparation and Analysis:

Each sample was prepared using the gravimetric technique. A representative subsample was weighed, ashed for eight hours, and reweighed to determine the proportion of the organic component. The ashed residue was ground in concentrated hydrochloric acid, dried and reweighed to determine the acid-soluble component weight percentage. The residual material was analyzed for asbestos using polarized light microscopy. Asbestos quantitation was performed using the semi-quantitative Point Count method following the general guidelines in EPA Method 600/R-93/116. The analytical sensitivity for the method is calculated as the asbestos concentration that results from one point counted in the analysis adjusted using the residual weight of the sample. The limit of detection for this method has not been determined.

Sample ID	Lab Number	Sample Description		
3-230802-02D	51681742	Tan Mastics with Debris		
<i>Point Count Results:</i>				
Number of asbestos points counted:	3	Organic weight percentage:	47.51	
Number of non-empty points:	1000	Acid-soluble weight percentage:	15.00	
Percent asbestos in layer:	0.11	Residual weight percentage:	37.48	
Analytical sensitivity (%):	0.04			
Asbestos type(s) detected:	Chrysotile			
Comment:				
3-230802-02E	51681743	Tan Mastics with Debris		
<i>Point Count Results:</i>				
Number of asbestos points counted:	6	Organic weight percentage:	50.93	
Number of non-empty points:	1000	Acid-soluble weight percentage:	5.04	
Percent asbestos in layer:	0.26	Residual weight percentage:	44.03	
Analytical sensitivity (%):	0.04			
Asbestos type(s) detected:	Chrysotile			
Comment:				
3-230802-02F	51681744	Tan Mastics with Debris		
<i>Point Count Results:</i>				
Number of asbestos points counted:	6	Organic weight percentage:	47.50	
Number of non-empty points:	1000	Acid-soluble weight percentage:	11.89	
Percent asbestos in layer:	0.24	Residual weight percentage:	40.61	
Analytical sensitivity (%):	0.04			
Asbestos type(s) detected:	Chrysotile			
Comment:				

Bulk Asbestos Material Analysis

(EPA Method 600/R-93/116, Point Count Analysis)

Health Science Associates
Joel Berman
10771 Noel Street

Los Alamitos, CA 90720

Client ID: L1596
Report Number: N015673
Date Received: 08/18/23
Date Analyzed: 08/24/23
Date Printed: 08/24/23

Job ID/Site: 230201LA; Griffith Structures, 101 W Manchester Blvd, Inglewood, CA 90301

SGSFL Job ID: L1596

PLM Report Number: B350584

Total Samples Submitted: 7

Total Samples Analyzed: 7

Sample Preparation and Analysis:

Each sample was prepared using the gravimetric technique. A representative subsample was weighed, ashed for eight hours, and reweighed to determine the proportion of the organic component. The ashed residue was ground in concentrated hydrochloric acid, dried and reweighed to determine the acid-soluble component weight percentage. The residual material was analyzed for asbestos using polarized light microscopy. Asbestos quantitation was performed using the semi-quantitative Point Count method following the general guidelines in EPA Method 600/R-93/116. The analytical sensitivity for the method is calculated as the asbestos concentration that results from one point counted in the analysis adjusted using the residual weight of the sample. The limit of detection for this method has not been determined.

Sample ID	Lab Number	Sample Description
3-230802-02G	51681745	Tan Mastics with Debris
<i>Point Count Results:</i>		
Number of asbestos points counted:	3	Organic weight percentage: 50.30
Number of non-empty points:	1000	Acid-soluble weight percentage: 0.64
Percent asbestos in layer:	0.15	Residual weight percentage: 49.05
Analytical sensitivity (%):	0.05	
Asbestos type(s) detected:	Chrysotile	

Comment:



Tiffani Ludd, Laboratory Supervisor, Carson Laboratory

Analytical results and reports are generated by SGS Forensic Laboratories (SGSFL) at the request of and for the exclusive use of the person or entity (client) named on such report. Results, reports or copies of same will not be released by SGSFL to any third party without prior written request from client. This report applies only to the sample(s) tested. Supporting laboratory documentation is available upon request. This report must not be reproduced except in full, unless approved by SGSFL. The client is solely responsible for the use and interpretation of test results and reports requested from SGSFL. This report must not be used by the client to claim product endorsement by NVLAP or any other agency of the U.S. Government. SGSFL is not able to assess the degree of hazard resulting from materials analyzed. SGS Forensic Laboratories reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified. All samples were received in acceptable condition unless otherwise noted.



ASBESTOS BULK SAMPLE DATA SHEET		FLOOR (circle one)	LD	1	2	(3)	PENTHOUSE	ROOF
TAT 5 day	Project Manager:	Joel Berman		Project #:			230201LA	
	Client:	Griffith Structures		Industrial Hygienist:			Devin Berman	
	Project Location:	101 W Manchester Blvd Inglewood, CA 90301		Rene Medina			Rodica Dullabaun Anahi Rizo-Zhang	
Comments:								

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
3-230802-01A	Daywall, mud & tape	3rd floor Entrance to Admin. Offices	near Conference Room 3A at wall base, near door	(F) TSI M (SM) NF SC	D SD (G)	10,000 ft ²	
01B		Main Library area	At West stairwell	(F) TSI M (SM) NF SC	D SD (G)		
01C		Main Library area	behind the East stairwell	(F) TSI M (SM) NF SC	D SD (G)		
02A	Carpet Glue	Main Library	SW area	(F) TSI M (SM) (NF) SC	D SD (G)	20,000 ft ²	
02B			S end	(F) TSI M (SM) (NF) SC	D SD (G)		
02C			SE corner	(F) TSI M (SM) (NF) SC	D SD (G)		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Relinquished by: Devin D. Berman	Date: 6/4/23	Time: 1020	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

WARNING CONTAINS 8-4-23 10:00am 20

E-mail results to: labresults@healthscience.comdsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET

FLOOR (circle one) LD 1 2 3 PENTHOUSE ROOF

TAT <i>5day</i>	Project Manager:	Joel Berman		Project #:	230201LA		Date:	8/ /2023	
	Client:	Griffith Structures		Industrial Hygienist:	Devin Berman		Rodica Dullabaun		
	Project Location:	101 W Manchester Blvd		Rene Medina		Anahi Rizo-Zhang			
	Inglewood, CA 90301		Comments:						

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
3-230802-02D	Carpet Glue	3rd floor Main Library	Central area	F TSI NF M SC (SM)	D SD (G)	20,000 ft ²	
02E			NE corner	F TSI NF M SC (SM)	D SD (G)		
02F		N Office area	N end floor	F TSI NF M SC (SM)	D SD (G)		
02G		Conference Room	NE corner	F TSI NF M SC (SM)	D SD (G)		
03A	Stair Tread	East Stairwell		F TSI NF M SC (SM)	D SD (G)	4000 ft ²	
03B		West Stairwell		F TSI NF M SC (SM)	D SD (G)		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Jarmin Contreras 8-4-23 10:00am

Relinquished by: <i>Devin Berman</i>	Date: <i>8/4/23</i>	Time: <i>1020</i>	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

E-mail results to: labresults@healthscience.comdsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET		FLOOR (circle one)		LD	1	2	3	PENTHOUSE	ROOF
TAT 5 day	Project Manager:	Joel Berman			Project #:			230201LA	
	Client:	Griffith Structures			Industrial Hygienist:			Devin Berman	
	Project Location:	101 W Manchester Blvd Inglewood, CA 90301			Rene Medina			Anahi Rizo-Zhang	
					Date: 8/2 /2023				
					Rodica Dullabaun				
					Comments:				

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
3-230802-04A	Blue Vinyl base core	3rd floor Main library Room	at E stairs	F TSI (M) SM SD (NF) SC (G)	D	21000 LF	
04B			NE corner	F TSI (M) SM SD (NF) SC (G)	D		
04C			N wall, w of conference 3A	F TSI (M) SM SD (NF) SC (G)	D		
05A	12" x 12" Black flooring	Staff stairwell	In front of water fountain	F TSI (M) SM SD (NF) SC (G)	D	32 DS 8/2/2023	
05B				F TSI (M) SM SD (NF) SC (G)	D		
05C				F TSI (M) SM SD (NF) SC (G)	D		
05D		On elevator		F TSI (M) SM SD (NF) SC (G)	D		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Relinquished by: Devin S. Berman	Date: 8/4/23	Time: 1020	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

Veronica Contreras 8/4/23 11:00am



ASBESTOS BULK SAMPLE DATA SHEET

FLOOR (circle one)

LD 1 2 3

PENTHOUSE

ROOF

TAT 5 day	Project Manager: Joel Berman		Project #: 230201LA		Date: 8/4/2023
	Client: Griffith Structures		Industrial Hygienist: Devin Berman		Rodica Dullabaun
	Project Location: 101 W Manchester Blvd		Rene Medina		Anahi Rizo-Zhang
	Inglewood, CA 90301		Comments:		

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
3-230804-06A	24"x24" ceiling tile	3 rd floor Conference Room	SE corner	F TSI NF M SC	D SD G	<1000 ft ²	
06B			N side Center	F TSI NF M SC	D SD G		
06C			SW corner	F TSI NF M SC	D SD G		
07A	24"x24" ceiling tile	Admin Area	SW corner	F TSI NF M SC	D SD G	<1000 ft ²	
07B			N side, Center	F TSI NF M SC	D SD G		
07C			W side	F TSI NF M SC	D SD G		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Gulmin Contreras 8-4-23 10:00 am

Relinquished by: Devin Berman	Date: 8/4/23	Time: 1020	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:



10771 Noel Street • Los Alamitos, CA 90720

Office: (714) 220-3922 • Fax: (714) 220-2081

Page 5 of 5E-mail results to: labresults@healthscience.comdsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET			FLOOR (circle one)	LD	1	2	3	PENTHOUSE	ROOF
TAT <i>5 day</i>	Project Manager:	Joel Berman		Project #:				230201LA	
	Client:	Griffith Structures		Industrial Hygienist:				Devin Berman	
	Project Location:	101 W Manchester Blvd Inglewood, CA 90301		Rene Medina				Anahi Rizo-Zhang	
Comments:									

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
3-230804-08A <i>08B 8/12/23</i>	Concealed Spline Ceiling system tiles	3 rd Main library floor	E side	F TSI M SC	D SD	5100 ft ²	
			SE corner	F TSI M SC	D SD		
				F TSI M SC	D SD		
				F TSI M SC	D SD		
				F TSI M SC	D SD		
				F TSI M SC	D SD		
				F TSI M SC	D SD		

Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

Quantity: ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Relinquished by: <i>Devin Berman</i>	Date: <i>8/14/23</i>	Time: <i>1020</i>	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:
Relinquished by:	Date:	Time:	Received by:	Date:	Time:

Devin Berman *8-14-23 10:04 am*



10771 Noel Street • Los Alamitos, CA 90720

Office: (714) 220-3922 • Fax: (714) 220-2081

Page 2 of 3E-mail results to: labresults@healthscience.comdsberman@heajanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET

FLOOR (circle one)

LD 1 2 3

PENTHOUSE

ROOF

Project #: 230201LA

Date: 8/3/2023

TAT

Project Manager: Joel Berman

Industrial Hygienist: Devin Berman

Rodica Dullabaun

Client: Griffith Structures

Rene Medina

Anahi Rizo-Zhang

Project Location: 101 W Manchester Blvd

Inglewood, CA 90301

Comments:

Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #
P-230803-03A	TSI wrap	Penthouse off piping	Center of Room	F TSI M SM SD	D	3002F	
03B				NF SC TSI M SM SD	G		
03C				F TSI M SM SD	D		
03D	TSI hard pack covering			NF SC TSI M SM SD	G	30LF	
04B				F TSI M SM SD	D		
04C				NF SC TSI M SM SD	G		

Type:

Condition:

Labeling:

Quantity:

F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings

D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition

W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing

ft² = square feet; lft = linear feet

Special Instructions to Laboratory:

Analyze per EPA 600 Method - PLM

Sergio Contreras 8-423 10:00 am DCU

Relinquished by:

Date:

Time: 1015

Received by:

Date:

Time:

Date:

Time:

Received by:

Date:

Time:

Date:

Time:

Received by:

Date:

Time:

DS = ~~Deep~~ Deep Dust Vibration Cloth




10771 Noel Street • Los Alamitos, CA 90720

Office: (714) 220-3922 • Fax: (714) 220-2081

Page 3 of 3E-mail results to: labresults@healthscience.comdsberman@heerjanmariebailey@yahoo.com

ASBESTOS BULK SAMPLE DATA SHEET				FLOOR (circle one)	LD	1	2	3	PENTHOUSE	ROOF
TAT <i>5day</i>	Project Manager: <u>Joel Berman</u>		Project #: <u>230201LA</u>		Date: <u>8/3/2023</u>					
	Client: <u>Griffith Structures</u>		Industrial Hygienist: <u>Devin Berman</u>		<u>Rodica Dullabaun</u>					
	Project Location: <u>101 W Manchester Blvd</u>		<u>Rene Medina</u>		<u>Anahi Rizo-Zhang</u>					
	<u>Inglewood, CA 90301</u>		Comments:							
Sample #	Material	Location	Description	Type (circle)	Condition	Quantity (ft ² /lft)	Photograph #			
P-230803-05A	Vibration Dampening Cloth	Penthouse	N area	F TSI M SC NF	D SD G	3-4 Total				
05B			W area	F TSI M SC NF	D SD G					
05C			S area	F TSI M SC NF	D SD G					
				F TSI M SC NF	D SD G					
				F TSI M SC NF	D SD G					
				F TSI M SC NF	D SD G					
				F TSI M SC NF	D SD G					
Type: F = Friable; NF = Non-friable; TSI = Thermal System Insulation; M = Miscellaneous Material; SM = Surface Material; SC = Spray-on Coatings										
Condition: D = Damaged (< 10% surface damage); SD = Significantly Damaged (> 10% surface damage); G = Good Condition										
Labeling: W = Wall; F = Floor; T = TSI; C = Ceiling; O = Miscellaneous; R = Roofing										
Quantity: ft ² = square feet; lft = linear feet										
Special Instructions to Laboratory: <u>WARNING CONTAMINATED 8/4/23 10:00am PO</u>										
Analyze per EPA 600 Method - PLM										
Relinquished by: <u>Devin Berman</u>		Date: <u>8/4/23</u>	Time: <u>1015</u>	Received by:	Date:	Time:				
Relinquished by:		Date:	Time:	Received by:	Date:	Time:				
Relinquished by:		Date:	Time:	Received by:	Date:	Time:				

Appendix B - Figures




Originator: D. Berman

Date(s): August 8, 2023

Griffith Structures
101 W. Manchester Blvd.,
Inglewood, CA 90301

Bulk Asbestos Sample Locations

Health
Science
Associates




Originator: D. Berman

Date(s): August 8, 2023

Griffith Structures
101 W. Manchester Blvd.,
Inglewood, CA 90301

Bulk Asbestos Sample Locations

Health
Science
Associates




Originator: D. Berman

Date(s): August 8, 2023

Griffith Structures
101 W. Manchester Blvd.,
Inglewood, CA 90301

Bulk Asbestos Sample Locations

Health
Science
Associates




Originator: D. Berman

Date(s): August 8, 2023

Griffith Structures
101 W. Manchester Blvd.,
Inglewood, CA 90301

Bulk Asbestos Sample Locations

Health
Science
Associates



Originator: D. Berman

Date(s): August 8, 2023

Griffith Structures
101 W. Manchester Blvd.,
Inglewood, CA 90301**Bulk Asbestos Sample Locations**
Mastic Asbestos Sample Locations**Health
Science
Associates**


Appendix C - Photo Exhibit

Inglewood Library
101 Manchester Blvd.
Inglewood, CA 90301
Asbestos
August 2, 3, and 4, 2023
HSA Project Number
230201LA





01. Miscellaneous Asbestos Sample 06A



02. Miscellaneous Asbestos Sample 06A



03. Miscellaneous Asbestos Sample 06B



04. Miscellaneous Asbestos Sample 06B



05. Miscellaneous Asbestos Sample 06C



06. Miscellaneous Asbestos Sample 06C



07. Miscellaneous Asbestos Sample 06D



08. Miscellaneous Asbestos Sample 06D



09. Miscellaneous Asbestos Sample 06E



10. Miscellaneous Asbestos Sample 06E



11. 3rd Floor Asbestos Sample 08A



12. 3rd Floor Asbestos Sample 08A



13. 3rd Floor Asbestos Sample 08B




14. 3rd Floor Asbestos Sample 08B



15. 3rd Floor Asbestos Sample 07A



16. 3rd Floor Asbestos Sample 07B



17. 3rd Floor Asbestos Sample 07C



18. 3rd Floor Asbestos Sample 06A




19. 3rd Floor Asbestos Sample 06B




20. 3rd Floor Asbestos Sample 06C




21. 2nd Floor Asbestos Sample 06A




22. 2nd Floor Asbestos Sample 06B




23. 1st Floor Asbestos Sample 08B



24. 1st Floor Asbestos Sample 14A




25. 1st Floor Asbestos Sample 14B




26. 1st Floor Asbestos Sample 14C



27. Loading Dock Asbestos Sample 06A




28. Loading Dock Asbestos Sample 06B



29. Loading Dock Asbestos Sample 06C

Inglewood Library
101 Manchester Blvd.
Inglewood, CA 90301
Paint Chips
August 2, 3, and 4, 2023
HSA Project Number
230201LA







01. Paint Chip 01




02. Paint Chip 01




03. Paint Chip 02



04. Paint Chip 02



05. Paint Chip 03



06. Paint Chip 03



07. Paint Chip 04



08. Paint Chip 04

Inglewood Library
101 Manchester Blvd.
Inglewood, CA 90301
August 2, 2023
HSA Project Number 230201LA






01. 1st Floor Asbestos Sample 01A



02. 1st Floor Asbestos Sample 01A



03. 1st Floor Asbestos Sample 05A



04. 1st Floor Asbestos Sample 05A




05. 1st Floor Asbestos Sample 05B



06. 1st Floor Asbestos Sample 05B




07. 1st Floor Asbestos Sample 05C




08. 1st Floor Asbestos Samples 01C and 10A



09. 1st Floor Asbestos Samples 01C and 10A



10. 1st Floor Asbestos Sample 10B




11. 1st Floor Asbestos Sample 10B



12. 1st Floor Asbestos Sample 10C




13. 1st Floor Asbestos Sample 10C



14. 1st Floor Asbestos Sample 05C



15. 1st Floor Asbestos Sample 05C




16. 1st Floor Asbestos Sample 02A



17. 1st Floor Asbestos Sample 02A



18. 1st Floor Asbestos Sample 02B



20. 1st Floor Asbestos Sample 02B



21. 1st Floor Asbestos Sample 02C



22. 1st Floor Asbestos Sample 02C



23. Emergency Evacuation Plan - 3rd Floor



24. 3rd Floor Asbestos Sample 02A



25. 3rd Floor Asbestos Sample 02A



26. 3rd Floor Asbestos Sample 02B



27. 3rd Floor Asbestos Sample 02B



28. 3rd Floor Asbestos Sample 02C



29. 3rd Floor Asbestos Sample 02C



30. 3rd Floor Asbestos Sample 02D




31. 3rd Floor Asbestos Sample 02D



32. 3rd Floor Asbestos Sample 02E




33. 3rd Floor Asbestos Sample 02F




34. 3rd Floor Asbestos Sample 02G



35. 3rd Floor Asbestos Sample 02G



36. 3rd Floor Asbestos Sample 01A




37. 3rd Floor Asbestos Sample 01A




38. 3rd Floor Asbestos Sample 01B



39. 3rd Floor Asbestos Sample 01B



40. 3rd Floor Asbestos Sample 01C



41. 3rd Floor Asbestos Sample 01C



42. Exterior of building, South wall



43. Exterior of building, South wall

Inglewood Library
101 Manchester Blvd.
Inglewood, CA 90301
August 3, 2023
HSA Project Number 230201LA






01. 2nd Floor Asbestos Sample 02A



02. 2nd Floor Asbestos Sample 02A




03. 2nd Floor Asbestos Sample 02B



04. 2nd Floor Asbestos Sample 02B



05. 2nd Floor Asbestos Sample 02C



06. 2nd Floor Asbestos Sample 02C



07. 2nd Floor Asbestos Sample 02D




08. 2nd Floor Asbestos Sample 02D



09. 2nd Floor Asbestos Sample 02E




10. 2nd Floor Asbestos Sample 02E



11. 2nd Floor Asbestos Sample 02F



12. 2nd Floor Asbestos Sample 02F



13. 2nd Floor Asbestos Sample 02G



14. 2nd Floor Asbestos Sample 02G



15. Loading Dock Asbestos Sample 02A



16. Loading Dock Asbestos Sample 02A



17. Loading Dock Asbestos Sample 02B



18. Loading Dock Asbestos Sample 02B




19. Loading Dock Asbestos Sample 11A



20. Loading Dock Asbestos Sample 11A



21. Loading Dock Asbestos Sample 11B



22. Loading Dock Asbestos Sample 11B




23. Loading Dock Asbestos Sample 02C



24. Loading Dock Asbestos Sample 02C




25. Loading Dock Asbestos Sample 02D



26. Loading Dock Asbestos Sample 02D




27. Loading Dock Asbestos Sample 02E




28. Loading Dock Asbestos Sample 02E



29. Loading Dock Asbestos Sample 11C



30. Miscellaneous Asbestos Sample 03A




31. Miscellaneous Asbestos Sample 03B



32. Miscellaneous Asbestos Sample 03C



33. Miscellaneous Asbestos Sample 02A




34. Miscellaneous Asbestos Sample 02B



35. Miscellaneous Asbestos Sample 02C




36. Miscellaneous Asbestos Sample 02D




37. Miscellaneous Asbestos Sample 02E



38. Exterior Photo




39. Miscellaneous Asbestos Sample 03D



40. Miscellaneous Asbestos Sample 03D




41. Miscellaneous Asbestos Sample 03E



42. Miscellaneous Asbestos Sample 03E

Inglewood Library
101 Manchester Blvd.
Inglewood, CA 90301
1st Floor
August 2, 2023
HSA Project Number 230201LA






03. 1st Floor, Asbestos Sample 07A



04. 1st Floor, Asbestos Sample 07B



05. 1st Floor, Asbestos Samples 04A and 07C



06. 1st Floor, Asbestos Samples 04A, 07C



07. 1st Floor, Asbestos Sample 06A



08. 1st Floor, Asbestos Sample 06A



09. 1st Floor, Asbestos Samples 06B and 04B



10. 1st Floor, Asbestos Samples 06B and 04B



11. 1st Floor, Asbestos Sample 06C



12. 1st Floor, Asbestos Sample 06C



13. 1st Floor, Asbestos Sample 09A



14. 1st Floor, Asbestos Sample 09A




15. 1st Floor, Asbestos Sample 09A



16. 1st Floor, Asbestos Sample 09A



17. 1st Floor, Asbestos Sample 09C



18. 1st Floor, Asbestos Sample 09C



19. 1st Floor, Asbestos Sample 04C



20. 1st Floor, Asbestos Sample 10A



21. 1st Floor, Asbestos Sample 10A




22. 1st Floor, Asbestos Sample 10B



23. 1st Floor, Asbestos Sample 10C



24. 1st Floor, Asbestos Samples 12A, 12B and 12C



25. 1st Floor, Asbestos Samples 12A, 12B, and 12C



26. Mat over where samples 12 were taken



27. 1st Floor, Asbestos Sample 03A



28. 1st Floor, Asbestos Sample 02D




29. 1st Floor, Asbestos Sample 02F



30. 1st Floor, Asbestos Sample 02G

Inglewood Library
101 Manchester Blvd.
Inglewood, CA 90301
August 2, 2023
3rd Floor
HSA Project Number 230201LA






31. 3rd Floor, Asbestos Sample 04C




32. 3rd Floor, Asbestos Sample 04C



33. 3rd Floor, Asbestos Sample 04B




34. 3rd Floor, Asbestos Sample 04B



35. 3rd Floor, Asbestos Sample 04A



36. 3rd Floor, Asbestos Sample 04A



37. 3rd Floor, Asbestos Sample 03B



38. 3rd Floor, Asbestos Sample 03A



39. 3rd Floor, Asbestos Samples 05A, 05B and 05C



40. 3rd Floor, Asbestos Sample 05D

Inglewood Library
101 Manchester Blvd.
Inglewood, CA 90301
August 2, 2023
Miscellaneous
HSA Project Number 230201LA






41. Miscellaneous Asbestos Sample 01A



42. Miscellaneous Asbestos Sample 01B



43. Miscellaneous Asbestos Sample 01C



44. Miscellaneous Asbestos Sample 08A

Appendix D - Licenses

State of California
Division of Occupational Safety and Health
Certified Asbestos Consultant

Devin Shana Berman

Name



Certification No. **15-5418**

Expires on **05/12/24**

This certification was issued by the Division of Occupational Safety and Health as authorized by Sections 7180 et seq. of the Business and Professions Code.

State of California
Division of Occupational Safety and Health
Certified Asbestos Consultant

Joel I Berman

Name



Certification No. **92-0838**

Expires on **01/13/24**

This certification was issued by the Division of Occupational Safety and Health as authorized by Sections 7180 et seq. of the Business and Professions Code.

State of California
Division of Occupational Safety and Health
Certified Asbestos Consultant

Rodica Dullabaun

Name



Certification No. **11-4716**

Expires on **04/20/24**

This certification was issued by the Division of Occupational Safety and Health as authorized by Sections 7180 et seq. of the Business and Professions Code.



STATE OF CALIFORNIA
DEPARTMENT OF PUBLIC HEALTH



LEAD-RELATED CONSTRUCTION CERTIFICATE

INDIVIDUAL:



Devin Berman

CERTIFICATE TYPE:

Lead Inspector/Assessor

NUMBER:

LRC-00002357

EXPIRATION DATE:

10/4/2023

Disclaimer: This document alone should not be relied upon to confirm certification status. Compare the individual's photo and name to another valid form of government issued photo identification. Verify the individual's certification status by searching for Lead-Related Construction Professionals at www.cdph.ca.gov/programs/clppb or calling (800) 597-LEAD



STATE OF CALIFORNIA
DEPARTMENT OF PUBLIC HEALTH



LEAD-RELATED CONSTRUCTION CERTIFICATE

INDIVIDUAL:



Rene Medina

CERTIFICATE TYPE:

Lead Sampling Technician

NUMBER:

LRC-00002314

EXPIRATION DATE:

2/17/2024

Disclaimer: This document alone should not be relied upon to confirm certification status. Compare the individual's photo and name to another valid form of government issued photo identification. Verify the individual's certification status by searching for Lead-Related Construction Professionals at www.cdph.ca.gov/programs/clppb or calling (800) 597-LEAD



STATE OF CALIFORNIA
DEPARTMENT OF PUBLIC HEALTH



LEAD-RELATED CONSTRUCTION CERTIFICATE

INDIVIDUAL:



Joel Berman

CERTIFICATE TYPE:

Lead Inspector/Assessor

Lead Project Monitor

NUMBER:

LRC-00003608

LRC-00003607

EXPIRATION DATE:

10/22/2023

10/22/2023

Disclaimer: This document alone should not be relied upon to confirm certification status. Compare the individual's photo and name to another valid form of government issued photo identification. Verify the individual's certification status by searching for Lead-Related Construction Professionals at www.cdph.ca.gov/programs/clppb or calling (800) 597-LEAD

Appendix E - Notifications

LEAD HAZARD EVALUATION REPORT**Section 1 — Date of Lead Hazard Evaluation** August 2, 3, and 4, 2023**Section 2 — Type of Lead Hazard Evaluation (Check one box only)**☒ Lead Inspection ☐ Risk assessment ☐ Clearance Inspection ☐ Other (specify) _____**Section 3 — Structure Where Lead Hazard Evaluation Was Conducted**

Address [number, street, apartment (if applicable)]		City	County	Zip Code
101 Manchester Blvd.		Inglewood	CA	90301
Construction date (year) of structure	Type of structure		Children living in structure?	
1973	<input type="checkbox"/> Multi-unit building <input type="checkbox"/> School or daycare <input type="checkbox"/> Single family dwelling <input checked="" type="checkbox"/> Other Public Library		<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Don't Know	


Section 4 — Owner of Structure (if business/agency, list contact person)

Name		Telephone number	
City of Inglewood		310-412-5111	
Address [number, street, apartment (if applicable)]		City	State
One Manchester Blvd.		Inglewood	CA
			Zip Code
			90301

Section 5 — Results of Lead Hazard Evaluation (check all that apply)

☐ No lead-based paint detected ☒ Intact lead-based paint detected ☐ Deteriorated lead-based paint detected
☐ No lead hazards detected ☐ Lead-contaminated dust found ☐ Lead-contaminated soil found ☒ Other Lead in ceramic tiles

Section 6 — Individual Conducting Lead Hazard Evaluation

Name		Telephone number	
Devin Berman		714-220-3922	
Address [number, street, apartment (if applicable)]		City	State
10771 Noel Street		Los Alamitos	CA
			Zip Code
			90720
CDPH certification number	Signature		Date
00002357			9/12/23

Name and CDPH certification number of any other individuals conducting sampling or testing (if applicable)

Rodica Dullabaun, LRC 00009201 and Rene Medina, LRC 00002314

Section 7 — Attachments

- A. A foundation diagram or sketch of the structure indicating the specific locations of each lead hazard or presence of lead-based paint;
B. Each testing method, device, and sampling procedure used;
C. All data collected, including quality control data, laboratory results, including laboratory name, address, and phone number.

First copy and attachments retained by inspector

Second copy and attachments retained by owner

Third copy only (no attachments) mailed or faxed to:

California Department of Public Health
Childhood Lead Poisoning Prevention Branch Reports
850 Marina Bay Parkway, Building P, Third Floor
Richmond, CA 94804-6403
Fax: (510) 620-5656