



STATEMENT OF WORK

Permanent Fire Station 46 Construction Staking

1. Project Control and Construction Limits(T&M)

Hunsaker will provide preliminary field survey for the project. The work includes the following:

- a. Review control in the area and establish control at and around the site.
- b. Provide stakes for all the demo and or perimeter of the project.
- c. A total of 2 site visits for a 2-man crew is included.

2. Rough Grade Staking (T&M)

Hunsaker will provide stakes for the proposed rough grades for pads, parking, and driveways.

- a. A total of 3 site visits for a 2-man crew is included.

3. Rough Grade Pad and Form Certifications (T&M)

After the pads are graded, H&A will as-built pads and bottom of excavations for structures. If needed, Hunsaker will survey and provide form certifications for structures as requested.

- a. A total of 5 site visits for a 2-man crew is included.

4. Wet Utilities Staking (T&M)

Hunsaker will provide stakes for the proposed wet utilities as needed to construct the improvements. Stakes will be provided for:

- a. Sewer mains, cleanouts, manholes, grade breaks, and connection points.
- b. The proposed fire, irrigation and domestic water services.
- c. A total of 6 site visits for a 2-man crew is included.

5. Storm Drain/Biofiltration Staking (T&M)

Hunsaker will provide stakes for the proposed storm drain lines and water quality treatment. Stakes will be provided at cleanouts, inlets, grades breaks, and other drainage structures.

- a. A total of 7 site visits for a 2-man crew is included.



STATEMENT OF WORK

Permanent Fire Station 46 Construction Staking

6. Building and Structure Staking (T&M)

Hunsaker will set 1 set of stakes for the onsite buildings and structures depicted on the Precise Grading Plan including:

- a. Foundation gridlines on first floor of the Fire Station 46 building.
- b. Trash Enclosure, Generator, Fuel and Hose room walls.
- c. Reserve apparatus structure
- d. A total of 8 site visits for a 2-man crew is included.

7. Fine Grading Staking (T&M)

Hunsaker will provide stakes for curbs, sidewalks, pedestrian ramps, building pads, swales, and driveway stakes.

- a. A total of 8 site visits for a 2-man crew is included.

8. Dry Utility and Site Lighting Staking(T&M)

Hunsaker will provide stakes for Dry utility Connections, Transformer Pads, electrical, gas lines, and onsite lighting system.

- a. A total of 6 site visits for a 2-man crew is included.

9. Miscellaneous Wall and Fence Staking(T&M)

Hunsaker will provide 1 set of stakes for miscellaneous walls and fences.

- a. A total of 4 site visits for a 2-man crew is included.

10. As-built and Final Grading Certification Survey (T&M)

After the project is completed, H&A will field as-built critical facilities and final site grading elevations for all As-built Plans and Certifications prepared in Item 2 above.

- a. A total of 4 site visits for a 2-man crew is included.