



VENTURA UNIFIED SCHOOL DISTRICT

VETURA HIGH SCHOOL STADIUM UPGRADES AND SITE IMPROVEMENTS

BID # E14-25

09/18/2026

ADDENDUM #01

NOTICE TO BIDDERS:

The following revisions and/or clarifications shall be made to the bidding requirements and contract documents. Revise and amend the documents for the above-named project in accordance with this addendum. The bid shall reflect these addendum changes and each bidder shall refer in their bid to this addendum.

All bidding requirements and contract documents shall apply to this addendum as originally indicated in the applicable portions of the contract documents, unless otherwise modified by this addendum.

Contractors shall acknowledge this addendum at the space provided on the Bid Proposal.

REVISIONS, CLARIFICATIONS, & RESPONSES TO PRE-BID RFI'S:

1. Please see attached sheet C2.03 for incorporation into the bid set of documents.

REVISIONS TO THE PLANS: C2.03

REVISIONS TO THE SPECIFICATIONS: Not Applicable

END OF ADDENDUM #01

Addendum: 1 Page

ENCLOSURES: 1 Page

Total Number of Pages: 2

SYMBOL	DESCRIPTION
	GRIND 2" MIN AND OVERLAY EXISTING PAVEMENT. LIMITS SHOWN ARE APPROXIMATE. OVERLAY SLOPES SHOULD BE IN ACCORD WITH ACCESSIBILITY REQUIREMENTS.
	PEDESTRIAN CONCRETE PAVEMENT 5" PCC OVER 6" AB PER GEOTECHNICAL ENGINEER'S RECOMMENDATION PAGE 3083.1. SEE ALSO DETAIL 12 SHEET C7.01
	DRIVE AISLE AC PAVEMENT 2" AC OVER 4" AB PER GEOTECHNICAL ENGINEER'S RECOMMENDATION. (TRAFFIC INDEX = 4.0)
	APPROXIMATE LIMIT OF WORK
	GRADE BREAK
	SAWCUT (E) PAVEMENT AS NEEDED. SEE DEMOLITION PLAN
	FLOWLINE
	OVERLAND RELEASE

KEY NOTE	DESCRIPTION
01	CONSTRUCT VERTICAL CURB PER DETAIL 03 SHEET C7.01.
02	CONSTRUCT FLUSH CURB PER DETAIL 07 SHEET C7.01.
03	JOIN EXISTING RETAINING WALL AND MATCH EXISTING GRADE.
04	CONSTRUCT RETAINING WALL PER STRUCTURAL PLANS.
05	CONSTRUCT RETAINING WALL WITH FENCE POSTS PER LANDSCAPE MATERIALS PLAN SHEET L1.01 AND L1.02.
06	SYNTHETIC TURF SYSTEM AT FOOTBALL FIELD PER LANDSCAPE MATERIALS PLAN SHEET L1.01 AND L1.02.
07	GRADE BOTTOM OF BASE (BOB) TO ENSURE DRAINAGE TOWARDS SUBDRAIN. SEE STORM DRAIN PLANS.
08	RUBBERIZED TRACK SURFACING PER LANDSCAPE MATERIALS PLAN SHEET L1.01 AND L1.02.
09	CONCRETE RADIUS MONUMENT PER DETAIL 18 SHEET L5.05.
10	REMOVE AND REINSTALL FENCE IN PLACE TO INSTALL STORM DRAIN PIPE.
11	MATCH (E) GRADE. PROVIDE 1% MINIMUM GRADE FOR DRAINAGE OUT OF THE WHEELCHAIR SEATING AREA.
12	CONSTRUCT CONCRETE RETAINING WALL WITH FENCING PER LANDSCAPE DETAIL 03 SHEET L5.02.
13	CONSTRUCT WALL PER LANDSCAPE SHEET L3.01.
14	CONSTRUCT STEM WALL PER STRUCTURAL DETAIL 08 SHEET S6.02.
15	CONSTRUCT GUARDRAIL ATTACHMENT TO EXISTING CONCRETE RETAINING WALL PER LANDSCAPE DETAIL 15 SHEET L5.02.

1. SEE LANDSCAPE PLANS FOR PAVERS, LOCATION AND TYPE OF CONCRETE WALKS AND HARDSCAPE INCLUDING DETAILS FOR CONCRETE FINISHES, CONTROL JOINTS AND EXPANSION JOINTS.
2. VERIFY ALL VEHICULAR AND NON-VEHICULAR LIMITS WITH LANDSCAPE PLANS.
3. RUNNING TRACK PAVING SHALL BE INSTALLED SO THAT THE TRACK RUBBERIZED SURFACING SHALL BE FLUSH AND SMOOTH PER SPECIFICATIONS. RUBBERIZED SURFACING CMAS BY OWNER.

THIS HORIZONTAL CONTROL PLAN ESTABLISHES THE FOLLOWING TO BE USED AS BASE CONTROL FOR CONSTRUCTION STAKING.

1. PRIOR TO STAKING ANY FIELDGAL OR FOULPOLE, SURVEYOR SHALL VERIFY THAT THE COORDINATES SHOWN ON THIS PLAN MATCHES THE SPORTFIELD DIMENSIONS AND PRODUCT SPECIFICATIONS.
2. IF ANY DISCREPANCIES ARE FOUND DURING CONSTRUCTION STAKING NOTIFY CIVIL ENGINEER IMMEDIATELY.
3. SEE LANDSCAPE PLANS FOR DETAILED HARDSCAPE DIMENSIONS.
4. SEE LANDSCAPE PLANS FOR LOCATION AND TYPE OF CONCRETE WALKS AND HARDSCAPE INCLUDING DETAILS FOR CONCRETE FINISHES, CONTROL JOINTS AND EXPANSION JOINTS.

2 NORTH CATALINA STREET
VENTURA, CA 93001

Developed for

